

**City of Nashua, New Hampshire
Division of Public Works**

**CDBG Manchester St/Concord St
Crosswalks
IFB0851-081414**

**French Street at Manchester Street, Mt. Pleasant Street at
Manchester Street, Orange Street at Concord Street and
Laton Street at Concord Street**

**Construction Specifications
and
Contract Documents**



Prepared By:

**Division of Public Works
9 Riverside Street
Nashua, NH 03062
(603) 589-3120
Fax: (603) 589-3169**

July 2014

TABLE OF CONTENTS

DIVISION

1.	INVITATION FOR BID
2.	INSTRUCTIONS TO BIDDERS
3.	BID FORM, BID BOND AND CONTRACTOR'S QUALIFICATIONS
4.	PERFORMANCE AND PAYMENT BONDS
5.	AGREEMENT
6.	GENERAL CONDITIONS
7.	SUPPLEMENTARY CONDITIONS.....
8.	SPECIAL PROVISIONS
	A. Federal Labor Standards Provisions
	B. Prevailing Wage Rate – Hillsborough County (Highway)
	C. U.S. Dept of Labor Form WH-247
9.	EXHIBITS
	A. Notice to Proceed
	B. Application for Payment
	C. Change Order
	D. Certificate of Substantial Completion
	E. Affidavit of Payment
10.	CONSTRUCTION SPECIFICATIONS

DIVISION 1
INVITATION FOR BID



City of Nashua

Central Purchasing

229 Main Street

Nashua NH 03060

603-589-3330 Fax: 603-589-3344

July 24, 2014

Invitation for Bids

CDBG Manchester St/Concord St Crosswalks IFB0851-081414

The City of Nashua, Division of Public Works, is seeking bids for the CDBG Manchester St/Concord St Crosswalks project. The scheduled work for this project involves the installation of two (one on Manchester Street and one on Concord Street) pedestrian push button activated RRFB (rectangular rapid flashing beacon) systems and associated intersection improvements of French Street at Manchester Street, Mt. Pleasant Street at Manchester Street, Orange Street at Concord Street and Laton Street at Concord Street. Work includes excavation, saw cutting, milling, pavement restoration, granite curbing, concrete sidewalk, detectable warning panels, minor drainage modifications, enhanced pavement markings and signage. This is a project funded by a Community Development Block Grant and will follow all required rules for wages and payroll as noted in the contract documents.

INSTRUCTION TO BIDDERS:

Bids must be submitted on the Bid Schedule in its entirety, **in duplicate (one (1) original and one (1) copy**, in a sealed envelope plainly marked "**CDBG Manchester St/Concord St Crosswalks**" and must be received at the City Purchasing Department, Lower Level, 229 Main St, City Hall, Nashua, NH 03060 prior to **3:00 pm, Thursday, August 14, 2014**. Postmarks or other timestamps will not be accepted in lieu of actual delivery. The firm can use whatever delivery mechanism it chooses as long as it remains clear that the firm is responsible for submissions prior to the date and time. Detailed "Instructions to Bidders" may be found in Division 1 of the contract document.

Further details, including the Contract Document are available, beginning, Tuesday, July 29, 2014, at 12 NOON, on the City's web site, www.nashuanh.gov under Citizens Favorites, Current Bid Opportunities, document **IFB0851-081414**. Bids will be opened and read at that time. Results of the bid opening will be posted on our website, under Bid Results, within twenty-four (24) hours of the opening.

A mandatory pre-bid conference will be held at **8:30AM on Thursday, August 7, 2014**, in the Conference Room of the City of Nashua Division of Public Works, 9 Riverside Street, Nashua, NH 03062 followed by a site visit, if requested. **You or your representatives are required to attend this meeting if you intend to submit a bid.**

No bid documents are available at the Central Purchasing Offices.

The estimated project timeline is as follows:

Item	Date	Time/Location
Mandatory Pre-bid Conference	Thursday, August 7, 2014	8:30AM DPW Admin/Engineering 9 Riverside Street Nashua NH 03062
Deadline for Questions	Friday, August 8, 2014	5:00 PM
Answers/Clarifications posted	Monday, August 11, 2014	5:00 PM
Bid Submittal Date	Thursday, August 14, 2014	3:00 PM City Purchasing Office 229 Main St Nashua NH 03060

Vendors are encouraged to submit questions via email; however, the City assumes no liability for assuring accurate/complete email transmission/receipt and is not responsible to acknowledge receipt. **Inquiries must be submitted in writing**, citing the IFB title, IFB number, Page, Section, and received **no later than Friday, August 8, 2014 at 5:00 PM to:**

Timothy Watson, PE,
Senior Staff Engineer
watsont@nashuanh.gov

The City will consider all timely-received questions and requests for change and, if reasonable and appropriate, will issue an addendum to clarify or modify this IFB. Answers to vendor submitted questions and other addenda will be posted under document **IFB0851-081414** on the City of Nashua website; www.nashuanh.gov under Citizen Favorites, Current Bid Opportunities **no later than Monday, August 11, 2014 at 5:00 PM.**

No bid will be considered unless accompanied by a bid security in the form of a Bid Bond, in an amount not less than five percent (5%) of the Total Bid Price. All bids are binding for sixty (60) days following the deadline for bids, or until the effective date of any resulting contract, whichever is later

The successful bidder will be required to execute the Agreement and obtain the Performance Bond and Payment Bond, each in the amount of 100 percent of the Contract Price within ten (10) calendar days from the date when Notice to Award is delivered. In case of failure to execute the Agreement, the City may consider the successful bidder in default, in which case the Bid Bond accompanying the proposal shall become the property of the City of Nashua.

The successful bidder must maintain the following lines of coverage and policy limits for the duration of the contract. Any subcontractors used by the CONTRACTOR are subject to the same coverage and limits and is a subcontractor of the CONTRACTOR and not the OWNER. It is the responsibility of the CONTRACTOR to update Certificates of Insurance during the term of the contract. **The City of Nashua must be named as an Additional Insured.**

Provide coverage for not less than the following amounts or greater:

General Liability: \$1,000,000 per Occurrence \$2,000,000 Aggregate

Motor Vehicle Liability: \$1,000,000 Combined Single Limit

***Coverage must include all owned, non-owned and hired vehicles.**

Workers' Compensation Coverage according to Statute of the State of New Hampshire:

\$100,000 / \$500,000 / \$100,000

All bidders and subcontractors at every tier under the bidder will fully comply with NH RSA Chapter 281-A, "Workers' Compensation". It is the responsibility of the CONTRACTOR to submit to the OWNER certificates of insurance for the Designer and all other subcontractors prior to the start of the project. It is the responsibility of the CONTRACTOR to provide the OWNER with updated certificates of insurance for the CONTRACTOR and all subcontractors 10 days prior to the expiration of coverage. The OWNER may, at any time, order the CONTRACTOR to stop work, suspend the contract or terminate the contract for non-compliance. All subcontractors except for Designer are subject to the same insurance requirements as the CONTRACTOR.

Contractor shall ensure that its activities and activities of its employees are in strict compliance with all Environmental Protection Agency, NHDES, and DOT regulations and all other applicable federal, state and local statutes, ordinances, regulations and rules, including without limitation, the Federal OSHA of 1970, as amended and the standards and regulations issued hereunder, and all other statutes, ordinances, regulations, rules, standards and requirements of common law in relation to industrial hygiene and safety, and the protection of health and the environment.

The City of Nashua would like to emphasize the importance of construction work zone safety. The City has adopted the provisions of the Manual on Uniform Traffic Control Devices (MUTCD) for work zone safety. Unless otherwise indicated in this contract, the contract shall follow the requirements of the MUTCD at all roadway construction work zones.

To be eligible for an award, a bidder must be deemed "responsible". A responsible bidder 1) has the ability, capacity and skill to provide the goods or services required; 2) can provide the goods or services within the time frame specified; 3) has a satisfactory record of integrity, reputation, judgment and experience; 4) has sufficient financial resources to provide the goods or services; 5) has an ability to provide future maintenance and support as required; and 6) has developed a positive track record with the City of Nashua to the extent the bidder has previously provided goods or services.

Bids must be submitted in the format provided and address the items specified in the bid package.

Delivery of the Bids shall be at the Vendor's expense. The time of receipt shall be considered when a Bid has been officially documented by the Department, in accordance with its established policies, as having been received at the location designated above. The City of Nashua accepts no responsibility for mislabeled mail. Any and all damage that may occur due to shipping shall be the Vendor's responsibility.

Postmarks or other timestamps will **not** be accepted in lieu of actual delivery. The firm can use whatever delivery mechanism it chooses as long as it remains clear that the firm is responsible for submissions prior to the date and time.

The City of Nashua assumes no liability for the payment of costs and expenses incurred by any bidder in responding to this request for bids. All bids become the sole property of the City of Nashua. This request for bids is not a contract and alone shall not be interpreted as such but rather serves as an instrument through which bids are solicited.

The City of Nashua may reject any or all of the bids on any basis and without disclosure of a reason. The failure to make such a disclosure shall not result in accrual of any right, claim or cause of action by any unsuccessful bidder against the City of Nashua.

The City reserves the right to waive any irregularities when the public interest will be served thereby. The City also reserves the right to negotiate any change or amendment in any bid without soliciting further bids if the action is necessary for the best interest of the City. A bid that is abnormally high or low for any bid item, or as a whole, may be rejected as unbalanced.

The City is exempt of all taxes. All bids must be FOB Nashua, NH. All bidders must comply with all applicable Equal Employment Opportunity laws and regulations.

Pursuant to NRO 5-71 (A), The City of Nashua supports the concept of purchasing products which are biodegradable, can be, or have been recycled, or are environmentally sound. Due consideration will be given to the purchase of such products. If you are bidding on any such products which qualify, please so indicate in a cover sheet by item number and description.

Pursuant to NRO 5-78 (F), the purchasing manager shall not solicit a bid from a contractor who is in default on the payment of taxes, licenses or other monies due the city. Therefore, this bid request is void as to anyone who is in default on said payments.

Questions relating to this request may be directed to Timothy Watson, PE, Senior Staff Engineer, at watsont@nashuanh.gov

Respectfully,

Mary Sanchez, CPPB

Mary Sanchez, CPPB
Purchasing Agent II
City of Nashua
sanchezm@nashuanh.gov

DIVISION 2

INSTRUCTIONS TO BIDDERS

TABLE OF CONTENTS

INSTRUCTIONS TO BIDDERS

	<u>Page</u>
Article 1 - Defined Terms	2
Article 2 - Copies of Bidding Documents.....	2
Article 3 - Qualifications of Bidders.	2
Article 4 - Examination of Bidding Documents, Other Related Data, and Site.....	2
Article 5 - Pre-bid Conference.....	5
Article 6 - Site and Other Areas	5
Article 7 - Interpretations and Addenda.....	5
Article 8 - Bid Security.....	6
Article 9 - Contract Times	6
Article 10 - Liquidated Damages.....	6
Article 11 - Substitute and "Or-Equal" Items	6
Article 12 - Subcontractors, Suppliers and Others	6
Article 13 - Preparation of Bid	7
Article 14 - Basis of Bid; Evaluation of Bids	8
Article 15 - Submittal of Bid.....	8
Article 16 - Modification and Withdrawal of Bid	9
Article 17 - Opening of Bids	9
Article 18 - Bids to Remain Subject to Acceptance	9
Article 19 - Award of Contract.....	9
Article 20 - Contract Security	10
Article 21 - Signing of Agreement	10
Article 22 - Retainage	10
Article 23 – Appeal by Bidders	11

INSTRUCTIONS TO BIDDERS

Article 1 – Defined Terms

- 1.01 Terms used in these Instructions to Bidders will have the meanings indicated in the General Conditions and Supplementary Conditions. Additional terms used in these Instructions to Bidders have the meanings indicated below which are applicable to both the singular and plural thereof:
- A. *Bidder* – The individual or entity who submits a Bid directly to OWNER.
 - B. *Issuing Office* – The office from which the Bidding Documents are to be issued and where the bidding procedures are to be administered.
 - C. *Successful Bidder* – The lowest responsible Bidder submitting a responsive Bid to whom OWNER (on the basis of OWNER's evaluation as hereinafter provided) makes an award.

Article 2 – Copies of Bidding Documents

- 2.01 Complete sets of the Bidding Documents in the number and for the deposit sum, if any, stated in the Advertisement or Invitation to Bid may be obtained from the Issuing Office.
- 2.02 Complete sets of Bidding Documents must be used in preparing Bids; neither OWNER nor ENGINEER assume any responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.

Article 3 – Qualifications of Bidders.

- 3.01 To demonstrate Bidder's qualifications to perform the Work, each Bidder must submit a completed Construction Contractor's Qualification for Engineered Projects..

Article 4 – Examination of Bidding Documents, Other Related Data, and Site.

4.01 *Subsurface and Physical Conditions*

- A. The Supplementary Conditions identify:
 - 1. Those reports of explorations and tests of subsurface conditions at or contiguous to the Site that ENGINEER has used in preparing the Bidding Documents.
 - 2. Those drawings of physical conditions in or relating to existing surface and subsurface structures at or contiguous to the Site (except Underground Facilities) that ENGINEER has used in preparing the Bidding Documents.
- B. Copies of reports and drawings referenced in paragraph 4.01.A will be made available by OWNER to any Bidder on request. Those reports and drawings are

not part of the Contract Documents, but the “technical data” contained therein upon which Bidder is entitled to rely as provided in paragraph 4.02 of the General Conditions has been identified. Bidder is responsible for any interpretation or conclusion Bidder draws from and “technical data” or any other data, interpretations, opinions or information contained in such reports or shown or indicated in such drawings.

4.02 *Underground Facilities*

- A. Information and data shown or indicated in the Bidding Documents with respect to existing Underground Facilities at or contiguous to the site is based upon information and data furnished to OWNER and ENGINEER by owners of such Underground Facilities including OWNER, or others. OWNER and ENGINEER do not assume responsibility for the accuracy or completeness thereof unless it is expressly provided otherwise in the Supplementary Conditions.

4.03 *Hazardous Environmental Condition*

- A. The Supplementary Conditions identify those reports and drawings relating to a Hazardous Environmental Condition identified at the Site, if any, that ENGINEER has used in preparing the Bidding Documents.
- B. Copies of reports and drawings referenced in paragraph 4.03.A will be made available by OWNER to any Bidder on request. Those reports and drawings are not part of the Contract Documents, but the “technical data” contained therein upon which Bidder is entitled to rely as provided in paragraph 4.06 of the General Conditions has been identified. Bidder is responsible for any interpretation or conclusion Bidder draws from and “technical data” or any other data, interpretations, opinions or information contained in such reports or shown or indicated in such drawings.

4.04 Provisions concerning responsibilities for the adequacy of data furnished to prospective Bidders with respect to subsurface conditions, other physical conditions and Underground Facilities, and possible changes in the Bidding Documents due to differing or unanticipated conditions appear in Paragraphs 4.02, 4.03, and 4.04 of the General Conditions. Provisions concerning responsibilities for the adequacy of data furnished to prospective Bidders with respect to a Hazardous Environmental Conditions at the Site, if any, and possible changes in the Contract Documents due to any Hazardous Environmental Condition uncovered or revealed at the Site was not shown or indicated in the Drawings or Specifications or identified in the Contract Documents to be within the scope of the Work appear in paragraph 4.06 of the General Conditions.

4.05 On request, OWNER will provide each Bidder access to the site to conduct such examinations, investigations, explorations, tests and studies, as Bidder deems necessary for submission of a Bid. Bidder shall fill all holes and clean up and restore the site to its former conditions upon completion of such explorations, investigations, tests and studies.

4.06 Reference is made to Article 7 of the General Conditions for the identification of the general nature of work that is to be performed at the site by OWNER or others (such as

utilities and other prime contractors) that relates to the work for which a Bid is to be submitted. On request, OWNER will provide to each Bidder for examination access to or copies of Contract Documents (other than portions thereof related to price) for such other work.

4.07. It is the responsibility of each Bidder before submitting a Bid to:

- A. Examine and carefully study the Bidding Documents, including any Addenda and other related data identified in the Bidding Documents;
- B. Visit the Site to become familiar with and satisfy Bidder as to the general, local, and Site conditions that may affect cost, progress, and performance of the Work;
- C. Become familiar with and satisfy Bidder as to all federal, state, and local Laws and Regulations that may affect cost, progress, performance of the Work;
- D. Carefully study all reports of explorations and tests of subsurface conditions at or contiguous to the Site and all drawings of physical conditions in or relating to existing surface or subsurface structures at or contiguous to the Site (except Underground Facilities) which have been identified in the Supplementary Conditions as provided in paragraph 4.02 of the General Conditions, and carefully study all reports and drawings of a Hazardous Environmental Condition, if any, at the Site which have been identified in the supplementary Conditions as provided in paragraph 4.06 of the General Conditions;
- E. Obtain and carefully study (or assume responsibility for doing so) all additional or supplementary examinations, investigations, explorations, tests, studies, and data concerning conditions (surface, subsurface, and Underground Facilities) at or contiguous to the Site which may affect cost, progress, or performance of the Work or which relate to any aspect of the means, methods, techniques, sequences, and procedures of construction to be employed by Bidder, including any specific means, methods, techniques, sequences, and procedures of construction expressly required by the Bidding Documents, and safety precautions and programs incident thereto;
- F. Agree at the time of submitting its Bid that no further examinations, investigations, explorations, tests, studies, or data are necessary for the determination of its Bid for performance of the Work at the price bid and within the times and in accordance with the other terms and conditions of the Bidding Documents;
- G. Become aware of the general nature of the work to be performed by OWNER and others at the Site that relates to the Work as indicated in the Bidding Documents;
- H. Correlate the information known to Bidder, information and observations obtained from visits to the Site, reports and drawings identified in the Bidding Documents, and all additional examinations, investigations, explorations, tests, studies, and data with the Bidding Documents;

- I. Promptly give ENGINEER written notice of all conflicts, errors, ambiguities, or discrepancies that Bidder discovers in the Bidding Documents and confirm that the written resolution thereof by ENGINEER is acceptable to Bidder; and
 - J. Determine that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance of the Work.
- 4.08 The submission of a Bid will constitute an incontrovertible representation by Bidder that Bidder has complied with every requirement of this Article 4, that without exception the Bid is premised upon performing and furnishing the Work required by the Bidding Documents and applying the specific means, methods, techniques, sequences or procedures of construction that may be shown or indicated or expressly required by the Bidding Documents, that Bidder has given ENGINEER written notice of all conflicts, errors, ambiguities and discrepancies that Bidder has discovered in the Contract Documents and the written resolutions thereof by ENGINEER is acceptable to Bidder, and that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performing and furnishing the Work.

Article 5 – Pre-bid Conference

- 5.01 A **mandatory** pre-bid conference will be held on the date and time prescribed and at the place indicated in the Advertisement or Invitation to Bid. Representatives of OWNER and ENGINEER will be present to discuss the Project. Bidders are encouraged to attend and participate in the conference. OWNER will transmit to all prospective Bidders of record such Addenda, as OWNER considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be binding or legally effective.

Article 6 – Site and Other Areas

- 6.01 The Site is identified in the Bidding Documents. All additional lands and access thereto required for temporary construction facilities, construction equipment or storage of materials and equipment to be incorporated in the Work are to be obtained and paid for by CONTRACTOR. Easements for permanent structures or permanent changes in existing facilities are to be obtained and paid for by OWNER unless otherwise provided in the Bidding Documents.

Article 7 – Interpretations and Addenda

- 7.01 All questions about the meaning or intent of the Bidding Documents are to be directed to ENGINEER. Interpretations or clarifications considered necessary by ENGINEER in response to such questions will be issued by Addenda mailed or delivered to all parties recorded by ENGINEER as having received the Bidding Documents. Questions received less than ten (10) days prior to the date for opening of Bids may not be answered. Only questions answered by formal written Addenda will be binding. Oral and other interpretations or clarifications will be without legal effect.
- 7.02 Addenda may also be issued to clarify, correct, or change the Bidding Documents as deemed advisable by OWNER or ENGINEER.

Article 8 – Bid Security

- 8.01 A Bid must be accompanied by Bid security made payable to OWNER in an amount of five percent of Bidder's maximum Bid price and in the form of a Bid Bond (on form attached) issued by a surety meeting the requirements of Paragraphs 5.01 and 5.02 of the General Conditions.
- 8.02 The Bid security of the Successful Bidder will be retained until such Bidder has executed the Contract Documents, furnished the required contract security and met the other conditions of the Notice of Award, whereupon the Bid security will be returned. If the Successful Bidder fails to execute and deliver the Contract Documents and furnish the required contract security within 15 days after the Notice of Award, OWNER may annul the Notice of Award and the Bid security of that Bidder will be forfeited. The Bid security of other Bidders whom OWNER believes to have a reasonable chance of receiving the award may be retained by OWNER until the earlier of seven days after the Effective Date of the Agreement or 61 days after the Bid opening, whereupon Bid security furnished by such Bidders will be returned.
- 8.03 Bid security of other Bidders whom OWNER believes do not have a reasonable chance of receiving the award will be returned within seven days after the Bid opening.

Article 9 – Contract Times

- 9.01 The number of calendar days within which, or the dates by which, the Work is to be (a) substantially completed and (b) also completed and ready for final payment are set forth in the Agreement.

Article 10 – Liquidated Damages

- 10.01 Provisions for liquidated damages, if any, are set forth in the Agreement.

Article 11 – Substitute and "Or-Equal" Items

- 11.01 The Contract, if awarded, will be on the basis of materials and equipment described in the Drawings or specified in the Specifications without consideration of possible substitute or "or-equal" items. Whenever it is specified or described in the Bidding Documents that a substitute or "or-equal" item of material or equipment may be furnished or used by CONTRACTOR if acceptable to ENGINEER, application for such acceptance will not be considered by ENGINEER until after the Effective Date of the Agreement. The procedure for submission of any such application by CONTRACTOR and consideration by ENGINEER is set forth in the General Conditions and may be supplemented in the General Requirements.

Article 12 – Subcontractors, Suppliers and Others

- 12.01 Each Bidder must submit a completed List of Subcontractors on the Form furnished with the completed Bid Form. The apparent Successful Bidder, and any other Bidder so requested, shall within seven days after the Bid opening submit to OWNER supplemental information in the form of an experience statement with the pertinent

information regarding similar projects and other evidence of qualification of each Subcontractor, Supplier, person or organization if requested by OWNER or ENGINEER. IF OWNER or ENGINEER, after due investigation, has reasonable objection to any proposed Subcontractor, Supplier, individual, or entity, OWNER may, before the Notice of Award is given request apparent Successful Bidder to submit an acceptable substitute, in which case apparent Successful Bidder shall submit an acceptable substitute, Bidder's Bid price will be increased (or decreased) by the difference in cost occasioned by such substitution and OWNER may consider such price adjustment in evaluating Bids and making the contract award.

- 12.02 If apparent Successful Bidder declines to make any such substitution, OWNER may award the Contract to the next lowest Bidder that proposes to use acceptable Subcontractors, Suppliers, individuals, or entities. Declining to make requested substitutions will not constitute grounds for forfeiture of the Bid security of any Bidder. Any Subcontractor, Supplier, individual, or entity so listed and against which OWNER or ENGINEER makes no written objection prior to the giving of the Notice of Award will be deemed acceptable to OWNER and ENGINEER subject to revocation of such acceptance after the Effective Date of the Agreement as provided in Article 6.06 of the General Conditions.
- 12.03 CONTRACTOR shall not be required to employ any Subcontractor, Supplier, individual, or entity against whom CONTRACTOR has reasonable objection.

Article 13 – Preparation of Bid

- 13.01 The Bid Form is included with the Bidding Documents. Additional copies may be obtained from ENGINEER (or the Issuing Office).
- 13.02 All blanks on the Bid Form and Bid Schedule(s) must be completed by printing in ink or by typewriter and the Bid signed. A bid price shall be indicated for each Bid item listed therein.
- 13.03 A Bid by a corporation shall be executed in the corporate name by the president or a vice-president (or other corporate officer accompanied by evidence of authority to sign) and the corporate seal must be affixed and attested by the secretary or an assistant secretary. The corporate address and state of incorporation shall be shown below the signature.
- 13.04 A Bid by a partnership shall be executed in the partnership name and signed by a partner (whose title must appear under the signature), accompanied by evidence of authority to sign. The official address of the partnership must be shown below the signature.
- 13.05 A bid by a limited liability company shall be executed in the name of the firm by a member and accompanied by evidence of authority to sign. The state of formation of the firm and the official address of the firm must be shown below the signature.
- 13.06 A Bid by an individual shall show the Bidder's name and official address.

- 13.07 A Bid by a joint venture shall be executed by each joint venturer in the manner indicated on the Bid Form. The official address of the joint venture must be shown below the signature.
- 13.08 All names must be typed or printed in black ink below the signatures.
- 13.09 The Bid shall contain an acknowledgment of receipt of all Addenda, the numbers of which must be filled in on the Bid Form.
- 13.10 The address and telephone number for communications regarding the Bid must be shown.
- 13.11 The Bid shall contain evidence of Bidder's authority and qualification to do business in the state where the Project is located. Bidder's state contractor license number for the state of the Project, if any, must also be shown on the Bid Form.

Article 14 – Basis of Bid; Evaluation of Bids

14.01 *Unit Price*

- A. Bidders shall submit a Bid on a unit price basis for each item of Work listed in the Bid schedule.
 - B. The total of all estimated prices will be determined as the sum of the products of the estimated quantity of each item and the unit price Bid for each item. The final quantities and Contract Price will be determined in accordance with paragraph 11.03 of the General Conditions.
 - C. Discrepancies between the multiplication of units of Work and unit prices will be resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum. Discrepancies between words and figures will be resolved in favor of the words.
- 14.02 The Bid price shall include such amounts as the Bidder deems proper for overhead and profit on account of cash allowance, if any, named in the Contract Documents as provided in paragraph 11.02 of the General Conditions.

Article 15 – Submittal of Bid

- 15.01 Each prospective Bidder is furnished one copy of the Bidding Documents with one separate unbound copy each of the Bid Form, and if required, the Bid Bond. The unbound copy of the Bid Form is to be completed and submitted with the Bid security and the following data:
- A. List of Subcontractors
 - B. Construction Contractor's Qualification Statement for Engineering Construction

- 15.02 A bid shall be submitted no later than the date and time prescribed and at the place indicated in the advertisement or invitation to Bid and shall be enclosed in an opaque sealed envelope plainly marked with the Project title (and, if applicable, the designated portion of the Project for which the Bid is submitted), the name and address of Bidder, and shall be accompanied by the Bid security and other required documents. If a Bid is sent by mail or other delivery system, the sealed envelope containing the Bid shall be enclosed in a separate envelope plainly marked on the outside with the notation "BID ENCLOSED." A mailed Bid shall be addressed to City of Nashua Purchasing Department, P.O. Box 2019, 229 Main Street, Nashua, NH, 03061-2019.

Article 16 – Modification and Withdrawal of Bid

- 16.01 A Bid may be modified or withdrawn by an appropriate document duly executed in the manner that a Bid must be executed and delivered to the place where Bids are to be submitted prior to the date and time for the opening of Bids.
- 16.02 If, within twenty-four hours after Bids are opened any Bidder files a duly signed written notice with OWNER and promptly thereafter demonstrates to the reasonable satisfaction of OWNER that there was a material and substantial mistake in the preparation of its Bid, **OWNER may, in its sole discretion, choose to not accept the Bid and return the same to Bidder.** Thereafter, that Bidder will be disqualified from further bidding on the Work.

Article 17 – Opening of Bids

- 17.01 Bids will be opened at the time and place indicated in the advertisement or invitation to Bid and, unless obviously non-responsive, read aloud publicly. An abstract of the amounts of the base Bids and major alternates, if any, will be made available to Bidders after the opening of Bids through posting on the City's website.

Article 18 – Bids to Remain Subject to Acceptance

- 18.01 All Bids will remain subject to acceptance for the period of time stated in the Bid Form, but OWNER may, in its sole discretion, release any Bid and return the Bid security prior to the end of this period.

Article 19 – Award of Contract

- 19.01 OWNER reserves the right to reject any or all Bids, including without limitation, nonconforming, nonresponsive, unbalanced or conditional Bids. OWNER further reserves the right to reject the Bid of any Bidder whom it finds, after reasonable inquiry and evaluation, to be non-responsive. OWNER may also reject the Bid of any Bidder if OWNER believes that it would not be in the best interest of the Project to make an award to that Bidder. OWNER also reserves the right to waive all informalities not involving price, time or changes in the Work and to negotiate contract terms with the Successful Bidder.
- 19.02 More than one Bid for the same Work from an individual or entity under the same or different names will not be considered. Reasonable grounds for believing that any

Bidder has an interest in more than one Bid for the Work may be cause for disqualification of that Bidder and the rejection of all Bids in which that Bidder has an interest.

- 19.03 In evaluating Bids, OWNER will consider whether or not the Bids comply with the prescribed requirements, and such alternates, unit prices and other data, as may be requested in the Bid Form or prior to the Notice of Award.
- 19.04 In evaluating Bidders, OWNER will consider the qualifications of Bidders and may consider the qualifications and experience of Subcontractors, Suppliers, and other individuals or entities proposed for those portions of the Work for which the Subcontractors, Suppliers, and other individuals or entities must be submitted as provided in the Supplementary Conditions..
- 19.05 OWNER may conduct such investigations as OWNER deems necessary to establish the responsibility, qualifications and financial ability of Bidders, proposed Subcontractors, Suppliers individuals, or entities to perform the Work in accordance with the Contract Documents.
- 19.06 If the Contract is to be awarded, OWNER will award the Contract to lowest Bidder whose evaluation by OWNER indicates to OWNER that the award will be in the best interests of the Project.

Article 20 - Contract Security

20.01 Article 5 of the General Conditions, as may be modified by the Supplementary Conditions, sets forth OWNER's requirements as to Performance and Payment Bonds and insurance. When the Successful Bidder delivers the executed Agreement to OWNER, it must be accompanied by such Bonds.

Article 21 – Signing of Agreement

21.01 When OWNER gives a Notice of Award to the Successful Bidder, it shall be accompanied by the required number of unsigned counterparts of the Agreement with the other Contract Documents, which are identified in the Agreement attached thereto. The Successful Bidder shall sign and deliver the required number of counterparts of the Agreement and attached documents to OWNER, including the Performance and Payment Bonds and the Certificate of Insurance. Within 10 days thereafter, OWNER shall deliver one fully signed counterpart to Successful Bidder with a complete set of drawings with appropriate identification.

21.02 A fully executed City of Nashua Purchase Order will accompany the fully signed counterpart to successful Bidder.

Article 22 – Retainage

22.01 Provisions concerning retainage and Contractors' rights to deposit securities in lieu of retainage are set forth in the Agreement.

Article 23 – Appeal by Bidders

- 23.01 Any bidder may appeal a pending bid award prior to award by Owner. The appellant must:
- A. Submit a written protest to the Owner's contract administrator within five (5) workdays after the bid opening.
 - B. Describe, in the written protest, the issues to be addresses on appeal.
 - C. Post, with the written protest, a bond with a surety meeting the requirements of General Condition 5.02 authorized to do business in this state or submit other security in a form approved by Owner who will hold the bond or security until a determination is made on the appeal.
 - D. Post the bond or other security in the amount of 25% of the total dollar value of the appellant's bid, up to a maximum bond or other security amount of 250,000.00.
 - E. Not seek any type of judicial intervention until Owner has rendered its final decision on the protest.
- 23.02 Owner will stay award actions until after the Owner's contract administrator has responded in writing to the protest. If the appellant is not satisfied with the response, the appellant may then protest to the Board of Public Works, who will render a final decision for the Owner. No bid protests will be heard by the Board of Public Works unless bidder has followed the appeal process.
- 23.03 If an appeal is granted, the full amount of the posted bond or security will be returned to the appellant. If the appeal is denied or not upheld, a claim may be made against the bond for expenses suffered by the Owner because of the unsuccessful appeal.
- 23.04 Owner is not liable for any costs, expenses, attorney's fees, loss of income, or other damages sustained by the appellant in a bid process.

DIVISION 3
BID FORM
BID BOND
CONTRACTOR'S QUALIFICATIONS
SCHEDULE OF VALUES

BID FORM

PROJECT: CDBG Manchester St/Concord St Crosswalks - IFB0851-081414

STATE CONTRACT NO.: N/A FEDERAL CONTRACT NO.: N/A

THIS BID IS SUBMITTED TO: City of Nashua
Purchasing Department
229 Main Street, City Hall
Nashua, NH 03061-2019

1.01 The undersigned BIDDER proposes and agrees, if this Bid is accepted, to enter into an agreement with OWNER in the form included in the Bidding Documents to perform all Work as specified or indicated in the Bidding Documents for the prices and within the times indicated in this Bid and in accordance with the other terms and conditions of the Bidding Documents.

2.01 BIDDER accepts all of the terms and conditions of the Advertisement or Invitation to Bid and Instructions to Bidders, including without limitation those dealing with the disposition of Bid security. The Bid will remain subject to acceptance for 60 days after the day of Bid opening, or for such longer period of time that Bidder may agree to in writing upon request of OWNER.

3.01 In submitting this Bid, BIDDER represents, as set forth in the Agreement, that:

- A. BIDDER has examined and carefully studied the Bidding Documents and the following Addenda, receipt of all which is hereby acknowledged.

Addendum No.

Addendum Date

- B. BIDDER has visited the Site and become familiar with and is satisfied as to the general, local and Site conditions that may affect cost, progress, and performance of the Work.
- C. BIDDER is familiar with and is satisfied as to all federal, state and local Laws and Regulations that may affect cost, progress and performance of the Work.
- D. BIDDER has obtained and carefully studied (or assumes responsibility for having done so) all additional or supplementary examinations, investigations, explorations, tests, studies and data concerning conditions (surface, subsurface and Underground Facilities) at or contiguous to the Site which may affect cost, progress, or performance of the Work or which relate to any aspect of the means, methods, techniques, sequences, and procedures of construction to be employed by BIDDER, and safety precautions and programs incident thereto.
- E. BIDDER does not consider that any further examinations, investigations, explorations, tests, studies, or data are necessary for the determination of this

Bid for performance of the Work at the price(s) bid and within the times and in accordance with the other terms and conditions of the Bidding Documents.

- F. BIDDER is aware of the general nature of work to be performed by OWNER and others at the Site that relates to the Work as indicated in the Bidding Documents.
- G. BIDDER has correlated the information known to BIDDER, information and observations obtained from visits to the Site, reports and drawings identified in the Bidding Documents, and all additional examinations, investigations, explorations, tests, studies, and data with the Bidding Documents.
- H. BIDDER has given ENGINEER written notice of all conflicts, errors, ambiguities, or discrepancies that BIDDER has discovered in the Bidding Documents, and the written resolution thereof by ENGINEER is acceptable to BIDDER.
- I. The Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance of the Work for which this Bid is submitted.

4.01 BIDDER further represents that this Bid is genuine and not made in the interest of or on behalf of any undisclosed individual or entity and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation; BIDDER has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid; BIDDER has not solicited or induced any individual or entity to refrain from bidding; and BIDDER has not sought by collusion to obtain for itself any advantage over any other Bidder or over OWNER.

5.01 The requirements of the New Hampshire Revised Statutes Annotated shall apply to this project. The BIDDER is responsible for compliance with all applicable statutes. The entire set of the Revised Statutes Annotated is available online at:

<http://gencourt.state.nh.us/rsa/html/indexes/default.html>

6.01 BIDDER will complete the Work in accordance with the Contract Documents for the following prices:

SEE ATTACHED BID SCHEDULE

- A. Unit Prices have been computed in accordance with paragraph 11.03.B of the General Conditions.
- B. BIDDER acknowledges that estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Bid items will be based on actual quantities provided, determined as provided in the Contract Documents.

7.01 BIDDER agrees that the Work will be substantially completed and completed and ready for final payment in accordance with paragraph 14.07.B of the General Conditions on or before the dates or within the number of calendar days indicated in the Agreement.

7.02 BIDDER accepts the provisions of the Agreement as to liquidated damages in the event of failure to complete the Work within the times specified in the Agreement.

8.01 The following documents are attached to and made a condition of this Bid:

- A. Bid Form;
- B. Bid Bond;
- C. A tabulation of Subcontractors, Suppliers and other individuals and entities required to be identified in this Bid; and
- D. Construction Contractor's Qualification Statement for Engineered Construction.

9.01 Communications concerning this Bid shall be addressed to:
(Contractor's mailing address to be filled in by Bidder)

10.01 The terms used in this Bid with initial capital letters have the meanings indicated in the Instructions to Bidders, the General Conditions, and the Supplementary Conditions.

SUBMITTED on _____, 20_____

If BIDDER is:

An Individual

Name (typed or printed): _____

By: _____ (SEAL)

(Individual's Signature)

Doing business as: _____

Business address: _____

Phone No.: _____

Fax No.: _____

A Partnership

Partnership Name: _____(SEAL)

By: _____

(Signature of General Partner – attach evidence of authority to sign)

Name (typed or printed): _____

Business address: _____

Phone No.: _____ Fax No.: _____

A Corporation

Corporation Name: _____(SEAL)

State of Incorporation: _____

Type (General Business, Professional, Service, Limited Liability): _____

By: _____

(Signature -- attach evidence of authority to sign)

Name (typed or printed): _____

Title: _____(Corporate Seal)

Attest: _____

(Signature of Corporate Secretary)

Business Address: _____

Phone No.: _____ Fax No.: _____

Date of Qualification to do business is _____

A Joint Venture

Joint Venture Name: _____(SEAL)

By: _____

(Signature of joint ventured partner -- attach evidence of authority to sign)

Name (typed or printed): _____

Title: _____

Business Address: _____

Phone No.: _____ Fax No.: _____

Joint Venture Name: _____(SEAL)

By: _____

(Signature -- attach evidence of authority to sign)

Name (typed or printed): _____

Title: _____

Business Address: _____

Phone No.: _____ Fax No.: _____

Phone and FAX Number, and Address for receipt of official communications:

(Each joint ventured must sign. The manner of signing for each individual, partnership and corporation that is a party to the joint venture should be in the manner indicated above).

The name and address of each subcontractor who will be paid at least five percent (5%) of the prime contractor's total bid shall be listed below. To be deemed a responsive bid, this form must be submitted even if no subcontractors are required to be listed. In that case, the bidder should state "None" (or similar language stating that no subcontractors need to be listed) in the space below. (Refer to General Condition 6.09.H)

[illegible]

Within two hours after the completion of the opening of the bids, the general contractors who submitted the three lowest bids must provide a list of each subcontractor who will provide labor or a portion of the work or improvement to the contractor for which the subcontractor will be paid an amount exceeding one percent (1%) of the prime contractor's bid or \$50,000, whichever is greater, and the number of the license issued to the subcontractor. **If a general contractor fails to submit such a list within the required time, the bid shall be deemed not responsive.** To be deemed a responsive bid, this form must be submitted even if no subcontractors are required to be listed. In that case, the bidder should state "None" (or similar language stating that no subcontractors need to be listed) in the space below. (Refer to General Condition 6.09.H.)

BF - 7 of 7

**City of Nashua, New Hampshire
Division of Public Works
CDBG Manchester St/Concord St Crosswalks
Bid Schedule**

Firm Name _____

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Units</u>	<u>Item Description & Unit Price (in both words and numerical)</u>	<u>Unit Price in numerals</u>	<u>Total Price in numerals</u>
202.61	390	LF	CURB REMOVAL FOR STORAGE (LANDFILL) Dollars and Cents		
203.1	170	CY	COMMON EXCAVATION Dollars and Cents		
214.	1	U	FINE GRADING Dollars and Cents		
304.3	100	CY	CRUSHED GRAVEL (F) Dollars and Cents		
403.11	40	TON	HOT BITUMINOUS PAVEMENT, MACHINE METHOD Dollars and Cents		
403.12	20	TON	HOT BITUMINOUS PAVEMENT, HAND METHOD Dollars and Cents		
417.1	370	SY	MILLING BITUMINOUS SURFACES Dollars and Cents		
604.12	3	U	CATCH BASINS TYPE B Dollars and Cents		
604.41	3	EA	RECONSTRUCTING/ADJUSTING CATCH BASIN & DROP INLET Dollars and Cents		
604.5	1	LF	RECONSTRUCTING/ADJUSTING MANHOLES Dollars and Cents		
608.24	380	SY	4" CONCRETE SIDEWALK (F) Dollars and Cents		
				SUBTOTAL BS-1	

**City of Nashua, New Hampshire
Division of Public Works
CDBG Manchester St/Concord St Crosswalks
Bid Schedule**

Firm Name _____

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Units</u>	<u>Item Description & Unit Price (in both words and numerical)</u>	<u>Unit Price in numerals</u>	<u>Total Price in numerals</u>
608.541	12	U	DETECTABLE WARNING DEVICES, PLASTIC Dollars and Cents		
609.01	180	LF	STRAIGHT GRANITE CURB Dollars and Cents		
609.02	275	LF	CURVED GRANITE CURB Dollars and Cents		
615.0071	100	LB	STEEL SIGN POSTS Dollars and Cents		
615.0141	3	U	RELOCATING TRAFFIC SIGN Dollars and Cents		
615.022	20	SF	TRAFFIC SIGN TYPE B, BREAKAWAY MOUNTS (F) Dollars and Cents		
615.9901	3	U	REMOVE AND STOCKPILE TRAFFIC SIGN Dollars and Cents		
618.6	3000	\$	UNIFORMED OFFICERS ALLOWANCE - Three Thousand Dollars and no Cents	\$ 3,000.00	\$ 3,000.00
618.7	900	HR	FLAGGERS ALLOWANCE - Nineteen Thousand Eight Hundred Dollars and no cents	\$ 19,800.00	\$ 19,800.00
619.1	1	U	MAINTENANCE OF TRAFFIC Dollars and Cents		
628.2	955	LF	SAWED BITUMINOUS PAVEMENT Dollars and Cents		
				SUBTOTAL BS-2	

**City of Nashua, New Hampshire
Division of Public Works
CDBG Manchester St/Concord St Crosswalks
Bid Schedule**

Firm Name _____

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Units</u>	<u>Item Description & Unit Price (in both words and numerical)</u>	<u>Unit Price in numerals</u>	<u>Total Price in numerals</u>
632.0104	290	LF	RETROREFLECTIVE PAINT PAVE. MARKING, 4" LINE Dollars and Cents	_____	_____
641.	30	CY	LOAM Dollars and Cents	_____	_____
644.15	10	LB	PARK SEED TYPE 15 Dollars and Cents	_____	_____
692.	1	U	MOBILIZATION NOT TO EXCEED 5% OF CONTRACT Dollars and TO BE PAID ON PERCENT COMPLETE BASIS Cents	_____	_____
A	1190	SF	IMPRINTED AGGREGATE REINFORCED PREFORMED THERMOPLASTIC PAVEMENT MARKING SYSTEM Dollars and Cents	_____	_____
B	310	SF	PREFORMED THERMOPLASTIC PAVEMENT MARKINGS Dollars and Cents	_____	_____
C	36	SY	BRICK MATERIAL AND INSTALLATION Dollars and Cents	_____	_____
D	8	EA	BOLLARD - STEEL FILLED WITH CONCRETE Dollars and Cents	_____	_____
E	2	U	RECTANGULAR RAPID FLASH BEACON SYSTEM Dollars and Cents	_____	_____

SUBTOTAL BS-3 _____

**City of Nashua, New Hampshire
Division of Public Works
CDBG Manchester St/Concord St Crosswalks
Bid Schedule**

Firm Name _____

<u>Item No.</u>	<u>Estimated Quantity</u>	<u>Units</u>	<u>Item Description & Unit Price (in both words and numerical)</u>	<u>Unit Price in numerals</u>	<u>Total Price in numerals</u>
-----------------	-------------------------------	--------------	--	-----------------------------------	------------------------------------

SUMMARY of Each Bid Sheet

SUBTOTAL of Page BS-1

SUBTOTAL of Page BS-2

SUBTOTAL of Page BS-3

TOTAL BID PRICE FIGURES

TOTAL BID PRICE WORDS

Dollars and

Cents

Contractor:

Name of Firm

Authorized Signature:

Date

BID BOND PENAL SUM FORM

BIDDER (Name and Address):

SURETY (Name and Address of Principal Place of Business):

OWNER (Name and Address):

BID

BID DUE DATE: _____

PROJECT (Brief Description Including Location): _____

BOND

BOND NUMBER: _____

DATE: (Not later than Bid Due Date): _____

PENAL SUM: _____

(Words)

(Figures)

IN WITNESS WHEREOF, Surety and Bidder, Intending to be legally bound hereby, subject to the terms printed on the reverse side hereof, do each cause the Bid Bond to be duly executed on its behalf by its authorized officer, agent, or representative.

BIDDER

SURETY

_____(Seal)
Bidder's Name and Corporate Seal

_____(Seal)
Surety's Name and Corporate Seal

By: _____
Signature and Title

By: _____
Signature and Title
(Attach Power of Attorney)

Attest: _____
Signature and Title

Attest: _____
Signature and Title

Note: (1) Above addresses are to be used for giving required notice.
(2) Any singular reference to Bidder, Surety, OWNER or other party shall be considered plural where applicable.

1. Bidder and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors, and assigns to pay to OWNER upon default of Bidder the penal sum set forth on the face of this Bond.
2. Default of Bidder shall occur upon the failure of Bidder to deliver within the time required by the Bidding Documents (or any extension thereof agreed to in writing by OWNER) the executed Agreement required by the Bidding Documents and any performance and payment bonds required by the Bidding Documents and Contract Documents.
3. This obligation shall be null and void if:
 - 3.1. OWNER accepts Bidder's bid and Bidder delivers within the time required by the Bidding Documents (or any extension thereof agreed to in writing by OWNER) the executed Agreement required by the Bidding Documents and any performance and payment bonds required by the Bidding Documents and Contract Documents, or
 - 3.2 All bids are rejected by OWNER, or
 - 3.3 OWNER fails to issue a notice of award to Bidder within the time specified in the Bidding Documents (or any extension thereof agreed to in writing by Bidder and, if applicable, consented to by Surety when required by paragraph 5 hereof).
4. Payment under this bond will be due and payable upon default by Bidder and Within 30 calendar days after receipt by Bidder and Surety of written notice of default from OWNER, which notice will be given with reasonable promptness, identifying this Bond and the Project and including a statement of the amount due.
5. Surety waives notice of and any and all defenses based on or arising out of any time extension to issue notice of award agreed to in writing by OWNER and Bidder, provided that the time for issuing Notice of Award including extensions shall not in the aggregate exceed 120 days from Bid Due Date without Surety's written consent.
6. No suit or action shall be commenced under this Bond prior to 30 calendar days after the notice of default required in paragraph 4 above is received by Bidder and Surety, and in no case later than one year after Bid due date.
7. Any suit or action under this Bond shall be commenced only in a court of competent jurisdiction located in the state in which the Project is located.
8. Notice required hereunder shall be in writing and sent to Bidder and Surety at their respective addresses shown on the face of this Bond. Such notices may be sent by personal delivery, commercial courier or by United States Registered or Certified Mail, return receipt requested, postage pre-paid, and shall be deemed to be effective upon receipt by the party concerned.
9. Surety shall cause to be attached to this Bond a current and effective Power of Attorney evidencing the authority of the officer, agent or representative who executed this Bond on behalf of Surety to execute, seal and deliver such Bond and bind the Surety thereby.
10. This Bond is intended to conform to all applicable statutory requirements. Any applicable requirement of any applicable statute that has been omitted from this Bond shall be deemed to be included herein as if set forth at length. If any provision of the Bond conflicts with any applicable provision of any applicable statute, then the provision of said statute shall govern and the remainder of this Bond that is not in conflict therewith shall continue in full force and effect.
11. The term "Bid" as used herein includes a Bid, offer or proposal as applicable.

CONSTRUCTION CONTRACTOR'S QUALIFICATION STATEMENT FOR ENGINEERED CONSTRUCTION

Submitted by:

Name of Organization _____

Name of Individual _____

Title _____

Address _____

Telephone _____

Submitted to:

Name _____

Address _____

Telephone _____

Project Name and Description (if applicable)

Contractor' General Business Information

Check If:

☐ Corporation ☐ Partnership ☐ Joint Venture ☐ Sole Proprietorship

If Corporation:

a. Date and State of Incorporation

b. List of Executive Officers

Name	Title
<hr/>	<hr/>
<hr/>	<hr/>
<hr/>	<hr/>

If Partnership:

a. Date and State of Organization

b. Names of Current General Partners

c. Type of Partnership

☐ General ☐ Publicly Traded
☐ Limited ☐ Other (describe):

If Joint Venture:

a. Date and State of Organization

b. Name, Address and Form of Organization of Joint Venture Partners: (Indicate managing partner by an asterisk *)

1. On Schedule A, attached, list major engineered construction projects completed by this organization in the past five (5) years. (If joint venture, list each participant's projects separately).

2. On Schedule B, attached, list current projects under construction by this organization, (If joint venture, list each participant's projects separately).

3. Name of surety company and name, address, and phone number of agent.

4. Is your organization a member of a controlled group of corporations as defined in I.R.C. Sec. 1563?

☐ Yes ☐ No

If yes, show names and addresses of affiliated companies.

5. Furnish on Schedule C, attached, details of the construction experience of the principal individuals of your organization directly involved in construction operations.

6. Has your organization ever failed to complete any construction contract awarded to it?

☐ Yes ☐ No

If yes, describe circumstances and provide details on attachment.

7. Has any Corporate officer, partner, joint venture participant or proprietor ever failed to complete a construction contract awarded to him or her in their own name or when acting as a principal of another organization?

☐ Yes ☐ No

If yes, describe circumstances and provide details on attachment.

8. In the last five years, has your organization ever failed to substantially complete a project in a timely manner?

☐ Yes ☐ No

If yes, describe circumstances and provide details on attachment.

9. Does your organization now have any legal suits or arbitration claims pending or outstanding against it or any officers?

☐ Yes ☐ No

If yes, describe circumstances and provide details on attachment.

10. Has your organization had a contract partially or completely terminated for default (cause) within the past five years?

☐ Yes ☐ No

If yes, describe circumstances and provide details on attachment.

11. List the licensed categories of work that your company normally performs with its own workforce. _____

12. If required, can your organization provide a bid bond for this project?

☐ Yes ☐ No

13. What is your approximate total bonding capacity?

☐ \$500,000 to \$2,000,000

☐ \$2,000,000 to \$5,000,000

☐ \$5,000,000 to \$10,000,000

☐ \$10,000,000 or more

14. Describe the permanent safety program you maintain within your organization. Use attachment if necessary.

15. Furnish the following information with respect to an accredited banking institution familiar with your organization.

Name of Bank _____

Address _____

Account Manager _____

Telephone _____

I hereby certify that the information submitted herewith, including any attachment is true to the best of my knowledge and belief.

By: _____

Title: _____

Dated: _____

This Page Intentionally Left Blank

Schedule A – List of Major Engineered Construction Projects Completed in the Past Five (5) Years

<u>Name, Location and Description of Project</u>	<u>Owner</u>	<u>Design Engineer</u>	<u>Date Completed</u>	<u>Contract Price</u>	<u>Reference/Contact & Address & Phone</u>
---	---------------------	-------------------------------	------------------------------	------------------------------	---

Schedule B – List of Current Projects Under Construction

<u>Name, Location and Description of Project</u>	<u>Owner</u>	<u>Design Engineer</u>	<u>Contract Price</u>	<u>Amount Completed</u>	<u>Date of Scheduled Completion</u>	<u>Reference/Contact & Address & Phone</u>
---	---------------------	-----------------------------------	------------------------------	------------------------------------	--	---

Schedule C - Construction Experience of Principal Individuals Involved in Construction Operations

Name	Position	Date started with this organization	Date started working in construction	Prior positions and experience in construction
-------------	-----------------	--	---	---

**DIVISION 4
PERFORMANCE
AND
PAYMENT BONDS**

CONSTRUCTION PERFORMANCE BOND

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

CONTRACTOR (Name and Address):

SURETY (Name and Address of Principal Place of Business):

OWNER (Name and Address):

CONSTRUCTION CONTRACT

Date:

Amount:

Description (Name and Location):

BOND

Date (Not earlier than Construction Contract Date):

Amount:

Modifications to this Bond Form:

Surety and Contractor, intending to be legally bound hereby, subject to the terms printed on the following two pages, do each cause this Performance Bond to be duly executed on its behalf by its authorized officer, agent or representative.

CONTRACTOR AS PRINCIPAL

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:

SURETY

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:
(Attach Power of Attorney)

Space provided below for signatures of additional parties, if required)

CONTRACTOR AS PRINCIPAL

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:

SURETY

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:

(Attach Power of Attorney)

1. The CONTRACTOR and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the OWNER for the performance of the Construction Contract, which is incorporated herein by reference.

2. If the CONTRACTOR performs the Construction Contract, the Surety and the CONTRACTOR shall have no obligation under this Bond, except to participate in conferences as provided in Subparagraph 3.1.

3. If there is no OWNER Default, the Surety's obligation under this Bond shall arise after:

3.1 The OWNER has notified the CONTRACTOR and the Surety at its address described in Paragraph 10 below, that the OWNER is considering declaring a CONTRACTOR Default and has requested and attempted to arrange a conference with the CONTRACTOR and the Surety to be held not later than fifteen days after receipt of such notice to discuss methods of performing the Construction Contract. If the OWNER, the CONTRACTOR and the Surety agree, the CONTRACTOR shall be allowed a reasonable time to perform the Construction Contract, but such an agreement shall not waive the OWNER's right, if any, subsequently to declare a CONTRACTOR Default; and

3.2 The OWNER has declared a CONTRACTOR Default and formally terminated the CONTRACTOR's right to complete the contract. Such CONTRACTOR Default shall not be declared earlier than twenty days after the CONTRACTOR and the Surety have received notice as provided in Subparagraph 3.1; and

3.3 The OWNER has agreed to pay the Balance of the Contract Price to:

3.3.1 The Surety in accordance with the terms of the Contract;

3.3.2 Another contractor selected pursuant to paragraph 4.3 to perform the Contract.

4. When the OWNER has satisfied the conditions of Paragraph 3, the Surety shall promptly and

at the Surety's expense take one of the following actions:

4.1 Arrange for the CONTRACTOR, with consent of the OWNER, to perform and complete the Construction Contract; or

4.2 Undertake to perform and complete the Construction Contract itself, through its agents or through independent contractors; or

4.3 Obtain bids or negotiated proposals from qualified contractors acceptable to the OWNER for a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the OWNER and the CONTRACTOR selected with the OWNER's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the OWNER the amount of damages as described in Paragraph 6 in excess of the Balance of the Contract Price incurred by the OWNER resulting from the CONTRACTOR's default; or

4.4 Waive its right to perform and complete, arrange for completion, or obtain a new CONTRACTOR and with reasonable promptness under the circumstances:

4.4.1. After investigation, determine the amount for which it may be liable to the OWNER and, as soon as practicable after the amount is determined, tender payment therefor to the OWNER; or

4.4.2. Deny liability in whole or in part and notify the OWNER citing reasons therefor.

5. If the Surety does not proceed as provided in paragraph 4 with reasonable promptness, the Surety shall be deemed to be in default on this Bond fifteen days after receipt of an additional written notice from the OWNER to the Surety demanding that the Surety perform its obligations under this Bond, and the OWNER shall be entitled to enforce any remedy available to the OWNER, If the Surety proceeds as provided in paragraph 4.4 , and the OWNER refuses the payment tendered or the Surety has denied liability, in whole or in part,

without further notice the OWNER shall be entitled to enforce any remedy available to the OWNER.

6. After the OWNER has terminated the CONTRACTOR's right to complete the Construction Contract, and if the Surety elects to act under paragraph 4.1, 4.2, or 4.3, above, then the responsibilities of the Surety to the OWNER shall not be greater than those of the CONTRACTOR under the Construction Contract, and the responsibilities of the OWNER to the Surety shall not be greater than those of the OWNER under the Construction Contract. To the limit of the amount of this Bond, but subject to commitment by the OWNER of the Balance of the Contract Price to mitigation of costs and damages on the Construction Contract, the Surety is obligated without duplication for:

- 6.1 The responsibilities of the CONTRACTOR for correction of defective work and completion of the Construction Contract;
- 6.2 Additional legal, design professional and delay costs resulting from the CONTRACTOR's Default, and resulting from the actions or failure to act of the Surety under paragraph 4; and
- 6.3 Liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or nonperformance of the CONTRACTOR.

7. The Surety shall not be liable to the OWNER or others for obligations of the CONTRACTOR that are unrelated to the Construction Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the OWNER or its heirs, executors, administrators, or successors.

8. The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.

9. Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and shall be instituted within two years after CONTRACTOR Default or within two years after the CONTRACTOR ceased

working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this Paragraph are void or prohibited by Law, the Minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.

10. Notice to the Surety, the OWNER or the CONTRACTOR shall be mailed or delivered to the address shown on the signature page.

11. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

12. Definitions.

- 12.1 Balance of the Contract Price: The total amount payable by the OWNER to the CONTRACTOR under the Construction Contract after all proper adjustments have been made, including allowance to the CONTRACTOR of any amounts received or to be received by the OWNER in settlement of insurance or other claims for damages to which the CONTRACTOR is entitled, reduced by all valid and proper payments made to or on behalf of the CONTRACTOR under the Construction Contract.
- 12.2. Construction Contract: The agreement between the OWNER and the CONTRACTOR identified on the signature page, including all Contract Documents and changes thereto.
- 12.3. CONTRACTOR Default: Failure of the CONTRACTOR, which has neither been remedied nor waived, to perform or otherwise to comply with the terms of the Construction Contract.
- 12.4. OWNER Default: Failure of the OWNER, which has neither been remedied nor waived, to pay the CONTRACTOR as required by the Construction Contract or to perform and complete or comply with the other terms thereof.

CONSTRUCTION PAYMENT BOND

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

CONTRACTOR (Name and Address):

SURETY (Name and Address of Principal Place of Business):

OWNER (Name and Address):

CONSTRUCTION CONTRACT

Date:

Amount:

Description (Name and Location):

BOND

Date (Not earlier than Construction Contract Date):

Amount:

Modifications to this Bond Form:

Surety and Contractor, intending to be legally bound hereby, subject to the terms printed on the following two pages, do each cause this Payment Bond to be duly executed on its behalf by its authorized officer, agent or representative.

CONTRACTOR AS PRINCIPAL

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:

SURETY

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:
(Attach Power of Attorney)

Space provided below for signatures of additional parties, if required)

CONTRACTOR AS PRINCIPAL

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:

SURETY

Company: _____ (Corp. Seal)

Signature: _____

Name and Title:

(Attach Power of Attorney)

1. The CONTRACTOR and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the OWNER to pay for labor, materials and equipment furnished for use in the performance of the Construction Contract, which is incorporated herein by reference.

2. With respect to the OWNER, this obligation shall be null and void if the CONTRACTOR:

2.1 Promptly makes payment, directly or indirectly, for all sums due Claimants, and

2.2 Defends, indemnifies and holds harmless the OWNER from all claims, demands, liens or suits by any person or entity who furnished labor, materials or equipment for use in the performance of the Construction Contract, provided the OWNER has promptly notified the CONTRACTOR and the Surety (at the address described in Paragraph 12) of any claims, demands, liens or suits and tendered defense of such claims, demands, liens or suits to the CONTRACTOR and the Surety, and provided there is no OWNER Default.

3. With respect to Claimants, this obligation shall be null and void if the CONTRACTOR promptly makes payment, directly or indirectly, for all sums due.

4. The Surety shall have no obligation to Claimants under this Bond until:

4.1 Claimants who are employed by or have a direct contract with the CONTRACTOR have given notice to the Surety (at the address described in Paragraph 12) and sent a copy, or notice thereof, to the OWNER, stating that a claim is being made under this Bond and, with substantial accuracy, the amount of the claim.

4.2 Claimants who do not have a direct contract with the CONTRACTOR:

4.2.1. Have furnished written notice to the CONTRACTOR and sent a copy, or notice thereof, to the OWNER, within 90 days after having last performed labor or last furnished materials or equipment included in the claim stating, with substantial accuracy, the amount of the claim and

the name of the party to whom the materials were furnished or supplied or for whom the labor was done or performed; and

4.2.2. Have either received a rejection in whole or in part from the CONTRACTOR, or not received within 30 days of furnishing the above notice any communication from the CONTRACTOR by which the CONTRACTOR has indicated the claim will be paid directly or indirectly; and

4.2.3. Not having been paid within the above 30 days, have sent a written notice to the Surety (at the address described in Paragraph 12) and sent a copy, or notice thereof, to the OWNER, stating that a claim is being made under this Bond and enclosing a copy of the previous written notice furnished to the CONTRACTOR.

5. If a notice required by Paragraph 4 is given by the OWNER to the CONTRACTOR or to the Surety, that is sufficient compliance.

6. When the Claimant has satisfied the conditions of Paragraph 4, the Surety shall promptly and at the Surety's expense take the following actions:

6.1 Send an answer to the Claimant, with a copy to the OWNER, within 45 days after receipt of the claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed.

6.2 Pay or arrange for payment of any undisputed amounts.

7. The Surety's total obligation shall not exceed the amount of this Bond, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.

8. Amounts owed by the OWNER to the CONTRACTOR under the Construction Contract shall be used for the performance of the Construction Contract and to satisfy claims, if any, under any Construction Performance Bond. By the CONTRACTOR furnishing and the OWNER accepting this Bond, they agree

that all funds earned by the CONTRACTOR in the performance of the Construction Contract are dedicated to satisfy obligations of the CONTRACTOR and the Surety under this Bond, subject to the OWNER's priority to use the funds for the completion of the work.

9. The Surety shall not be liable to the OWNER, Claimants or others for obligations of the CONTRACTOR that are unrelated to the Construction Contract. The OWNER shall not be liable for payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligations to make payments to, give notices on behalf of, or otherwise have obligations to Claimants under this Bond.

10. The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.

11. No suit or action shall be commenced by a Claimant under this Bond other than in a court of competent jurisdiction in the location in which the work or part of the work is located or after the expiration of one year from the date (1) on which the Claimant gave the notice required by paragraph 4.1 or paragraph 4.2.3, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.

12. Notice to the Surety, the OWNER or the CONTRACTOR shall be mailed or delivered to the address shown on the signature page. Actual receipt of notice by Surety, the OWNER or the CONTRACTOR, however accomplished, shall be sufficient compliance as of the date received at the address shown on the signature page.

13. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or the legal requirement shall be deemed incorporated herein. The intent is, that this Bond shall be construed as a statutory bond and not as a common law bond.

14. Upon request by any person or entity appearing to be a potential beneficiary of this Bond, the CONTRACTOR shall promptly furnish a copy of this Bond or shall permit a copy to be made.

15. DEFINITIONS

15.1 Claimant: An individual or entity having a direct contract with the CONTRACTOR or with a subcontractor of the CONTRACTOR to furnish labor, materials or equipment for use in the performance of the Contract. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the CONTRACTOR and the CONTRACTOR's subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.

15.2 Contract: The agreement between the OWNER and the CONTRACTOR identified on the signature page, including all Contract Documents and changes thereto.

15.3 OWNER Default: Failure of the OWNER, which has neither been remedied nor waived, to pay the CONTRACTOR as required by the Construction Contract or to perform and complete or comply with the other terms thereof.

DIVISION 5 AGREEMENT

STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

THIS AGREEMENT is dated as of the _____ day of _____ in the year 20____ by and between the City of Nashua, New Hampshire (hereinafter called OWNER) and _____ (hereinafter called CONTRACTOR).

OWNER and CONTRACTOR, in consideration of the mutual covenants hereinafter set forth, agree as follows:

ARTICLE 1 - WORK

1.01 CONTRACTOR shall complete all Work as specified or indicated in the Contract Documents.

ARTICLE 2 - THE PROJECT

2.01 The Project for which the Work under the Contract Documents may be the whole or only a part is generally described as follows:

**CDBG Manchester St./ Concord St. Crosswalks
IFB0851-081414**

ARTICLE 3 - ENGINEER

3.01 The Project has been designed by: **Division of Public Works
Engineering Department
9 Riverside St
Nashua, NH 03062**

who is hereinafter called ENGINEER and who is to act as OWNER's representative, assume all duties and responsibilities, and have the rights and authority assigned to ENGINEER in the Contract Documents in connection with completion of the Work in accordance with the Contract Documents.

ARTICLE 4 - CONTRACT TIMES

4.01 *Time of the Essence*

A. All time limits for Milestones, if any, Substantial Completion, and completion and readiness for final payment as stated in the Contract Documents are of the essence of the Contract.

4.02 *Dates for Substantial Completion and Final Payment*

The Work will be substantially completed within **120** calendar days after the date of Notice to Proceed when the Contract Times commence to run as provided in paragraph 2.03 of the General Conditions, and completed and ready for final payment in accordance with paragraph 14.07 of the General Conditions within **150** calendar days after the date when the Contract Times commence to run.

4.03 Liquidated Damages

A. CONTRACTOR and OWNER recognize that time is of the essence of this Agreement and that OWNER will suffer financial loss if the Work is not completed within the times specified in paragraph 4.02 above, plus any extensions thereof allowed in accordance with Article 12 of the General Conditions. The parties also recognize the delays, expense and difficulties involved in proving in a legal or arbitration proceeding the actual loss suffered by OWNER if the Work is not completed on time. Accordingly, instead of requiring any such proof, OWNER and CONTRACTOR agree that as liquidated damages for delay (but not as a penalty) CONTRACTOR shall pay OWNER ONE HUNDRED dollars **(\$100)** for each day that expires after the time specified in paragraph 4.02 for Substantial Completion until the Work is substantially complete. After Substantial Completion, if CONTRACTOR shall neglect, refuse or fail to complete the remaining Work within the time specified in paragraph 4.02 for completion and readiness for final payment or any proper extension thereof granted by OWNER, CONTRACTOR shall pay OWNER TWO HUNDRED dollars **(\$200)** for each day that expires after the time specified in paragraph 4.02 for completion and readiness for final payment until the Work is completed and ready for final payment.

B. In the event that the CONTRACTOR fails to pay OWNER the specified liquidated damages amount within thirty (30) days of CONTRACTOR's being notified of said damages, OWNER may deduct the amount of the assessed liquidated damages from the final payment or retention withheld pursuant to Article 14 of the General Conditions.

ARTICLE 5 - CONTRACT PRICE

5.01 Subject to additions and deductions by Change Order, the OWNER shall pay CONTRACTOR, in accordance with the Contract Documents, the Contract Sum of:

_____ (\$ _____)

The Contract Sum shall include all items and services necessary for the proper execution and completion of the Work determined below:

A. for all Unit Price Work, an amount equal to the sum of the established Unit Price for each separately identified item of Unit Price Work times the estimated quantity of that item, as indicated in the attached Bid Schedule;

B. as provided in paragraph 11.03 of the General Conditions estimated quantities are not guaranteed, and determinations of actual quantities and classification are to be made by ENGINEER as provided in paragraph 9.08 of the General Conditions. Unit prices have been computed as provided in paragraph 11.03 of the General Conditions.

ARTICLE 6 - PAYMENT PROCEDURES

6.01 Submittal and Processing of Payments

A. CONTRACTOR shall submit Applications for Payment in accordance with Article 14 of the General Conditions. Applications for Payment will be processed by ENGINEER as provided in the General Conditions.

6.02 *Progress Payments; Retainage*

A. *Progress Payments.* Prior to Substantial Completion, The OWNER will once each month make a progress payment to the CONTRACTOR on the basis of an estimate of the total amount of work done to the time of the estimate and its value as prepared by the CONTRACTOR and approved by the ENGINEER. All such payments will be measured by the schedule of values established in paragraph 2.07.A of the General Conditions (and in the case of Unit Price Work based on the number of units completed) or, in the event there is no schedule of values, as provided in the General Requirements.

B. *Retainage.* The OWNER will retain a portion of the progress payment, each month, in accordance with the following procedures:

1. The OWNER will establish an escrow account in the bank of the OWNER'S choosing. The account will be established such that interest on the principal will be paid to the CONTRACTOR. The principal will be the accumulated retainage paid into the account by the OWNER. The principal will be held by the bank, available only to the OWNER, until termination of the contract.
2. Until the work is 50% complete, as determined by the ENGINEER, retainage shall be 10% of the monthly payments claimed. The computed amount of retainage will be deposited in the escrow account established above.
3. After the work is 50% complete, and provided the CONTRACTOR has satisfied the ENGINEER in quality and timeliness of the work, and provided further that there is no specific cause for withholding additional retainage no further amount will be withheld. The escrow account will remain at the same balance throughout the remainder of the project.

6.03 *Final Payment*

A. Upon final completion and acceptance of the Work in accordance with paragraph 14.07 of the General Conditions, OWNER shall hold 2% retainage during the **1 (one) year** warranty period and release it only after the project has been accepted.

ARTICLE 7 - CONTRACTOR'S REPRESENTATIONS

7.01 In order to induce OWNER to enter into this Agreement CONTRACTOR makes the following representations:

A. CONTRACTOR has examined and carefully studied the Contract Documents and the other related data identified in the Bidding Documents.

B. CONTRACTOR has visited the Site and become familiar with and is satisfied as to the general, local, and Site conditions that may affect cost, progress, and performance of the Work.

C. CONTRACTOR is familiar with and is satisfied as to all federal, state, and local Laws and Regulations that may affect cost, progress, and performance of the Work.

D. CONTRACTOR has carefully studied all (if any): (1) reports of explorations and tests of subsurface conditions at or contiguous to the Site and all drawings of physical conditions in or relating to existing surface or subsurface structures at or contiguous to the Site (except Underground Facilities) which have been identified in the Supplementary Conditions as provided in paragraph 4.02 of the General Conditions and (2) reports and drawings of a Hazardous Environmental Condition, if any, at the Site which has been identified in the Supplementary Conditions as provided in paragraph 4.06 of the General Conditions.

CONTRACTOR is entitled to rely upon the general accuracy of the "technical data" as provided in paragraph 4.2 of the General Conditions. CONTRACTOR acknowledges that such reports and drawings are not Contract Documents and may not be complete for CONTRACTOR's purposes. CONTRACTOR acknowledges that OWNER and ENGINEER do not assume responsibility for the accuracy or completeness of information and data shown or indicated in the Contract Documents with respect to Underground Facilities at or contiguous to the site.

E. CONTRACTOR has obtained and carefully studied (or assumes responsibility for having done so) all additional or supplementary examinations, investigations, explorations, tests, studies, and data concerning conditions (surface, subsurface and Underground Facilities) at or contiguous to the Site which may affect cost, progress, or performance of the Work or which relate to any aspect of the means, methods, techniques, sequences and procedures of construction, if any, expressly required by the Contract Documents to be employed by CONTRACTOR, and safety precautions and programs incident thereto.

F. CONTRACTOR does not consider that any further examinations, investigations, explorations, tests, studies, or data are necessary for the performance of the Work at the Contract Price, within the Contract Times, and in accordance with the other terms and conditions of the Contract Documents.

G. CONTRACTOR is aware of the general nature of work to be performed by OWNER and others at the Site that relates to the Work as indicated in the Contract Documents.

H. CONTRACTOR has correlated the information known to CONTRACTOR, information and observations obtained from visits to the Site, reports and drawings identified in the Contract Documents and all additional examinations, investigations, explorations, tests, studies, and data with the Contract Documents.

I. CONTRACTOR has given ENGINEER written notice of all conflicts, errors, ambiguities or discrepancies that CONTRACTOR has discovered in the Contract Documents, and the written resolution thereof by ENGINEER is acceptable to CONTRACTOR.

J. The Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.

ARTICLE 8 - CONTRACT DOCUMENTS

8.01 *Contents*

A. The Contract Documents consist of the following:

1. This Agreement;
2. Invitation for Bid;
3. Instructions to Bidders;

4. General Conditions;
 5. Supplementary Conditions (if applicable);
 6. Special Provisions (if applicable);
 7. Bid Bond;
 8. Bid Form;
 9. Performance Bond;
 10. Payment Bond;
 11. Certificate of Insurance
 12. Construction Specifications as listed in Table of Contents
 13. Addenda (numbers _____ to _____, inclusive);
 14. Exhibits, as listed in the Table of Contents, to this Agreement
 15. The following which may be delivered or issued on or after the Effective Date of the Agreement and are not attached hereto:
 - a. Written Amendments
 - b. Change Order(s)
 14. New Hampshire Department of Transportation "Standard Specifications for Road and Bridge Construction", **latest** edition, incorporated by reference or unless otherwise indicated.
 15. "Manual of Uniform Traffic Control Devices", **latest** edition, incorporated by reference.
 16. City of Nashua, Standard Specifications for Sewers and Drains, Approved and Adopted June 15, 1992, incorporated by reference.
 17. City of Nashua, Standard Specifications for Road Construction, Approved and Adopted June 11, 1986, incorporated by reference.
 18. Fully Executed City of Nashua Purchase Order
- B. The documents listed in paragraph 8.01.A are attached to this Agreement (except as expressly noted otherwise above).
- C. There are no Contract Documents other than those listed above in this Article 8.
- D. The Contract Documents may only be amended, modified or supplemented as provided in paragraph 3.04 of the General Conditions.

ARTICLE 9 - MISCELLANEOUS

9.01 Terms

A. Terms used in this will have the meanings indicated in the General Conditions.

9.02. Assignment of Contract

A. No assignment by a party hereto of any rights under or interests in the Contract will be binding on another party hereto without the written consent of the party sought to be bound; and, specifically but without limitation, moneys that may become due and moneys that are due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law), and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignor from any duty or responsibility under the Contract Documents.

9.03 Successors and Assigns

A. OWNER and CONTRACTOR each binds itself, its partners, successors, assigns, and legal representatives to the other party hereto, its partners, successors, assigns, and legal representatives in respect to all covenants, agreements, and obligations contained in the Contract Documents.

9.04 Severability

A. Any provision or part of the Contract Documents held to be void or unenforceable under any Law or Regulation shall be deemed stricken, and all remaining provisions shall continue to be valid and binding upon OWNER and CONTRACTOR, who agree that the Contract Documents shall be reformed to replace such stricken provision or part thereof with a valid and enforceable provision that comes as close as possible to expressing the intention of the stricken provision.

9.05 Choice of Law and Venue

A. This Agreement shall be goverened by the laws of the State of New Hampshire, and any litigation shall be brought in a court located in the State of New Hampshire.

Address for giving notices to Owner:

Division of Public Works
9 Riverside Street
Nashua, NH 03062

Address for giving notices to Contractor:

Agent for service of process:

IN WITNESS WHEREOF, OWNER and CONTRACTOR have signed this Agreement in triplicate. One counterpart each has been delivered to OWNER, CONTRACTOR and ENGINEER. All portions of the Contract Documents have been signed, initialed or identified by OWNER and CONTRACTOR or identified by ENGINEER on their behalf.

CITY OF NASHUA – OWNER

Donnalee Lozeau, Mayor City of Nashua

Date: _____

CONTRACTOR:

By: _____
(Authorized Representative)

Print Name: _____

Date: _____

DIVISION 6
GENERAL CONDITIONS

TABLE OF CONTENTS FOR GENERAL CONDITIONS

	<u>Page</u>
ARTICLE 1 - DEFINITIONS AND TERMINOLOGY	4
1.01 Defined Terms.....	4
1.02 Terminology.....	7
ARTICLE 2 - PRELIMINARY MATTERS.....	8
2.01 Delivery of Bonds	8
2.02 Copies of Documents	8
2.03 Commencement of Contract Times; Notice to Proceed	8
2.04 Starting the Work	8
2.05 Before Starting Construction	8
2.06 Preconstruction Conference.....	9
2.07 Initial Acceptance of Schedules	9
ARTICLE 3 - CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE	9
3.01 Intent	9
3.02 Reference Standards	10
3.03 Reporting and Resolving Discrepancies	10
3.04 Amending and Supplementing Contract Documents	10
3.05 Reuse of Documents.....	11
ARTICLE 4 - AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS; REFERENCE POINTS	11
4.01 Availability of Lands.....	11
4.02 Subsurface and Physical Conditions.....	12
4.03 Differing Subsurface or Physical Conditions	12
4.04 Underground Facilities	13
4.05 Reference Points.....	14
4.06 Hazardous Environmental Condition at Site.....	15
ARTICLE 5 - BONDS AND INSURANCE	16
5.01 Performance, Payment, and Other Bonds	16
5.02 Licenses Sureties and Insurers	16
5.03 Certificates of Insurance	16
5.04 CONTRACTOR's Liability Insurance	16
5.05 Property Insurance	18
5.06 Waiver of Rights.....	18
ARTICLE 6 - CONTRACTOR'S RESPONSIBILITIES	19
6.01 Supervision and Superintendence	19
6.02 Labor; Working Hours	19
6.03 Services, Materials, and Equipment.....	19
6.04 Progress Schedule.....	20
6.05 Substitutes and "Or-Equals"	20
6.06 Concerning Subcontractors, Suppliers, and Others.....	21
6.07 Patent Fees and Royalties	22
6.08 Permits	23
6.09 Laws and Regulations	23
6.10 Taxes	25
6.11 Use of Site and Other Areas	25
6.12 Record Documents	26
6.13 Safety and Protection	27
6.14 Safety Representative	28

6.15 Hazard Communication Programs	28
6.16 Emergencies	28
6.17 Shop drawings and Samples	28
6.18 Continuing The Work	29
6.19 CONTRACTOR's General Warranty and Guarantee.....	29
6.20 Indemnification.....	30
ARTICLE 7 - OTHER WORK.....	31
7.01 Related Work at Site.....	31
7.02 Coordination.....	31
ARTICLE 8 - OWNER'S RESPONSIBILITIES	31
8.01 Communications to Contractor	31
8.02 Replacement of ENGINEER.....	32
8.03 Furnish Data	32
8.04 Pay Promptly When Due.....	32
8.05 Lands and Easements; Reports and Tests.....	32
8.06 Insurance	32
8.07 Change Orders	32
8.08 Inspections, Tests, and Approvals	32
8.09 Limitations on OWNER's Responsibilities	32
8.10 Undisclosed Hazardous Environmental Condition.....	32
8.11 Evidence of Financial Arrangements	32
ARTICLE 9 - ENGINEER'S STATUS DURING CONSTRUCTION	33
9.01 OWNER's Representative	33
9.02 Visits to Site	33
9.03 Project Representative.....	33
9.04 Clarifications and Interpretations	33
9.05 Authorized Variations in Work.....	33
9.06 Rejecting Defective Work	34
9.07 Shop Drawings, Change Orders and Payments	34
9.08 Determinations for Unit Price Work	34
9.09 Decisions on Requirements of Contract Documents and Acceptability of Work	34
9.10 Limitations on ENGINEER's Authority and Responsibilities	34
ARTICLE 10 - CHANGES IN THE WORK; CLAIMS.....	35
10.01 Authorized Changes in the Work	35
10.02 Unauthorized Changes in the Work.....	35
10.03 Execution of Change Orders.....	35
10.04 Notification to Surety	35
10.05 Disputes – Not Insurance Related	36
ARTICLE 11 - COST OF THE WORK; CASH ALLOWANCES; UNIT PRICE WORK	36
11.01 Cost of the Work	36
11.02 Cash Allowances.....	39
11.03 Unit Price Work.....	39
ARTICLE 12 - CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIMES	39
12.01 Change of Contract Price.....	39
12.02 Change of Contract Times	40
12.03 Delays Beyond CONTRACTOR's Control	40
12.04 Delays Within CONTRACTOR's Control	41
12.05 Delays Beyond OWNER's and CONTRACTOR's Control.....	41
12.06 Delay Damages.....	41

ARTICLE 13 - TESTS AND INSPECTIONS; CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK	41
13.01 Notice of Defects	41
13.02 Access to Work	41
13.03 Tests and Inspections	41
13.04 Uncovering Work	42
13.05 OWNER May Stop the Work	43
13.06 Correction or Removal of Defective Work	43
13.07 Correction Period	43
13.08 Acceptance of Defective Work	43
13.09 OWNER May Correct Defective Work	44
ARTICLE 14 - PAYMENTS TO CONTRACTOR AND COMPLETION	44
14.01 Schedule of Values	44
14.02 Progress Payment	44
14.03 CONTRACTOR'S Warranty of Title	46
14.04 Substantial Completion	46
14.05 Partial Utilization	47
14.06 Final Inspection	47
14.07 Final Payment	48
14.08 Final Completion Delayed	48
14.09 Waiver of Claims	49
ARTICLE 15 - SUSPENSION OF WORK AND TERMINATION	49
15.01 OWNER May Suspend Work	49
15.02 OWNER May Terminate for Cause	49
15.03 OWNER May Terminate For Convenience	50
15.04 CONTRACTOR May Stop Work or Terminate	51
ARTICLE 16 - DISPUTE RESOLUTION.....	51
16.01 Methods and Procedures	51
ARTICLE 17 - MISCELLANEOUS.....	51
17.01 Giving Notice	51
17.02 Computation of Times	51
17.03 Cumulative Remedies	52
17.04 Survival of Obligations	52
17.05 Controlling Law	52
17.06 Access to Records	52
17.07 Road Closures and Traffic Delays	52
17.08 Prohibited Interest	52

GENERAL CONDITIONS

ARTICLE 1 - DEFINITIONS AND TERMINOLOGY

1.01 *Defined Terms*

A. Wherever used in the Contract Documents and printed with initial or all capital letters, the terms listed below will have the meanings indicated which are applicable to both the singular and plural thereof.

1. *Addenda*--Written or graphic instruments issued prior to the opening of Bids, which clarify, correct, or change the Bidding Requirements or the Contract Documents.

2. *Agreement*--The written instrument which is evidence of the agreement between OWNER and CONTRACTOR covering the Work.

3. *Application for Payment*--The form acceptable to ENGINEER which is to be used by CONTRACTOR during the course of the Work in requesting progress or final payments and which is to be accompanied by such supporting documentation as is required by the Contract Documents.

4. *Asbestos*--Any material that contains more than one percent asbestos and is friable or is releasing asbestos fibers into the air above current action levels established by the United States Occupational Safety and Health Administration.

5. *Bid*--The offer or proposal of a bidder submitted on the prescribed form setting forth the prices for the Work to be performed.

6. *Bidding Documents*--The Bidding Requirements and the proposed Contract Documents (including all Addenda issued prior to receipt of Bids).

7. *Bidding Requirements*--The Advertisement or Invitation to Bid, Instructions to Bidders, Bid security form, if any, and the Bid form with any supplements.

8. *Bonds*--Performance and payment bonds and other instruments of security.

9. *Change Order*--A document recommended by ENGINEER which is signed by CONTRACTOR and OWNER and authorizes an addition, deletion, or revision in the Work or an adjustment in the Contract Price or the Contract Times, issued on or after the Effective Date of the Agreement.

10. *Claim*--A demand or assertion by OWNER or CONTRACTOR seeking an adjustment of Contract Price or Contract Times, or both, or other relief with respect to the terms of the Contract. A demand for money or services by a third party is not a Claim.

11. *Contract*--The entire and integrated written agreement between the OWNER and CONTRACTOR concerning the Work. The contract supersedes prior negotiations, representations, or agreements, whether written or oral.

12. *Contract Documents*--The Contract Documents establish the rights and obligations of the parties and include the Agreement, Addenda (which pertain to the Contract Documents), CONTRACTOR's Bid (including documentation accompanying the Bid and any post Bid documentation submitted prior to the Notice of Award) when attached as an exhibit to the Agreement, the Notice to Proceed, the Bonds, these General Conditions, the Supplementary Conditions, the Specifications, the Drawings and the Purchases Order as the same are more specifically identified in the Agreement, together with all Written Amendments, Change Orders, Field Orders, and ENGINEER's written interpretations and clarifications issued on or after the Effective Date Of the Agreement. Approved Shop Drawings and the reports and drawings of subsurface and physical conditions are not Contract Documents. Only printed or hard copies of the items listed in this paragraph are Contract Documents. Files in

electronic media format of text, data, graphics, and the like that may be furnished by OWNER to CONTRACTOR are not Contract Documents.

13. *Contract Price*--The moneys payable by OWNER to CONTRACTOR for completion of the Work in accordance with the Contract Documents as stated in the Agreement (subject to the provisions of paragraph 11.03 in the case of Unit Price Work).

14. *Contract Times*--The number of days or the dates stated in the Agreement to: (i) achieve Substantial Completion; and (ii) complete the Work so that it is ready for final payment as evidenced by ENGINEER's written recommendation of final payment.

15. *CONTRACTOR*--The individual or entity with whom OWNER has entered into the Agreement.

16. *Cost of the Work*--See paragraph 11.01.A for definition.

17. *Drawings*--That part of the Contract Documents prepared or approved by ENGINEER which graphically shows the scope, extent, and character of the Work to be performed by CONTRACTOR. Shop Drawings and other CONTRACTOR submittals are not Drawings as so defined.

18. *Effective Date of the Agreement*--The date indicated in the Agreement on which it becomes effective, but if no such date is indicated, it means the date on which the Agreement is signed and delivered by the last of the two parties to sign and deliver.

19. *ENGINEER*--The individual or entity named as such in the Agreement.

20. *ENGINEER's Consultant*--An individual or entity having a contract with ENGINEER to furnish services as ENGINEER's independent professional associate or consultant with respect to the Project and who is identified as such in the Supplementary Conditions.

21. *Field Order*--A written order issued by ENGINEER which requires minor changes in the Work but which does not involve a change in the Contract Price or the Contract Times.

22. *General Requirements*--Sections of Division 1 of the Specifications. The General Requirements pertain to all sections of the Specifications.

23. *Hazardous Environmental Condition*--The presence at the Site of Asbestos, PCBs, Petroleum, Hazardous Waste, or Radioactive Material in such quantities or circumstances that may present a substantial danger to persons or property exposed thereto in connection with the Work.

24. *Hazardous Waste*--The term Hazardous Waste shall have the meaning provided in Section 1004 of the Solid Waste Disposal Act (42 USC Section 6903) as amended from time to time.

25. *Laws and Regulations; Laws or Regulations*--Any and all applicable laws, rules, regulations, ordinances, codes, and orders of any and all governmental bodies, agencies, authorities, and courts having jurisdiction.

26. *Liens*--Charges, security interests, or encumbrances upon Project funds, real property, or personal property.

27. *Milestone*--A principal event specified in the Contract Documents relating to an intermediate completion date or time prior to Substantial Completion of all the Work.

28. *Notice of Award*--The written notice by OWNER to the apparent successful bidder stating that upon timely compliance by the apparent successful bidder with the conditions precedent listed therein, OWNER will sign and deliver the Agreement.

29. *Notice to Proceed*--A written notice given by OWNER to CONTRACTOR fixing the date on which the Contract Times will commence to run and on which CONTRACTOR shall start to perform the Work under the Contract Documents.
30. *OWNER*--The individual, entity, public body, or authority with whom CONTRACTOR has entered into the Agreement and for whom the Work is to be performed.
31. *Partial Utilization*--Use by OWNER of a substantially completed part of the Work for the purpose for which it is intended (or a related purpose) prior to Substantial Completion of all the Work.
32. *PCB's*--Polychlorinated biphenyls.
33. *Petroleum*--Petroleum, including crude oil or any fraction thereof which is liquid at standard conditions of temperature and pressure (60 degrees Fahrenheit and 14.7 pounds per square inch absolute), such as oil, petroleum, fuel oil, oil sludge, oil refuse, gasoline, kerosene, and oil mixed with other non-Hazardous Waste and crude oils.
34. *Project*--The total construction of which the Work to be performed under the Contract Documents may be the whole, or a part as may be indicated elsewhere in the contract Documents.
35. *Project Manual*--The bound documentary information prepared for bidding and constructing the Work. A listing of the contents of the Project Manual, which may be bound in one or more volumes, is contained in the table(s) of contents.
36. *Radioactive Material*--Source, special nuclear, or byproduct material as defined by the Atomic Energy Act of 1954 (42 USC Section 2011 et seq.) as amended from time to time.
37. *Resident Project Representative*--The authorized representative of ENGINEER who may be assigned to the Site or any part thereof.
38. *Samples*--Physical examples of materials, equipment, or workmanship that are representative of some portion of the Work and which establish the standards by which such portion of the Work will be judged.
39. *Shop Drawings*--All drawings, diagrams, illustrations, schedules, and other data or information which are specifically prepared or assembled by or for CONTRACTOR and submitted by CONTRACTOR to illustrate some portion of the Work.
40. *Site*--Lands or areas indicated in the Contract Documents as being furnished by OWNER upon which the Work is to be performed, including rights-of-way and easements for access thereto, and such other lands furnished by OWNER which are designated for the use of CONTRACTOR.
41. *Specifications*--That part of the Contract Documents consisting of written technical descriptions of materials, equipment, systems, standards, and workmanship as applied to the Work and certain administrative details applicable thereto.
42. *Subcontractor*--An individual or entity having a direct contract with CONTRACTOR or with any other Subcontractor for the performance of a part of the Work at the Site.
43. *Substantial Completion*--The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of ENGINEER, the Work (or a specified part thereof) is sufficiently complete, in accordance with the Contract Documents, so that the Work (or a specified part thereof) can be utilized for the purposes for which it is intended. The terms "substantially complete" and "substantially completed" as applied to all or part of the Work refer to Substantial Completion thereof.
44. *Supplementary Conditions*--That part of the Contract Documents which amends or supplements these General Conditions.

45. *Supplier*--A manufacturer, fabricator, supplier, distributor, material man, or vendor having a direct contract with CONTRACTOR or with any Subcontractor to furnish materials or equipment to be incorporated in the Work by CONTRACTOR or any Subcontractor.

46. *Underground Facilities*--All underground pipelines, conduits, ducts, cables, wires, manholes, vaults, tanks, tunnels, or other such facilities or attachments, and any encasements containing such facilities, including those that convey electricity, gases, steam, liquid petroleum products, telephone or other communications, cable television, water, wastewater, storm water, other liquids or chemicals, or traffic or other control systems.

47. *Unit Price Work*--Work to be paid for on the basis of unit prices.

48. *Work*--The entire completed construction or the various separately identifiable parts thereof required to be provided in the Contract Documents. Work includes and is the result of performing or providing all labor, services, and documentation necessary to produce such construction, and furnishing, installing, and incorporating all materials and equipment into such construction, all as required by the Contract Documents.

49. *Written Amendment*--A written statement modifying the Contract Documents, signed by OWNER and CONTRACTOR on or after the Effective Date of the Agreement and normally dealing with the nonengineering or nontechnical rather than strictly construction-related aspects of the Contract Documents.

1.02 Terminology

A. Intent of Certain Terms or Adjectives

1. Whenever in the Contract Documents the terms "as allows," "as approved," or terms of like effect or import are used, or the adjectives "reasonable," "suitable," "acceptable," "proper," "satisfactory," or adjectives of like effect or import are used to describe an action or determination of ENGINEER as to the Work, it is intended that such action or determination will be solely to evaluate, in general, the completed Work for compliance with the requirements of and information in the Contract Documents and conformance with the design concept of the completed Project as a functioning whole as shown or indicated in the Contract Documents (unless there is a specific statement indicating otherwise). The use of any such term or adjective shall not be effective to assign to ENGINEER any duty or authority to supervise or direct the performance of the Work or any duty or authority to undertake responsibility contrary to the provisions of paragraph 9.10 or any other provision of the Contract Documents.

B. Day

1. The work "day" shall constitute a calendar day of regular working hours except Saturdays, Sundays and any legal holiday.

C. Defective

1. The word "defective," when modifying the work "Work," refers to Work that is unsatisfactory, faulty, or deficient in that it does not conform to the Contract Documents or does not meet the requirements of any inspection, reference standard, test, or approval referred to in the Contract Documents, or has been damaged prior to ENGINEER's recommendation of final payment (unless responsibility for the protection thereof has been assumed by OWNER at Substantial Completion in accordance with paragraph 14.04 or 14.05).

D. Furnish, Install, Perform, Provide

1. The word "furnish," when used in connection with services, materials, or equipment, shall mean to supply and deliver said services, materials, or equipment to the Site (or some other specified location) ready for use or installation and in usable or operable condition.

2. The word "install," when used in connection with services, materials, or equipment, shall mean to furnish and install said services, materials, or equipment complete and ready for intended use.

3. The words "perform" or "Provide," when used in connection with services, materials, or equipment, shall mean to furnish and install said services, materials, or equipment complete and ready for intended use.

4. When "furnish," "install," "perform," or "provide" is not used in connection with services, materials, or equipment in a context clearly requiring an obligation of CONTRACTOR, "provide" is implied.

E. Unless stated otherwise in the Contract Documents, words or phrases which have a well-known technical or construction industry or trade meaning are used in the Contract Documents in accordance with such recognized meaning.

ARTICLE 2 - PRELIMINARY MATTERS

2.01 Delivery of Bonds

A. When CONTRACTOR delivers the executed Agreements to OWNER, CONTRACTOR shall also deliver to OWNER such Bonds as CONTRACTOR may be required to furnish.

2.02 Copies of Documents

A. OWNER shall furnish to CONTRACTOR up to 5 copies of the Contract Documents as are reasonably necessary for execution of the Work. Additional copies will be furnished upon request at the cost of reproduction.

2.03 Commencement of Contract Times; Notice to Proceed

A. The Contract Times will commence to run on the day indicated in the Notice to Proceed

2.04 Starting the Work

A. CONTRACTOR shall start to perform the Work on the date when the Contract Times commence to run. No Work shall be done at the Site prior to the date on which the Contract Times commence to run.

2.05 Before Starting Construction

A. *CONTRACTOR's Review of Contract Documents:* Before undertaking each part of the Work, CONTRACTOR shall carefully study and compare the Contract Documents and check and verify pertinent figures therein and all applicable field measurements. CONTRACTOR shall promptly report in writing to ENGINEER any conflict, error, ambiguity, or discrepancy which CONTRACTOR may discover and shall obtain a written interpretation or clarification from ENGINEER before proceeding with any Work affected thereby; however, CONTRACTOR shall not be liable to OWNER or ENGINEER for failure to report any conflict, error, ambiguity, or discrepancy in the Contract Documents unless CONTRACTOR knew or reasonably should have known thereof.

B. *Preliminary Schedules:* Within ten days after the effective Date of the Agreement (unless otherwise specified in the General Requirements), CONTRACTOR shall submit to ENGINEER for its timely review:

1. A preliminary progress schedule indicating the times (numbers of days or dates) for starting and completing the various stages of the Work, including any Milestones specified in the Contract Documents;
2. A preliminary schedule of Shop Drawing and Sample submittals which will list each required submittal and the times for submitting, reviewing, and processing such submittal; and
3. A preliminary schedule of values for all of the Work which includes quantities and prices of items which when added together equal the Contract Price and subdivides the Work into component parts in sufficient detail to serve as the basis for progress payments during performance of the Work. Such prices will include an appropriate amount of overhead and profit applicable to each item of Work.

3. A preliminary schedule of values for all of the Work which includes quantities and prices of items which when added together equal the Contract Price and subdivides the Work into component parts in sufficient detail to serve as the basis for progress payments during performance of the Work. Such prices will include an appropriate amount of overhead and profit applicable to each item of Work.

C. *Evidence of Insurance*: Before any Work at the Site is started, CONTRACTOR and OWNER shall each deliver to the other, with copies to each additional insured identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance which either of them or any additional insured may reasonably request) which CONTRACTOR and OWNER respectively are required to purchase and maintain in accordance with Article 5.

2.06 Preconstruction Conference

A. Within 20 days after the Contract times start to run, but before any Work at the Site is started, a conference attended by CONTRACTOR, ENGINEER, and others as appropriate will be held to establish a working understanding among the parties as to the Work and to discuss the schedules referred to in paragraph 2.05.B, procedures for handling Shop Drawings and other submittals, processing Applications for Payment, and maintaining required records.

2.07 Initial Acceptance of Schedules

A. Unless otherwise provided in the Contract Documents, at least ten days before submission of the first Application for Payment a conference attended by CONTRACTOR, ENGINEER, and others as appropriate will be held to review for acceptability to ENGINEER as provided below the schedules submitted in accordance with paragraph 2.05.B. CONTRACTOR shall have an additional ten days to make corrections and adjustments and to complete and resubmit the schedules. No progress payment shall be made to CONTRACTOR until acceptable schedules are submitted to ENGINEER.

1. The progress schedule will be acceptable to ENGINEER if it provides an orderly progression of the Work to completion within any specified Milestones and the Contract Times. Such acceptance will not impose on ENGINEER responsibility for the progress schedule, for sequencing, scheduling, or progress of the Work nor interfere with or relieve CONTRACTOR from CONTRACTOR's full responsibility therefore.

2. CONTRACTOR's schedule of Shop Drawing and Sample submittals will be acceptable to ENGINEER if it provides a workable arrangement for reviewing and processing the required submittals.

3. CONTRACTOR's schedule of values will be acceptable to ENGINEER as to form and substance if it provides a reasonable allocation of the Contract Price to component parts of the Work.

ARTICLE 3 - CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE

3.01 Intent

A. The Contract Documents are complementary; what is called for by one is as binding as if called for by all.

B. It is the intent of the Contract documents to describe a functionally complete Project (or part thereof) to be constructed in accordance with the Contract Documents. Any labor, documentation, services, materials, or equipment that may reasonably be inferred from the Contract Documents or from prevailing custom or trade usage as being required to produce the intended result will be provided whether or not specifically called for at no additional cost to OWNER.

C. Clarifications and interpretations of the Contract Documents shall be issued by ENGINEER as provided in Article 9.

3.02 Reference Standards

A. Standards, Specifications, Codes, Laws, and Regulations

1. Reference to standards, specifications, manuals, or codes of any technical society, organization, or association, or to Laws or Regulations, whether such reference be specific or by implication, shall mean the standard, specification, manual, code, or Laws or Regulations in effect at the time of opening of Bids (or on the Effective Date of the Agreement if there were no Bids), except as may be otherwise specifically stated in the Contract Documents.

2. No provision of any such standard, specification, manual or code, or any instruction of a Supplier shall be effective to change the duties or responsibilities of OWNER, CONTRACTOR, or ENGINEER, or any of their subcontractors, consultants, agents, or employees from those set forth in the Contract Documents, nor shall any such provision or instruction be effective to assign to OWNER, ENGINEER, or any of ENGINEER's Consultants, agents, or employees any duty or authority to supervise or direct the performance of the Work or any duty or authority to undertake responsibility inconsistent with the provisions of the Contract Document.

3.03 Reporting and Resolving Discrepancies

A. Reporting Discrepancies

1. If, during the performance of the Work, CONTRACTOR discovers any conflict, error, ambiguity, or discrepancy within the Contract Documents or between the Contract Documents and any provision of any Law or Regulation applicable to the performance of the Work or of any standard, specification, manual or code, or of any instruction of any Supplier, CONTRACTOR shall report it to ENGINEER in writing at once. CONTRACTOR shall not proceed with the Work affected thereby (except in an emergency as required by paragraph 6.16A) until an amendment or supplement to the Contract Documents has been issued by one of the methods indicated in paragraph 3.04; provided, however, that CONTRACTOR shall not be liable to OWNER or ENGINEER for failure to report any such conflict, error, ambiguity, or discrepancy unless CONTRACTOR knew or reasonably should have known thereof.

2. In case of discrepancy, calculated dimensions will govern over scaled dimensions, Drawings will govern over Standard Specifications, and Construction Specifications will govern over both Drawings and Standard Specifications. The CONTRACTOR shall take no advantage of any apparent error or omission in the Drawings or Construction Specifications, and the ENGINEER will be permitted to make such corrections and interpretations as may be deemed necessary to fulfill the intent of the Contract Documents.

B. Resolving Discrepancies

1. Except as may be otherwise specifically stated in the Contract Documents, the provisions of the Contract Documents shall take precedence in resolving any conflict, error, ambiguity, or discrepancy between the provisions of the Contract Documents and:

- a. The provisions of any standard, specification, manual, code, or instruction (whether or not specifically incorporated by reference in the Contract Documents); or
- b. The provisions of any Laws or Regulations applicable to the performance of the Work (unless such an interpretation of the provisions of the Contract Documents would result in violation of such Law or Regulation).

3.04 Amending and Supplementing Contract Documents

A. The Contract Documents may be amended to provide for additions, deletions, and revisions in the Work or to modify the terms and conditions thereof in one or more of the following ways: (i) a Written Amendment, or (ii) a Change Order; or B. The requirements of the Contract Documents may be supplemented and minor variations and deviations in the Work may be authorized, by one or more of the following ways: (i) a Field Order; (ii) ENGINEER's approval of a Shop Drawing or Sample; or (iii) ENGINEER's written interpretation or clarification.

3.05 Reuse of Documents

A. CONTRACTOR and any Subcontractor or Supplier or other individual or entity performing or furnishing any of the Work under a direct or indirect contract with OWNER: (i) shall not have or acquire any title to or ownership rights in any of the Drawings, Specifications, or other documents (or copies of any thereof) prepared by or bearing the seal of ENGINEER or ENGINEER's Consultant, including electronic media editions. This prohibition will survive final payment, completion, and acceptance of the Work, or termination or completion of the Contract. Nothing herein shall preclude CONTRACTOR from retaining copies of the Contract Documents for record purposes.

ARTICLE 4 - AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS; REFERENCE POINTS

4.01 Availability of Lands

A. OWNER shall furnish the Site. OWNER shall notify CONTRACTOR of any encumbrances or restrictions not of general application but specifically related to use of the Site with which CONTRACTOR must comply in performing the Work. OWNER will obtain in a timely manner and pay for easements for permanent structures or permanent changes in existing facilities. If CONTRACTOR and OWNER are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, as a result of any delay in OWNER's furnishing the Site, CONTRACTOR may make a Claim therefore as provided in paragraph 10.05.

B. Upon reasonable written request, OWNER shall furnish CONTRACTOR with a current statement of record legal title and legal description of the lands upon which the Work is to be performed and OWNER's interest therein as necessary for giving notice of or filing a mechanic's or construction lien against such lands in accordance with applicable Laws and Regulations.

C. CONTRACTOR shall provide for all additional lands and access thereto that may be required for temporary construction facilities or storage of materials and equipment.

D. If corporate or private property interferes with the Work, CONTRACTOR shall notify, in writing, the OWNER's of such property, advising them of the nature of the interference and shall arrange to cooperate with them for the protection or disposition of such property. CONTRACTOR shall furnish the ENGINEER with copies of such notifications and with copies of any agreements between the CONTRACTOR and the property OWNER's concerning such protection or disposition.

E. CONTRACTOR shall take all necessary precautions for the protection of corporate or private property, such as walls and foundations of buildings, vaults, underground structures of public utilities, underground drainage facilities, overhead structures of public utilities, trees, shrubbery, crops, and fences contiguous to the Work, of which the Contract does not provide for removal. CONTRACTOR shall protect and carefully preserve all official survey monuments, property marks, section markers, and Geological Survey Monuments, or other similar monuments, until OWNER, or authorized Surveyor or agent has witnessed or otherwise referenced their location or relocation. CONTRACTOR shall notify the ENGINEER of the presence of any such survey or property monuments as soon as they are discovered.

F. CONTRACTOR shall be responsible for the damage or destruction of property of any character resulting from neglect, misconduct, or omission in its manner or method of execution or the non-execution of the work, or caused by defective work or the use of unsatisfactory materials, and such responsibility shall not be released until the work shall have been completed and accepted and the requirements of the Construction Specifications complied with.

G. Whenever public or private property is so damaged or destroyed, the CONTRACTOR shall at its own expense, restore such property to a condition equal to that existing before such damage or injury was done by repairing, rebuilding, or replacing it as may be directed, or the CONTRACTOR shall otherwise make good such damage or destruction in an acceptable manner. If the CONTRACTOR fails to do so, the ENGINEER may, after giving the CONTRACTOR notice in writing, proceed to repair, rebuild, or otherwise restore such property as may be deemed necessary, and the cost thereof shall be deducted from any compensation due, or which may become due, the CONTRACTOR under its Contract.

4.02 Subsurface and Physical Conditions

A. Reports and Drawings:

1. Those reports of explorations and tests of subsurface conditions at or contiguous to the Site that ENGINEER has used in preparing the Contract Documents; and
2. Those drawings of physical conditions in or relating to existing surface or subsurface structures at or contiguous to the Site (except Underground Facilities) that ENGINEER has used in preparing the Contract Documents.

B. Limited Reliance by CONTRACTOR on Technical Data Authorized:

CONTRACTOR may rely upon the general accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," CONTRACTOR may not rely upon or make any Claim against OWNER, ENGINEER, or any of ENGINEER's Consultants with respect to:

1. The completeness of such reports and drawings for CONTRACTOR's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences, and procedures of construction to be employed by CONTRACTOR, and safety precautions and programs incident thereto; or
2. Other data, interpretations, opinions, and information contained in such reports or shown or indicated in such drawings; or
3. Any CONTRACTOR interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions, or information.

C. Potential for Hazardous Materials:

Work may include excavation through, and removal of, soils potentially containing undocumented asbestos-containing or other hazardous materials. Should the CONTRACTOR, while performing work under this Contract, uncover hazardous materials, as defined in federal, state and local regulations, he/she shall immediately notify the Engineer. No further disturbance of the area shall occur until the Engineer has collected and analyzed a representative sample of the suspected material. The area shall be cordoned off and covered with 6-mil polyethylene sheeting and await further directions from the Engineer.

4.03 Differing Subsurface or Physical Conditions

A. Notice: If CONTRACTOR believes that any subsurface or physical conditions at or contiguous to the Site that is uncovered or revealed either:

1. Is of such a nature as to establish that any "technical data" on which CONTRACTOR is entitled to rely as provided in paragraph 4.02 is materially inaccurate; or
2. Is of such a nature as to require a change in the Contract Documents; or
3. Differs materially from that shown or indicated in the Contract Documents; or
4. Is of an unusual nature, and differs materially from conditions ordinarily encountered and generally recognized as inherent in work of the character provided for in the Contract Documents; then CONTRACTOR shall, promptly after becoming aware thereof and before further disturbing the subsurface or physical conditions or performing any Work in connection therewith (except in an emergency as required by paragraph 6.16.A), notify OWNER and ENGINEER in writing about such condition. CONTRACTOR shall not further disturb such condition or perform any Work in connection therewith (except as aforesaid) until receipt of written order to do so.

B. *ENGINEER's Review*: After receipt of written notice as required by paragraph 4.03.A, ENGINEER will promptly review the pertinent condition, determine the necessity of OWNER's obtaining additional exploration or tests with respect thereto, and advise OWNER in writing (with a copy to CONTRACTOR) of ENGINEER'S findings and conclusions.

C. *Possible Price and Times Adjustments*

1. The Contract Price or the Contract Times, or both, will be equitably adjusted to the extent that the existence of such differing subsurface or physical condition causes an increase or decrease in CONTRACTOR's cost of, or time required for, performance of the Work; subject, however, to the following:

- a. Such condition must meet any one or more of the categories described in paragraph 4.03.A; and
- b. With respect to Work that is paid for on a Unit Price Basis, any adjustment in Contract Price will be subject to the provisions of paragraphs 9.08 and 11.03.

2. CONTRACTOR shall not be entitled to any adjustment in the Contract Price or Contract Times if:

- a. CONTRACTOR knew of the existence of such conditions at the time CONTRACTOR made a final commitment to OWNER in respect of Contract Price and Contract Times by the submission of a Bid or becoming bound under a negotiated contract; or
- b. The existence of such condition could reasonably have been discovered or revealed as a result of any examination, investigation, exploration, test, or study of the Site and Contiguous areas required by the Bidding Requirements or Contract Documents to be conducted by or for CONTRACTOR prior to CONTRACTOR's making such final commitment; or
- c. CONTRACTOR failed to give the written notice within the time and as required by paragraph 4.03.A.

3. If OWNER and CONTRACTOR are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, a Claim may be made therefore as provided in paragraph 10.05. However, OWNER, ENGINEER, and ENGINEER's Consultants shall not be liable to CONTRACTOR for any claims, costs, losses, or damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by CONTRACTOR on or in connection with any other project or anticipated project.

4.04 *Underground Facilities*

A. *Shown or Indicated*: The information and data shown or indicated in the Contract Documents with respect to existing Underground Facilities at or contiguous to the Site is based on information and data furnished to OWNER or ENGINEER by the OWNER's of such Underground Facilities, including OWNER, or by others. Unless it is otherwise expressly provided in the Supplementary Conditions:

1. OWNER and ENGINEER shall not be responsible for the accuracy or completeness of any such information or data; and
2. The cost of all of the following will be included in the Contract Price, and CONTRACTOR shall have full responsibility for:
 - a. Reviewing and checking all such information and data,
 - b. Locating all Underground Facilities shown or indicated in the Contract Documents.
 - c. Coordination of the Work with the OWNER's of such Underground Facilities, including OWNER, during construction, and

d. The safety and protection of all such Underground Facilities and repairing any damage thereto resulting from the Work.

B. Not Shown or Indicated

1. If an Underground Facility is uncovered or revealed at or contiguous to the Site which was not shown or indicated, or not shown or indicated with reasonable accuracy in the Contract Documents, CONTRACTOR shall, promptly after becoming aware thereof and before further disturbing conditions affected thereby or performing any Work in connection therewith (except in an emergency as required by paragraph 6.16.A), identify the OWNER of such Underground Facility and give written notice to that OWNER and to OWNER and ENGINEER. ENGINEER will promptly review the Underground Facility and determine the extent, if any, to which a change is required in the Contract Documents to reflect and document the consequences of the existence or location of the Underground Facility. During such time, CONTRACTOR shall be responsible for the safety and protection of such Underground Facility.

If ENGINEER concludes that a change in the Contract Documents is required, a Change Order will be issued to reflect and document such consequences. An equitable adjustment shall be made in the Contract Price or Contract Times, or both, to the extent that they are attributable to the existence or location of any Underground Facility that was not shown or indicated or not shown or indicated with reasonable accuracy in the Contract Documents and that CONTRACTOR did not know of and could not reasonably have been expected to be aware of or to have anticipated. If OWNER and CONTRACTOR are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment in Contract Price or Contract Times, OWNER or CONTRACTOR may make a Claim therefore as provided in paragraph 10.05.

CONTRACTOR shall notify the following underground utility locating service at least three full working days prior to beginning work: Dig Safe System, Inc. 1-800-344-7233.

A list of the major public utilities servicing the work area follows. The list indicates the name and telephone number of the responsible authority of the various utilities which should be notified if conflicts or emergencies arise during the progress of the work.

<u>Electricity</u> – Public Service of NH	1-800-662-7764
<u>Natural Gas</u> – Liberty Energy	1-603-222-3705
<u>Water</u> – Pennichuck Water Works	1-603-882-5191
<u>Telephone</u> – Fairpoint Communications	1-603-645-3500
<u>Cable TV</u> – Comcast	1-888-633-4266
<u>Fire Alarm Cable</u> – Nashua Fire Department	1-603-594-3641

2. At points where the CONTRACTOR's operations are adjacent to public and private utilities, CONTRACTOR shall not commence work until CONTRACTOR has made all arrangements necessary for the protection of utilities.

3. CONTRACTOR shall coordinate and cooperate with the OWNER's of any underground or overhead utility lines in their removal and rearrangement operations in order that these operations may progress in a reasonable manner, that duplication of rearrangement work may be reduced to a minimum, and that services rendered by those parties will not be unnecessarily interrupted.

4.05 Reference Points

A. OWNER shall provide engineering surveys to establish reference points for construction which in ENGINEER's judgment are necessary to enable CONTRACTOR to proceed with the Work. CONTRACTOR shall be responsible for laying out the Work, shall protect and preserve the established reference points and property monuments, and shall make no changes or relocations without the prior written approval of OWNER. CONTRACTOR shall report to ENGINEER whenever any reference point or property monument is lost or destroyed or requires relocation because of necessary changes in grades or locations, and shall be responsible for the accurate replacement or relocation of such reference points or property monuments by professionally qualified personnel.

4.06 Hazardous Environmental Condition at Site

A. Reports and Drawings: Reference is made to the Supplementary Conditions for the identification of those reports and drawings relating to a Hazardous Environmental Condition identified at the Site, if any, that have been utilized by the ENGINEER in the preparation of the Contract Documents.

B. Limited Reliance by CONTRACTOR on Technical Data Authorized: CONTRACTOR may rely upon the general accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," CONTRACTOR may not rely upon or make any Claim against OWNER, ENGINEER or any of ENGINEER's Consultants with respect to:

1. The completeness of such reports and drawings for CONTRACTOR's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences and procedures of construction to be employed by CONTRACTOR and safety precautions and programs incident thereto; or
2. Other data, interpretations, opinions and information contained in such reports or shown or indicated in such drawings; or
3. Any CONTRACTOR interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions or information.

C. CONTRACTOR shall not be responsible for any Hazardous Environmental Condition uncovered or revealed at the Site which was not shown or indicated in Drawings or Specifications or identified in the Contract Documents to be within the scope of the Work. CONTRACTOR shall be responsible for a Hazardous Environmental Condition created with any materials brought to the Site by CONTRACTOR, Subcontractors, Suppliers, or anyone else for whom CONTRACTOR is responsible.

D. If CONTRACTOR encounters a Hazardous Environmental Condition or if CONTRACTOR or anyone for whom CONTRACTOR is responsible creates a Hazardous Environmental Condition, CONTRACTOR shall immediately: (i) secure or otherwise isolate such condition; (ii) stop all Work in connection with such condition and in any area affected thereby (except in an emergency as required by paragraph 6.16); and (iii) notify OWNER and ENGINEER (and promptly thereafter confirm such notice in writing). OWNER shall promptly consult with ENGINEER concerning the necessity for OWNER to retain a qualified expert to evaluate such condition or take corrective action, if any.

E. CONTRACTOR shall not be required to resume Work in connection with such condition or in any affected area until after OWNER has obtained any required permits related thereto and delivered to CONTRACTOR written notice: (i) specifying that such condition and any affected area is or has been rendered safe for the resumption of Work; or (ii) specifying any special conditions under which such Work may be resumed safely. If OWNER and CONTRACTOR cannot agree as to entitlement to or on the amount or extent, if any, of any adjustment in Contract Price or Contract Times, or both, as a result of such Work stoppage or such special conditions under which Work is agreed to be resumed by CONTRACTOR, either party may make a Claim therefore as provided in paragraph 10.05.

F. If after receipt of such written notice CONTRACTOR does not agree to resume such Work based on a reasonable belief it is unsafe, or does not agree to resume such Work under such special conditions, then OWNER may order the portion of the Work that is in the area affected by such condition to be deleted from the Work. If OWNER and CONTRACTOR cannot agree as to entitlement to or on the amount or extent, if any, of an adjustment in Contract Price or Contract Times as a result of deleting such portion of the Work, then either party may make a Claim therefore as provided in paragraph 10.05. OWNER may have such deleted portion of the Work performed by OWNER'S own forces or others in accordance with Article 7.

G. To the fullest extent permitted by Laws and Regulations, CONTRACTOR shall indemnify and hold harmless OWNER, ENGINEER, ENGINEER's Consultants, and the officers, directors, partners, employees, agents, other consultants, and subcontractors of each and any of them from and against all claims, costs, losses, damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition created

by CONTRACTOR or by anyone for whom CONTRACTOR is responsible. Nothing in this paragraph 4.06.F shall obligate CONTRACTOR to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.

H. The provisions of paragraphs 4.02, 4.03, and 4.04 are not intended to apply to a Hazardous Environmental Condition uncovered or revealed at the Site.

ARTICLE 5 - BONDS AND INSURANCE

5.01 *Performance, Payment, and Other Bonds*

A. CONTRACTOR shall furnish performance and payment Bonds, each in an amount at least equal to the Contract Price as security for the faithful performance and payment of all CONTRACTOR's obligations under the Contract Documents. These Bonds shall remain in effect at least until one year after the date when final payment becomes due, except as provided otherwise by Laws or Regulations or by the Contract Documents. CONTRACTOR shall also furnish such other Bonds as are required by the Contract Documents.

B. All Bonds shall be in the form prescribed by the Contract Documents except as provided otherwise by Laws or Regulations, and shall be executed by such sureties as are named in the current list of "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies" as published in Circular 570 (amended) by the Financial Management Service, Surety Bond Branch, U.S. Department of the Treasury. All Bonds signed by an agent must be accompanied by a certified copy of such agent's authority to act.

C. If the surety on any Bond furnished by CONTRACTOR is declared bankrupt or becomes insolvent or its right to do business is terminated in any state where any part of the Project is located or it ceases to meet the requirements of paragraph 5.01.B, CONTRACTOR shall within 20 days thereafter substitute another Bond and surety, both of which shall comply with the requirements of paragraphs 5.01.B and 5.02.

5.02 *Licenses Sureties and Insurers*

A. All Bonds and insurance required by the Contract Documents to be purchased and maintained by CONTRACTOR shall be obtained from surety or insurance companies that are duly licensed or authorized in the jurisdiction in which the Project is located to issue Bonds or insurance policies for the limits and coverage's so required. Such surety and insurance companies shall also meet such additional requirements and qualifications as may be provided in the Supplementary Conditions.

B. All Sureties and Insurance Companies shall be authorized to do business in the State of New Hampshire and shall have an A.M. Best rating of "A(FSC-VIII)" or better. In the event that the Insurer fails to maintain an A.M. Best rating "A(FSC-VIII)" or better, the CONTRACTOR shall immediately retain a Surety which does meet the above requirements.

5.03 *Certificates of Insurance*

A. CONTRACTOR shall deliver to OWNER 10 days prior to Work, with copies to each additional insured identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance requested by OWNER or any other additional insured) which CONTRACTOR is required to purchase and maintain.

5.04 *CONTRACTOR's Liability Insurance*

A. CONTRACTOR shall purchase and maintain such liability and other insurance as is required by OWNER which will provide protection from claims which may arise out of or result from CONTRACTOR's performance of the Work and CONTRACTOR's other obligations under the Contract Documents, whether it is to be performed by CONTRACTOR, any Subcontractor or Supplier, or by anyone directly or indirectly employed by any of them to perform any of the Work, or by anyone for whose acts any of them may be liable.

B. The policies of insurance so required by this paragraph 5.04 to be purchased and maintained shall:

1. Include as additional insured (subject to any customary exclusion in respect of professional liability) OWNER, ENGINEER.

2. The CONTRACTOR must maintain the following lines of coverage and policy limits for the duration of the contract. Any subcontractors used by the CONTRACTOR are subject to the same coverage and limits and is a subcontractor of the CONTRACTOR and not the OWNER. It is the responsibility of the CONTRACTOR to update Certificates of Insurance during the term of the contract. Provide coverage for not less than the following amounts or greater:

General Liability

\$1,000,000 per Occurrence

\$2,000,000 Aggregate

City of Nashua Additional Insured

Motor Vehicle Liability *coverage must include all owned, non-owned and hired vehicles.

\$1,000,000 Combined Single Limit

Automobile Liability

City of Nashua Additional Insured

Workers' Compensation Coverage according to Statute of the State of New Hampshire:

\$100,000 / \$500,000 / \$100,000

All bidders and subcontractors at every tier under the bidder will fully comply with NH RSA Chapter 281-A, "Workers' Compensation".

It is the responsibility of the contractor to submit to the City of Nashua certificates of insurance for all subcontractors prior to the start of the project. It is the responsibility of the contractor to provide the City with updated certificates of insurance for the contractor and all subcontractors 10 days prior to the expiration of coverage. The City may, at any time, order the contractor to stop work, suspend the contract or terminate the contract for non-compliance. All subcontractors are subject to the same insurance requirements as the contractor.

3. Include completed operations insurance;

4. Include contractual liability insurance covering CONTRACTOR's indemnity obligations under paragraphs 6.07, 6.11, and 6.20;

5. Contain a provision or endorsement that the coverage afforded will not be canceled, materially changed or renewal refused until at least thirty days prior written notice has been given to OWNER and CONTRACTOR and to each other additional insured identified in the Supplementary Conditions to whom a certificate of insurance has been issued (and the certificates of insurance furnished by the CONTRACTOR pursuant to paragraph 5.03 will so provide);

6. Remain in effect until final payment and at all times thereafter when CONTRACTOR may be correcting, removing or replacing defective Work in accordance with paragraph 13.07; and

7. With respect to completed operations insurance, and any insurance coverage written on a claims-made basis, remain in effect for at least two years after final payment (and CONTRACTOR shall furnish OWNER and each other additional insured identified in the Supplementary Conditions, to whom a certificate of insurance has been issued, evidence satisfactory to OWNER and any such additional insured of continuation of such insurance at final payment and one year thereafter).

B. CONTRACTOR agrees to maintain all required insurance coverage throughout the entire term of the contract. If CONTRACTOR does not maintain coverage throughout the entire term of the contract, CONTRACTOR agrees that OWNER may, at any time the coverage is not maintained by CONTRACTOR, order the CONTRACTOR to stop work,

suspend the contract, or terminate the contract. CONTRACTOR further agrees, if applicable, as a precondition to the performance of any work under this contract and as a precondition to any obligation of the OWNER to make any payment under this contract to provide the OWNER with a certificate of a qualified insurer.

5.05 *Property Insurance*

A. CONTRACTOR must purchase and maintain property insurance upon the Work at the Site in the amount of the full replacement cost of the Work. This insurance shall:

1. include the interests of OWNER, CONTRACTOR, Subcontractors, ENGINEER, ENGINEER's Consultants and any other individuals or entities identified in the Supplementary Conditions, and the officers, directors, partners, employees, agents and other consultants and subcontractors of any of them each of whom is deemed to have an insurable interest and shall be listed as an insured or additional insured;
2. include expenses incurred in the repair or replacement of any insured property (including but not limited to fees and charges of engineers and architects);
3. cover materials and equipment stored at the Site or at another location that was agreed to in writing by OWNER prior to being incorporated in the Work, provided that the materials and equipment have been included in an application for payment recommended by ENGINEER; and
4. allow for partial utilization of the Work by OWNER;
5. include testing and startup; and
6. be maintained in effect until final payment is made unless otherwise agreed to in writing by OWNER, CONTRACTOR and ENGINEER with 30 days written notice to each other additional insured to whom a certificate of insurance has been issued.

B. CONTRACTOR shall be responsible for any deductible or self-insured retention. The risk of loss within the identified deductible amount will be borne by CONTRACTOR, Subcontractors, or others suffering any such loss, and if any of them wishes property insurance coverage within the limits of such amounts, each may purchase and maintain it at the purchaser's own expense. OWNER shall not be responsible for purchasing and maintaining any property insurance specified in this paragraph 5.06 to protect the interests of CONTRACTOR, Subcontractors, or others in the Work to the extent of any deductible amounts that are identified in the Supplementary Conditions.

C. All the policies of insurance (and the certificates or other evidence of the policy) required to be purchased and maintained in accordance with paragraph 5.06 will contain a provision or endorsement that the coverage afforded will not be canceled or materially changed or renewal refused until at least 30 days after written notice has been given to OWNER and CONTRACTOR and to each other additional insured to whom a certificate of insurance has been issued and will contain waiver provisions in accordance with paragraph 5.07.

5.06 *Waiver of Rights*

A. CONTRACTOR intends that all policies purchased in accordance with paragraph 5.06 will protect OWNER, CONTRACTOR, Subcontractors, ENGINEER, ENGINEER's Consultants, and all other individuals or entities identified in the Supplementary Conditions to be listed as insured (and the officers, directors, partners, employees, agents, and other consultants and subcontractors of each and any of them) in such policies and will provide primary coverage for all losses and damages caused by the perils or causes of loss covered by the policy. All CONTRACTOR policies must contain provisions to the effect that in the event of payment of any loss or damage the insurers will have no rights of recovery against any of the insured or additional insured there under. CONTRACTOR waive all rights against OWNER each other and their respective officers, directors, partners, employees, agents, and other consultants and subcontractors of each and any of them for all losses and damages caused by, arising out of or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work; and, in addition, waive all such rights against Subcontractors, ENGINEER, ENGINEER's Consultants, and all other individuals

or entities identified in the Supplementary Conditions to be listed as insured or additional insured (and the officers, directors, partners, employees, agents, and other consultants and subcontractors of each and any of them) under such policies for losses and damages so caused.

ARTICLE 6 - CONTRACTOR'S RESPONSIBILITIES

6.01 *Supervision and Superintendence*

A. CONTRACTOR shall supervise, inspect, and direct the Work competently and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the Work in accordance with the Contract Documents. CONTRACTOR shall be solely responsible for the means, methods, techniques, sequences, and procedures of construction, but CONTRACTOR shall not be responsible for the negligence of OWNER or ENGINEER in the design or specification of a specific means, method, technique, sequence, or procedure of construction which is shown or indicated in and expressly required by the Contract Documents. CONTRACTOR shall be responsible to see that the completed Work complies accurately with the Contract Documents.

B. At all times during the progress of the Work, CONTRACTOR shall assign a competent resident superintendent thereto who shall not be replaced without written notice to OWNER and ENGINEER except under extraordinary circumstances. The superintendent will be CONTRACTOR's representative at the Site and shall have authority to act on behalf of CONTRACTOR. All communications given to or received from the superintendent shall be binding on CONTRACTOR.

6.02 *Labor; Working Hours*

A. CONTRACTOR shall provide competent, suitably qualified personnel to survey, lay out, and construct the Work as required by the Contract Documents. CONTRACTOR shall at all times maintain good discipline and order at the Site.

B. Except as otherwise required for the safety or protection of persons or the Work or property at the Site or adjacent thereto, and except as otherwise stated in the Contract Documents, all Work at the Site shall be performed during regular working hours, and CONTRACTOR will not permit overtime work or the performance of Work on Saturday, Sunday, or any legal holiday without OWNER's written consent (which will not be unreasonably withheld) given after prior written notice to ENGINEER.

C. The following list of streets may not be opened or worked in between the hours of 7:00 AM and 9:00 AM and 3:00 PM and 6:00 PM, Monday through Friday of each week:

***Broad Street
East Hollis Street
Concord Street
Amherst Street
D. W. Highway
Kinsley Street
East Dunstable Road
Main Street***

6.03 *Services, Materials, and Equipment*

A. Unless otherwise specified in the General Requirements, CONTRACTOR shall provide and assume full responsibility for all services, materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, temporary facilities, and all other facilities and incidentals necessary for the performance, testing, start-up, and completion of the Work.

B. All materials and equipment incorporated into the Work shall be as specified or, if not specified, shall be of good quality and new, except as otherwise provided in the Contract Documents. All warranties and guarantees specifically called for by the Specifications shall expressly run to the benefit of OWNER. If required by ENGINEER, CONTRACTOR shall furnish satisfactory evidence (including reports of required tests) as to the source, kind, and

quality of materials and equipment. All materials and equipment shall be stored, applied, installed, connected, erected, protected, used, cleaned, and conditioned in accordance with instructions of the applicable Supplier, except as otherwise may be provided in the Contract Documents.

6.04 Progress Schedule

A. CONTRACTOR shall adhere to the progress schedule established in accordance with paragraph 2.07 as it may be adjusted from time to time as provided below.

1. CONTRACTOR shall submit to ENGINEER for acceptance (to the extent indicated in paragraph 2.07) proposed adjustments in the progress schedule that will not result in changing the Contract Times (or Milestones). Such adjustments will conform generally to the progress schedule then in effect and additionally will comply with any provisions of the General Requirements applicable thereto.

2. Proposed adjustments in the progress schedule that will change the Contract Times (or Milestones) shall be submitted in accordance with the requirements of Article 12. Such adjustments may only be made by a Change Order or Written Amendment in accordance with Article 12.

6.05 Substitutes and "Or-Equals"

A. Whenever an item of material or equipment is specified or described in the Contract Documents by using the name of a proprietary item or the name of a particular Supplier, the specification or description is intended to establish the type, function, appearance, and quality required. Unless the specification or description contains or is followed by words reading that no like, equivalent, or "or-equal" item or no substitution is permitted, other items of material or equipment or material or equipment of other Suppliers may be submitted to ENGINEER for review under the circumstances described below.

1. "Or-Equal" Items:

If in ENGINEER'S sole discretion an item of material or equipment proposed by CONTRACTOR is functionally equal to that named and sufficiently similar so that no change in related Work will be required, it may be considered by ENGINEER as an "or-equal" item, in which case review and approval of the proposed item may, in ENGINEER's sole discretion, be accomplished without compliance with some or all of the requirements for approval of proposed substitute items. For the purposes of this paragraph 6.05.A.1, a proposed item of material or equipment will be considered functionally equal to an item so named if:

- a. In the exercise of reasonable judgment ENGINEER determines that: (i) it is at least equal in quality, durability, appearance, strength, and design characteristics; (ii) it will reliably perform at least equally well the function imposed by the design concept of the completed Project as a functioning whole, and;
- b. CONTRACTOR certifies that: (i) there is no increase in cost to the OWNER; and (ii) it will conform substantially, even with deviations, to the detailed requirements of the item named in the Contract Documents.

2. Substitute Items

- a. If in ENGINEER's sole discretion an item of material or equipment proposed by CONTRACTOR does not qualify as an "or-equal" item under paragraph 6.05.A.1, it will be considered a proposed substitute item.
- b. CONTRACTOR shall submit sufficient information as provided below to allow ENGINEER to determine that the item of material or equipment proposed is essentially equivalent to that named and an acceptable substitute therefore. Requests for review of proposed substitute items of material or equipment will not be accepted by ENGINEER from anyone other than CONTRACTOR.
- c. The procedure for review by ENGINEER will be as set forth in paragraph 6.05.A.2.d, as supplemented in the General Requirements and as ENGINEER may decide is appropriate under the circumstances.

d. CONTRACTOR shall first make written application to ENGINEER for review of a proposed substitute item of material or equipment that CONTRACTOR seeks to furnish or use. The application shall certify that the proposed substitute item will perform adequately the functions and achieve the results called for by the general design, be similar in substance to that specified, and be suited to the same use as that specified. The application will state the extent, if any, to which the use of the proposed substitute item will prejudice CONTRACTOR's achievement of Substantial Completion on time, whether or not use of the proposed substitute item in the Work will require a change in any of the Contract Documents (or in the provisions of any other direct contract with OWNER for work on the Project) to adapt the design to the proposed substitute item and whether or not incorporation or use of the proposed substitute item in connection with the Work is subject to payment of any license fee or royalty. All variations of the proposed substitute item from that specified will be identified in the application, and available engineering, sales, maintenance, repair, and replacement services will be indicated. The application will also contain an itemized estimate of all costs or credits that will result directly or indirectly from use of such substitute item, including costs of redesign and claims of other contractors affected by any resulting change, all of which will be considered by ENGINEER in evaluating the proposed substitute item. ENGINEER may require CONTRACTOR to furnish additional data about the proposed substitute item.

B. *Substitute Construction Methods or Procedures*:: If a specific means, method, technique, sequence, or procedure of construction is shown or indicated in and expressly required by the Contract Documents, CONTRACTOR may furnish or utilize a substitute means, method, technique, sequence, or procedure of construction approved by ENGINEER. CONTRACTOR shall submit sufficient information to allow ENGINEER, in ENGINEER's sole discretion, to determine that the substitute proposed is equivalent to that expressly called for by the Contract Documents. The procedure for review by ENGINEER will be similar to that provided in subparagraph 6.05.A.2.

C. *Engineer's Evaluation*: ENGINEER will be allowed a reasonable time within which to evaluate each proposal or submittal made pursuant to paragraphs 6.05.A and 6.05.B. ENGINEER will be the sole judge of acceptability. No "or-equal" or substitute will be ordered, installed or utilized until ENGINEER's review is complete, which will be evidenced by either a Change Order for a substitute or an approved Shop drawing for an "or equal". ENGINEER will advise CONTRACTOR in writing of any negative determination.

D. *Special Guarantee*: OWNER may require CONTRACTOR to furnish at CONTRACTOR's expense a special performance guarantee or other surety with respect to any substitute.

E. *ENGINEER's Cost Reimbursement*: ENGINEER will record time required by ENGINEER and ENGINEER's Consultants in evaluating substitute proposed or submitted by CONTRACTOR pursuant to paragraphs 6.05.A.2 and 6.05.B and in making changes in the Contract Documents (or in the provisions of any other direct contract with OWNER for work on the Project) occasioned thereby. Whether or not ENGINEER approves a substitute item so proposed or submitted by CONTRACTOR, CONTRACTOR shall reimburse OWNER for the charges of ENGINEER and ENGINEER's Consultants for evaluating each such proposed substitute.

F. *CONTRACTOR's Expense*: CONTRACTOR shall provide all data in support of any proposed substitute or "or-equal" at CONTRACTOR's expense.

6.06 Concerning Subcontractors, Suppliers, and Others

A. CONTRACTOR shall not employ any Subcontractor, Supplier, or other individual or entity (including those acceptable to OWNER as indicated in paragraph 6.06.B), whether initially or as a replacement, against whom OWNER may have reasonable objection. CONTRACTOR shall not be required to employ any Subcontractor, Supplier, or other individual or entity to furnish or perform any of the Work against whom CONTRACTOR has reasonable objection.

B. If the Supplementary Conditions require the identity of certain Subcontractors, Suppliers, or other individuals or entities to be submitted to OWNER in advance for acceptance by OWNER by a specified date prior to the Effective Date of the Agreement, and if CONTRACTOR has submitted a list thereof in accordance with the Supplementary Conditions, OWNER's acceptance (either in writing or by failing to make written objection thereto by the date indicated for acceptance or objection in the Bidding Documents or the Contract Documents) of any such Subcontractor, Supplier,

or other individual or entity so identified may be revoked on the basis of reasonable objection after due investigation. CONTRACTOR shall submit an acceptable replacement for the rejected Subcontractor, Supplier, or other individual or entity, and the Contract Price will be adjusted by the difference in the cost occasioned by such replacement, and an appropriate Change Order will be issued or Written Amendment signed. No acceptance by OWNER of any such Subcontractor, Supplier, or other individual or entity, whether initially or as a replacement, shall constitute a waiver of any right of OWNER or ENGINEER to reject defective work.

C. CONTRACTOR shall be fully responsible to OWNER and ENGINEER for all acts and omissions of the Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work just as CONTRACTOR is responsible for CONTRACTOR's own acts and omissions. Nothing in the Contract Documents shall create for the benefit of any such Subcontractor, Supplier, or other individual or entity any contractual relationship between OWNER or ENGINEER and any such Subcontractor, Supplier or other individual or entity, nor shall it create any obligation on the part of OWNER or ENGINEER to pay or to see to the payment of any moneys due any such Subcontractor, Supplier, or other individual or entity except as may otherwise be required by Laws and Regulations.

D. CONTRACTOR shall be solely responsible for scheduling and coordinating the Work of Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work under a direct or indirect contract with CONTRACTOR.

E. CONTRACTOR shall require all Subcontractors, Suppliers, and such other individuals or entities performing or furnishing any of the Work to communicate with ENGINEER through CONTRACTOR.

F. The divisions and sections of the Specifications and the identifications of any Drawings shall not control CONTRACTOR in dividing the Work among Subcontractors or Suppliers or delineating the Work to be performed by any specific trade.

G. All Work performed for CONTRACTOR by a Subcontractor or Supplier will be pursuant to an appropriate agreement between CONTRACTOR and the Subcontractor or Supplier which specifically binds the Subcontractor or Supplier to the applicable terms and conditions of the Contract Documents for the benefit of OWNER and ENGINEER. Whenever any such agreement is with a Subcontractor or Supplier who is listed as an additional insured on the property insurance provided in paragraph 5.06, the agreement between the CONTRACTOR and the Subcontractor or Supplier will contain provisions whereby the Subcontractor or Supplier waives all rights against OWNER, CONTRACTOR, ENGINEER, ENGINEER's Consultants, and all other individuals or entities identified in the Supplementary Conditions to be listed as insured or additional insured (and the officers, directors, partners, employees, agents, and other consultants and subcontractors of each and any of them) for all losses and damages caused by, arising out of, relating to, or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work. If the insurers on any such policies require separate waiver forms to be signed by any Subcontractor or Supplier, CONTRACTOR will obtain the same.

6.07 *Patent Fees and Royalties*

A. CONTRACTOR shall pay all license fees and royalties and assume all costs incident to the use in the performance of the Work or the incorporation in the Work of any invention, design, process, product, or device which is the subject of patent rights or copyrights held by others. If a particular invention, design, process, product, or device is specified in the Contract Documents for use in the performance of the Work and if to the actual knowledge of OWNER or ENGINEER its use is subject to patent rights or copyrights calling for the payment of any license fee or royalty to others, the existence of such rights shall be disclosed by OWNER in the Contract Documents. To the fullest extent permitted by Laws and Regulations, CONTRACTOR shall indemnify and hold harmless OWNER, ENGINEER, ENGINEER's Consultants, and the officers, directors, partners, employees or agents, and other consultants of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device not specified in the Contract Documents.

6.08 Permits

A. Unless otherwise provided in the Supplementary Conditions, CONTRACTOR shall obtain and pay for all construction permits and licenses. OWNER shall assist CONTRACTOR, when necessary, in obtaining such permits and licenses. CONTRACTOR shall pay all governmental charges and inspection fees necessary for the prosecution of the Work which are applicable at the time of opening of Bids, or, if there are no Bids, on the Effective date of the Agreement. CONTRACTOR shall pay all charges of utility owners for connections to the Work, and OWNER shall pay all charges of such utility Owner's for capital costs related thereto, such as plant investment fees.

6.09 Laws and Regulations

A. CONTRACTOR shall give all notices and comply with all Laws and Regulations applicable to the performance of the Work. Except where otherwise expressly required by applicable Laws and Regulations, neither OWNER nor ENGINEER shall be responsible for monitoring CONTRACTOR's compliance with any Laws or Regulations.

B. If CONTRACTOR performs any Work knowing or having reason to know that it is contrary to Laws or Regulations, CONTRACTOR shall bear all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such Work; however, it shall not be CONTRACTOR's primary responsibility to make certain the Specifications and Drawings are in accordance with Laws and Regulations, but this shall not relieve CONTRACTOR of CONTRACTOR's obligations under paragraph 3.03.

C. Changes in Laws or Regulations not known at the time of opening of Bids (or, on the Effective Date of the Agreement if there were no Bids) having an effect on the cost or time of performance of the Work may be the subject of an adjustment in Contract Price or Contract Times. If OWNER and CONTRACTOR are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment, a Claim may be made therefore as provided in paragraph 10.05.

D. CONTRACTOR shall comply with all local laws, ordinances, and statutes, all provisions of the Revised Statutes Annotated, all provisions of the federal Davis-Bacon Act for projects with federal funding, and all regulations promulgated under either statute. Copies of the "City of Nashua Prevailing Wage Rates for Public Works", as determined by U.S. Department of Labor and "General Wage Determinations," as determined by the U.S. Department of Labor, are available for inspection at the City of Nashua Division of Public Works, 9 Riverside Street, Nashua, New Hampshire. If the provisions of the Davis-Bacon Act apply, all employees of the CONTRACTOR must be paid not less than the wage which is the greater of the Federal wage determinations. The hourly and daily rate of wages to be paid each class of mechanics and workers must be posted on the project site in a place generally visible to the employees.

E. If the Davis-Bacon Act applies, CONTRACTOR shall furnish to the OWNER within seven days after payment date of the weekly payroll period, a statement of wages paid for each of the CONTRACTOR's employees or a payroll report. If the Davis-Bacon Act applies, CONTRACTOR shall furnish to the OWNER within seven days after payment date of the weekly payroll period, a statement of wages paid for each of any subcontractor's employees or a payroll report for each subcontractor. The statement or report must include the CONTRACTOR's certification of compliance with the requirements of the supplementary condition. CONTRACTOR agrees that failure to comply with the portion of this supplementary condition requiring CONTRACTOR to furnish a certified statement of wages or payroll report will, in addition to any other retention allowed under this contract or under state or federal law, allow the OWNER to unilaterally, without notice to CONTRACTOR, retain an amount of up to 10% from each progress payment until the OWNER determines CONTRACTOR has complied with the provisions of this supplementary condition.

F. If the Davis-Bacon Act applies to work to be performed under this contract, CONTRACTOR shall furnish to the OWNER within seven days after payment date of the weekly payroll period, a statement of wages paid for each of CONTRACTOR's employees and for each of any subcontractor's employees or a payroll report from CONTRACTOR and from each subcontractor. Each statement or report must include the certification by CONTRACTOR of compliance with the provisions of the Davis-Bacon Act.

G. Workers' Compensation Coverage.

1. CONTRACTOR agrees as a precondition to the performance of any work under this contract and as a precondition to any obligation of the OWNER to make any payment under this contract to provide the OWNER with a certificate of a qualified insurer. CONTRACTOR also agrees, if applicable and before commencing any work under the contract, to complete and to provide the following written request to its insurer:

(Company Name) has entered into a contract with the City of Nashua to perform work from (starting date) to (ending date) and requests that the Insurer provide to the City of Nashua 1) a certificate of coverage and 2) notice of any lapse in coverage or nonpayment of coverage that the CONTRACTOR is required to maintain. The certificate and notice should be mailed to:

Risk Management
City of Nashua
229 Main Street
Nashua, NH 03060

2. CONTRACTOR agrees to maintain required workers' compensation coverage throughout the entire term of the contract. If CONTRACTOR does not maintain coverage throughout the entire term of the contract, CONTRACTOR agrees that OWNER may, at any time the coverage is not maintained by CONTRACTOR, order the CONTRACTOR to stop work, suspend the contract, or terminate the contract. For each six-month period this contract is in effect, CONTRACTOR agrees, prior to the expiration of the six-month period, to provide another written request to its insurer for the provision of a certificate and notice of lapse in or nonpayment of coverage. If CONTRACTOR does not make the request or does not provide the certificate before the expiration of the six-month period, CONTRACTOR agrees that OWNER may order the CONTRACTOR to stop work, suspend the contract, or terminate the contract.

H. To be deemed a responsive bid, the list of subcontractor form must be submitted even if no subcontractors are required to be listed. Submittal is as follows:

1. Each bid submitted to any officer, department, board or commission for the construction of any public work or improvement must include:

a. The name of each subcontractor who will provide labor or a portion of the work or improvement to the CONTRACTOR for which he will be paid an amount exceeding 5 percent of the prime CONTRACTOR's total bid. Within 2 hours after the completion of the opening of the bids, the general contractors who submitted the three lowest bids must submit a list of the name of each subcontractor who will provide labor or a portion of the work or improvement to the CONTRACTOR for which he will be paid an amount exceeding 1 percent of the prime CONTRACTOR's total bid or \$50,000, whichever is greater, and the number of the license issued to the subcontractor. If a general CONTRACTOR fails to submit such a list within the required time, his bid shall be deemed not responsive.

b. A description of the portion of the work or improvement which each subcontractor named in the bid will complete.

2. The CONTRACTOR shall list in his bid the name of a subcontractor for each portion of the project that will be completed by a subcontractor.

3. A CONTRACTOR whose bid is accepted shall not substitute any person for a subcontractor who is named in the bid, unless:

a. The awarding authority objects to the subcontractor, requests in writing a change in the subcontractor and pays any increase in costs resulting from the change; or

b. The substitution is approved by the awarding authority and:

(i) The subcontractor, after having a reasonable opportunity, fails or refuses to execute a written contract with the CONTRACTOR which was offered to the subcontractor with the same terms that all other subcontractors on the project were offered;

(ii) The named subcontractor files for bankruptcy or becomes insolvent; or

(iii) The named subcontractor fails or refuses to perform his subcontract within a reasonable time or is unable to furnish a performance bond and payment bond.

I. If blasting or use of explosives is necessary for prosecution of Work, the CONTRACTOR shall provide the ENGINEER with a blasting plan in compliance with OSHA, State, and local regulations, laws, ordinances, and requirements. CONTRACTOR shall exercise the utmost care not to endanger life or property. CONTRACTOR shall be responsible for all damage resulting from the use of explosives. CONTRACTOR shall notify each property OWNER and utility company having structures or facilities in proximity to the site of the work of its intentions to use explosives. Such notice shall be given sufficiently in advance to enable the utility companies to take such steps as they may deem necessary to protect their property from injury.

6.10 Taxes

A. CONTRACTOR shall pay all sales, consumer, use, and other similar taxes required to be paid by CONTRACTOR in accordance with the Laws and Regulations of the place of the Project which are applicable during the performance of the Work

6.11 Use of Site and Other Areas

A. Limitation on Use of Site and Other Areas

1. CONTRACTOR shall confine construction equipment, the storage of materials and equipment, and the operations of workers to the Site and other areas permitted by Laws and Regulations, and shall not unreasonably encumber the Site and other areas with construction equipment or other materials or equipment. CONTRACTOR shall assume full responsibility for any damage to any such land or area, or to the OWNER or occupant thereof, or of any adjacent land or areas resulting from the performance of the Work.

2. Should any claim be made by any such OWNER or occupant because of the performance of the Work, CONTRACTOR shall promptly settle with such other party by negotiation or otherwise resolve the claim by arbitration or other dispute resolution proceeding or at law.

B. Removal of Debris During performance of the Work:

During the progress of the Work CONTRACTOR shall keep the Site and other areas free from accumulations of waste materials, rubbish, and other debris. Removal and disposal of such waste materials, rubbish, and other debris shall conform to applicable Laws and Regulations.

C. Cleaning:

Prior to Substantial Completion of the Work CONTRACTOR shall clean the Site and make it ready for utilization by OWNER. At the completion of the Work CONTRACTOR shall remove from the Site all tools, appliances, construction equipment and machinery, and surplus materials and shall restore to original condition all property not designated for alteration by the Contract Documents.

D. Loading Structures:

CONTRACTOR shall not load nor permit any part of any structure to be loaded in any manner that will endanger the structure, nor shall CONTRACTOR subject any part of the Work or adjacent property to stresses or pressures that will endanger it.

E. To the fullest extent permitted by Laws and Regulations, CONTRACTOR shall indemnify and hold harmless OWNER, ENGINEER, ENGINEER's Consultant, and the officers, directors, partners, employees, agents, and other consultants of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any claim or action, legal or equitable, brought by any such OWNER or occupant against OWNER, ENGINEER, or any other party indemnified hereunder to the extent caused by or based upon CONTRACTOR's performance of the Work.

6.12 Record Documents

A. CONTRACTOR shall maintain in a safe place at the Site one record copy of all Drawings, Specifications, Addenda, Written Amendments, Change Orders, Field Orders, and written interpretations and clarifications in good order and annotated to show changes made during construction. These record documents together with all approved Samples and a counterpart of all approved Shop Drawings will be available to ENGINEER for reference. Upon completion of the Work, these record documents, Samples, and Shop Drawings will be delivered to ENGINEER for OWNER.

B CONTRACTOR shall mark up one set of paper prints to show the As-built conditions. They shall include all the information shown on the Contract Drawings and a record of all deviations, modifications, or changes from those Drawings, however minor, which were incorporated in the Work, all additional work not appearing on the Contract Drawings and all changes which are made after final inspection of the Contract Work. These As-built marked prints shall be kept current and available on the job site at all times. All changes from the Contract Drawings which are made in the Work or additional information which might be uncovered in the course of construction shall be accurately and neatly recorded as they occur by means of details and notes. No construction work shall be concealed until it has been inspected, approved, and recorded. The As-built marked prints will be jointly inspected for accuracy and completeness by the ENGINEER'S representative and a responsible representative of the CONTRACTOR prior to submission of the monthly pay estimate. Failure to keep the As-built marked prints on a current basis shall be sufficient justification to suspend pay estimates. The drawings shall show the following information, but not be limited to:

1. The location of any utility lines or other installations of any kind or description known to exist within the construction area. The location includes dimensions of permanent features.
2. The location and identification of all surface installations within 100 feet of the construction work.
3. The location and dimensions of any changes within the building or structure.
4. Correct grade or alignment of roads, structures, or utilities if any changes were made from Contract Drawings.
5. Correct elevations if changes were made in site grading.
6. Changes in details or design or additional information obtained from working drawings specified to be prepared or furnished by the CONTRACTOR including but not limited to fabrication, erection, installation plans and placing details, pipe sizes, insulation material, dimensions or equipment foundations, etc.
7. The topography and grades of all drainage installed or affected as a part of the Work.
8. All changes or modifications which result from the final inspection.

The As-built marked prints shall be delivered to the ENGINEER at the time of final inspection for ENGINEER's review and approval. All approval and acceptance of As-built drawings shall be accomplished before final payment is made to the CONTRACTOR.

6.13 Safety and Protection

A. CONTRACTOR shall be solely responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work. CONTRACTOR shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury or loss to:

1. All persons on the Site or who may be affected by the Work;
2. All the Work and materials and equipment to be incorporated therein, whether in storage on or off the Site; and
3. Other property at the Site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities, and Underground Facilities not designated for removal, relocation, or replacement in the course of construction.

B. CONTRACTOR shall comply with all applicable Laws and Regulations relating to the safety of persons or property, or to the protection of persons or property from damage, injury, or loss; and shall erect and maintain all necessary safeguards for such safety and protection. CONTRACTOR shall notify Owner's of adjacent property and of Underground Facilities and other utility Owner's when prosecution of the Work may affect them, and shall cooperate with them in the protection, removal, relocation, and replacement of their property. All damage, injury, or loss to any property referred to in paragraph 6.13.A.2 or 6.13.A.3 caused, directly or indirectly, in whole or in part, by CONTRACTOR, any Subcontractor, Supplier, or any other individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, shall be remedied by CONTRACTOR (except damage or loss attributable to the fault of Drawings or Specifications or to the acts or omissions of OWNER or ENGINEER or ENGINEER'S Consultant, or anyone employed by any of them, or anyone for whose acts any of them may be liable, and not attributable, directly or indirectly, in whole or in part, to the fault or negligence of CONTRACTOR or any Subcontractor, Supplier, or other individual or entity directly or indirectly employed by any of them). CONTRACTOR's duties and responsibilities for safety and for protection of the Work shall continue until such time as all the Work is completed and ENGINEER has issued a notice to OWNER and CONTRACTOR in accordance with paragraph 14.07.B that the Work is acceptable (except as otherwise expressly provided in connection with Substantial Completion).

C. Occupational Safety and Health Standards: CONTRACTOR's methods of construction and safety requirements, including but not limited to trench excavation and shoring where applicable, shall conform to the requirements of the Occupational Safety and Health Standards for the Construction Industry. The document entitled "Occupational Safety and Health Standards for the Construction Industry" (29 CFR PART 1926) with Amendments as of February 1, 1998, including 29 CFR part 1910 General Industry Safety and Health Standards Applicable to Construction, is not attached to the Contract Documents. Said requirements as identified and established above are incorporated herein by reference.

D. Power Lines: No equipment of any kind shall be used or permitted within such proximity to the conductors of the Public Services of New Hampshire power lines as to be in violation of the safe working clearance prescribed by the National Electrical Safety Code.

E. Protection of Utilities: The CONTRACTOR shall verify all utility locations prior to the start of construction. This shall include, but not necessarily limited to: irrigation and drainage ditches, culverts, water lines, sewer lines, telephone cables, cable television, gas lines and electric lines. Prior to the start of construction the CONTRACTOR shall call Dig Safe System, Inc. 1-800-344-7233 (two full working days notice required). The failure of any utility to subscribe to DIGS shall not relieve the CONTRACTOR from the responsibility of protection of that utility on the site. Any physical structure (i.e. curbs, sidewalks, paving, buildings, landscape improvements, utilities, etc., damaged by the CONTRACTOR shall be repaired or replaced in a condition equal to or better than the condition prior to the damage. Such repair or replacement shall be accomplished at the CONTRACTOR's expense without additional compensation from the OWNER.

F. CONTRACTOR shall ensure that its activities and activities of its employees, agents and subcontractors, and their employees and agents (including all sub-subcontractors), are in strict compliance with all Environmental Protection Agency, New Hampshire Department of Environmental Services, and Department of Transportation regulations and all other applicable federal, state and local statutes, ordinances, regulations and rules, including without limitation, the

Federal Occupational Safety and Health Act of 1970 (OSHA) as amended and the standards and regulations issued thereunder, and all other statutes, ordinances, regulations, rules, standards and requirements of common law in relation to industrial hygiene and safety, and the protection of health and the environment.

6.14 Safety Representative

A. CONTRACTOR shall designate a qualified and experienced safety representative at the Site whose duties and responsibilities shall be the prevention of accidents and the maintaining and supervising of safety precautions and programs. Work Site is subject to safety inspection by the City Safety Representative at any and all times.

6.15 Hazard Communication Programs

A. CONTRACTOR shall be responsible for coordinating any exchange of material safety data sheets or other hazard communication information required to be made available to or exchanged between or among employers at the Site in accordance with Laws or Regulations.

6.16 Emergencies

A. In emergencies affecting the safety or protection of persons or the Work or property at the Site or adjacent thereto, CONTRACTOR is obligated to act to prevent threatened damage, injury, or loss. CONTRACTOR shall give ENGINEER prompt written notice if CONTRACTOR believes that any significant changes in the Work or variations from the Contract Documents have been caused thereby or are required as a result thereof. If ENGINEER determines that a change in the Contract Documents is required because of the action taken by CONTRACTOR in response to such an emergency, Change Order will be issued.

6.17 Shop drawings and Samples

A. CONTRACTOR shall submit Shop Drawings to ENGINEER for review and approval in accordance with the acceptable schedule of Shop Drawings and Sample submittals. All submittals will be identified as ENGINEER may require and in the number of copies specified in the General Requirements. The data shown on the Shop Drawings will be complete with respect to quantities, dimensions, specified performance and design criteria, materials, and similar data to show ENGINEER the services, materials, and equipment CONTRACTOR proposes to provide and to enable ENGINEER to review the information for the limited purposes required by paragraph 6.17.E.

B. CONTRACTOR shall also submit Samples to ENGINEER for review and approval in accordance with the acceptable schedule of Shop Drawings and Sample submittals. Each Sample will be identified clearly as to material, Supplier, pertinent data such as catalog numbers, and the use for which intended and otherwise as ENGINEER may require to enable ENGINEER to review the submittal for the limited purposes required by paragraph 6.17.E. The numbers of each Sample to be submitted will be as specified in the Specifications.

C. Where a Shop Drawing or Sample is required by the Contract Documents or the schedule of Shop Drawings and Sample submittals acceptable to ENGINEER as required by paragraph 2.07, any related Work performed prior to ENGINEER's review and approval of the pertinent submittal will be at the sole expense and responsibility of CONTRACTOR.

D. Submittal Procedures

1. Before submitting each Shop Drawing or Sample, CONTRACTOR shall have determined and verified:

- a. All field measurements, quantities, dimensions, specified performance criteria, installation requirements, materials, catalog numbers, and similar information with respect thereto;
- b. All materials with respect to intended use, fabrication, shipping, handling, storage, assembly, and installation pertaining to the performance of the Work;

c. All information relative to means, methods, techniques, sequences, and procedures of construction and safety precautions and programs incident thereto; and

d. CONTRACTOR shall also have reviewed and coordinated each Shop Drawing or Sample with other Shop drawings and Samples and with the requirements of the Work and the Contract Documents.

2. Each submittal shall bear a stamp or specific written indication that CONTRACTOR has satisfied CONTRACTOR's obligations under the Contract Documents with respect to CONTRACTOR's review and approval of that submittal.

3. At the time of each submittal, CONTRACTOR shall give ENGINEER specific written notice of such variations, if any, that the Shop Drawing or Sample submitted may have from the requirements of the Contract Documents, such notice to be in a written communication separate from the submittal; and, in addition, shall cause a specific notation to be made on each Shop Drawing and Sample submitted to ENGINEER for review and approval of each such variation.

E. *ENGINEER's Review*

1. ENGINEER will timely review and approve Shop Drawings and Samples in accordance with the schedule of Shop Drawings and Sample submittals acceptable to ENGINEER. ENGINEER's review and approval will be only to determine if the items covered by the submittals will, after installation or incorporation in the Work, conform to the information given in the Contract Documents and be compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents.

2. ENGINEER's review and approval will not extend to means, methods, techniques, sequences, or procedures of construction (except where a particular means, method, technique, sequence, or procedure of construction is specifically and expressly called for in the Contract Documents) or to safety precautions or programs incident thereto. The review and approval of a separate item as such will not indicate approval of the assembly in which the item functions.

3. ENGINEER's review and approval of Shop Drawings or Samples shall not relieve CONTRACTOR from responsibility for any variation from the requirements of the Contract Documents unless CONTRACTOR has in writing called ENGINEER's attention to each such variation at the time of each submittal as required by paragraph 6.17.D.3 and ENGINEER has given written approval of each such variation by specific written notation thereof incorporated in or accompanying the Shop Drawing or Sample approval; nor will any approval by ENGINEER relieve CONTRACTOR from responsibility for complying with the requirements of paragraph 6.17.D.1.

F. *Resubmittal Procedures*

1. CONTRACTOR shall make corrections required by ENGINEER and shall return the required number of corrected copies of Shop Drawings and submit as required new Samples for review and approval. CONTRACTOR shall direct specific attention in writing to revisions other than the corrections called for by ENGINEER on previous submittals.

6.18 *Continuing the Work*

A. CONTRACTOR shall carry on the Work and adhere to the progress schedule during all disputes or disagreements with OWNER. No Work shall be delayed or postponed pending resolution of any disputes or disagreements, except as permitted by paragraph 15.04 or as OWNER and CONTRACTOR may otherwise agree in writing.

6.19 *CONTRACTOR's General Warranty and Guarantee*

A. CONTRACTOR warrants and guarantees to OWNER, ENGINEER, and ENGINEER's Consultants that all Work will be in accordance with the Contract Documents and will not be defective. CONTRACTOR's warranty and guarantee hereunder excludes defects or damage caused by:

1. Abuse, modification, or improper maintenance or operation by persons other than CONTRACTOR, Subcontractors, Suppliers, or any other individual or entity for whom CONTRACTOR is responsible; or

2. Normal wear and tear under normal usage.

B. CONTRACTOR's obligation to perform and complete the Work in accordance with the Contract Documents shall be absolute. None of the following will constitute an acceptance of Work that is not in accordance with the Contract Documents or a release of CONTRACTOR's obligation to perform the Work in accordance with the Contract Documents:

1. Observations by ENGINEER;

2. Recommendation by ENGINEER or payment by OWNER OF ANY PROGRESS OR FINAL PAYMENT;

3. The issuance of a certificate of Substantial Completion by ENGINEER or any payment related thereof by OWNER;

4. Use or occupancy of the Work or any part thereof by OWNER;

5. Any acceptance by OWNER or any failure to do so;

6. Any review and approval of a Shop Drawing or Sample submittal or the issuance of a notice of acceptability by ENGINEER;

7. Any inspection, test, or approval by others; or

8. Any correction of defective Work by OWNER.

6.20 Indemnification

A. Regardless of the coverage provided by any insurance, Contractor agrees to indemnify and shall defend and hold harmless the City, its agents, officials, employees and authorized representatives and their employees from and against any and all suits, causes of action, legal or administrative proceedings, arbitrations, claims, demands, damages, liabilities, interest, attorneys' fees, costs and expenses of any kind or nature in any manner caused, occasioned, or contributed to in whole or in part by reason of any negligent act, omission, or fault or willful misconduct, whether active or passive, of Contractor or of anyone acting under its direction or control or on its behalf in connection with or incidental to the performance of this contract. Contractor's indemnity, defense and hold harmless obligations, or portions thereof, shall not apply to liability caused by the sole negligence or willful misconduct of the party indemnified or held harmless.

B. In any and all claims against OWNER or ENGINEER, agents, officers, directors, partners, or employees by any employee (or the survivor or personal representative of such employee) of CONTRACTOR, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, the indemnification obligation under paragraph 6.20.A shall not be limited in any way by any limitation on the amount or type of damages, compensation, or benefits payable by or for CONTRACTOR or any such Subcontractor, Supplier, or other individual or entity.

C. The indemnification obligations of CONTRACTOR under paragraph 6.20.A shall not extend to the liability of ENGINEER and ENGINEER's Consultants or to the officers, directors, partners, employees, agents, and other consultants and subcontractors of each and any of them arising out of:

The preparation or approval of, or the failure to prepare or approve, maps, Drawings, opinions, reports, surveys, Change Orders, designs, or Specifications.

ARTICLE 7 - OTHER WORK

7.01 *Related Work at Site*

A. OWNER may perform other work related to the Project at the Site by OWNER's employees, or let other direct contracts therefore, or have other work performed by utility Owner's. If such other work is not noted in the Contract Documents, then:

1. Written notice thereof will be given to CONTRACTOR prior to starting any such other work; and
2. If OWNER and CONTRACTOR are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times that should be allowed as a result of such other work, a Claim may be made therefore as provided in paragraph 10.05.

B. CONTRACTOR shall afford each other contractor who is a party to such a direct contract and each utility OWNER (and OWNER, if OWNER is performing the other work with OWNER's employees) proper and safe access to the Site and a reasonable opportunity for the introduction and storage of materials and equipment and the execution of such other work and shall properly coordinate the Work with theirs. Unless otherwise provided in the Contract Documents, CONTRACTOR shall do all cutting, fitting, and patching of the Work that may be required to properly connect or otherwise make its several parts come together and properly integrate with such other work. CONTRACTOR shall not endanger any work of others by cutting, excavating, or otherwise altering their work and will only cut or alter their work with the written consent of ENGINEER and the others whose work will be affected. The duties and responsibilities of CONTRACTOR under this paragraph are for the benefit of such utility OWNERS and other contractors to the extent that there are comparable provisions for the benefit of CONTRACTOR in said direct contracts between OWNER and such utility OWNERS and other contractors.

C. If the proper execution or results of any part of CONTRACTOR's Work depends upon work performed by others under this Article 7, CONTRACTOR shall inspect such other work and promptly report to ENGINEER in writing any delays, defects, or deficiencies in such other work that render it unavailable or unsuitable for the proper execution and results of CONTRACTOR's Work. CONTRACTOR's failure to so report will constitute an acceptance of such other work as fit and proper for integration with CONTRACTOR's Work except for latent defects and deficiencies in such other work.

7.02 *Coordination*

A. If OWNER intends to contract with others for the performance of other work on the Project at the Site, the following will be set forth in Supplementary Conditions:

1. The individual or entity who will have authority and responsibility for coordination of the activities among the various contractors will be identified;
2. The specific matters to be covered by such authority and responsibility will be itemized; and
3. The extent of such authority and responsibilities will be provided.

B. Unless otherwise provided in the Supplementary Conditions, OWNER shall have sole authority and responsibility for such coordination.

ARTICLE 8 - OWNER'S RESPONSIBILITIES

8.01 *Communications to Contractor*

A. Except as otherwise provided in these General Conditions, OWNER shall issue all communications to CONTRACTOR through ENGINEER.

8.02 Replacement of ENGINEER

A. In case of termination of the employment of ENGINEER, OWNER shall appoint and whose status under the Contract Documents shall be that of the former ENGINEER.

8.03 Furnish Data

A. OWNER shall promptly furnish the data required of OWNER under the Contract Documents.

8.04 Pay Promptly When Due

A. OWNER shall make payments to CONTRACTOR promptly when they are due as provided in paragraphs 14.02.C and 14.07.C.

8.05 Lands and Easements; Reports and Tests

A. OWNER's duties in respect of providing lands and easements and providing engineering surveys to establish reference points are set forth in paragraphs 4.01 and 4.05. Paragraph 4.02 refers to OWNER's identifying and making available to CONTRACTOR copies of reports of explorations and tests of subsurface conditions and drawings of physical conditions in or relating to existing surface or subsurface structures at or contiguous to the Site that have been utilized by ENGINEER in preparing the Contract Documents.

8.06 Insurance

See Article 5.

8.07 Change Orders

A. OWNER is obligated to execute Change Orders as indicated in paragraph 10.03.

8.08 Inspections, Tests, and Approvals

A. OWNER's responsibility in respect to certain inspections tests, and approvals is set forth in paragraph 13.03.B.

8.09 Limitations on OWNER's Responsibilities

A. The OWNER shall not supervise, direct, or have control or authority over, nor be responsible for, CONTRACTOR's means, methods, techniques, sequences, or procedures of construction, of the safety precautions and programs incident thereto, or for any failure of CONTRACTOR to comply with Laws and Regulations applicable to the performance of the Work. OWNER will not be responsible for CONTRACTOR's failure to perform the Work in accordance with the Contract Documents.

8.10 Undisclosed Hazardous Environmental Condition

A. OWNER's responsibility in respect to an undisclosed Hazardous Environmental Condition is set forth in paragraph 4.06

8.11 Evidence of Financial Arrangements

A. If and to the extent OWNER has agreed to furnish CONTRACTOR reasonable evidence that financial arrangements have been made to satisfy OWNER's obligations under the Contract Documents, OWNER's responsibility in respect thereof will be as set forth in the Supplementary Conditions.

ARTICLE 9 - ENGINEER'S STATUS DURING CONSTRUCTION

9.01 OWNER's Representative

A. ENGINEER will be OWNER's representative during the construction period. The duties and responsibilities and the limitations of authority of ENGINEER as OWNER's representative during construction are set forth in the Contract Documents and will not be changed without written consent of OWNER and ENGINEER.

9.02 Visits to Site

A. ENGINEER will make visits to the Site at intervals appropriate to the various stages of construction as ENGINEER deems necessary in order to observe as an experienced and qualified design professional the progress that has been made and the quality of the various aspects of CONTRACTOR's executed Work. Based on information obtained during such visits and observations, ENGINEER, for the benefit of OWNER, will determine, in general, if the Work is proceeding in accordance with the Contract Documents. ENGINEER will not be required to make exhaustive or continuous inspections on the Site to check the quality or quantity of the Work. ENGINEER's efforts will be directed toward providing for OWNER a greater degree of confidence that the completed Work will conform generally to the Contract Documents. On the basis of such visits and observations, ENGINEER will keep OWNER informed of the progress of the Work and will endeavor to guard OWNER against defective Work.

B. ENGINEER's visits and observations are subject to all the limitations on ENGINEER's authority and responsibility set forth in paragraph 9.10, and particularly, but without limitation, during or as a result of ENGINEER's visits or observations of CONTRACTOR's Work ENGINEER will not supervise, direct, control, or have authority over or be responsible for CONTRACTOR's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of CONTRACTOR to comply with Laws and Regulations applicable to the performance of the Work.

9.03 Project Representative

A. If OWNER and ENGINEER agree, ENGINEER will furnish a Resident Project Representative to assist ENGINEER in providing more extensive observation of the Work. The responsibilities and authority and limitations thereon of any such Resident Project Representative and assistants will be as provided in paragraph 9.10 and in the Supplementary Conditions. If OWNER designates another representative or agent to represent OWNER at the Site who is not ENGINEER's Consultant, agent or employee, the responsibilities and authority and limitations thereof of such other individual or entity will be as provided in the supplementary Conditions.

9.04 Clarifications and Interpretations

A. ENGINEER will issue with reasonable promptness such written clarifications or interpretations of the requirements of the Contract Documents as ENGINEER may determine necessary, which shall be consistent with the intent of and reasonably inferable from the Contract Documents. Such written clarifications and interpretations will be binding on OWNER and CONTRACTOR. If OWNER and CONTRACTOR are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, that should be allowed as a result of a written clarification or interpretation, a Claim may be made therefore as provided in paragraph 10.05.

9.05 Authorized Variations in Work

A. ENGINEER may authorize minor variations in the Work from the requirements of the Contract documents which do not involve an adjustment in the Contract Price or the Contract Times and are compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. These may be accomplished by a Field Order and will be binding on OWNER and also on CONTRACTOR, who shall perform the Work involved promptly. If OWNER and CONTRACTOR are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, as a result of a Field Order, a Claim may be made therefore as provided in paragraph 10.05.

9.06 Rejecting Defective Work

A. ENGINEER will have authority to disapprove or reject Work which ENGINEER believes to be defective, or that ENGINEER believes will not produce a completed Project that conforms to the Contract Documents or that will prejudice the integrity of the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. ENGINEER will also have authority to require special inspection or testing of the Work as provided in paragraph 13.04, whether or not the Work is fabricated, installed, or completed.

9.07 Shop Drawings, Change Orders and Payments

A. In connection with ENGINEER's authority as to Shop Drawings and Samples, see paragraph 6.17.

B. In connection with ENGINEER's authority as to change orders, see Articles 10, 11, and 12.

C. In connection with ENGINEER's authority as to Applications for Payment, see Article 14.

9.08 Determinations for Unit Price Work

A. ENGINEER will have authority to determine the actual quantities and classifications of items of Unit Price Work performed by CONTRACTOR, and the written decisions of ENGINEER on such matters will be final, binding on OWNER and CONTRACTOR and not subject to appeal (except as modified by ENGINEER to reflect changed factual conditions).

9.09 Decisions on Requirements of Contract Documents and Acceptability of Work

A. ENGINEER will be the initial interpreter of the requirements of the Contract Documents and judge of the acceptability of the Work there under. Claims, disputes and other matters relating to the acceptability of the Work, the quantities and classifications of Unit Price Work, the interpretation of the requirements of the Contract documents pertaining to the performance of the Work, and Claims seeking changes in the Contract Price or Contract Times will be referred initially to ENGINEER in writing in accordance with the provisions of paragraph 10.05, with a request for a formal decision.

B. When functioning as interpreter and judge under this paragraph 9.09, ENGINEER will not be liable in connection with any interpretation or decision rendered in such capacity. The rendering of a decision by ENGINEER pursuant to this paragraph 9.09 with respect to any such Claim, dispute, or other matter (except any which have been waived by the making or acceptance of final payment as provided in paragraph 14.07) will be a condition precedent to any exercise by OWNER or CONTRACTOR of such rights or remedies as either may otherwise have under the Contract Documents or by Laws or Regulations in respect of any such Claim, dispute, or other matter.

9.10 Limitations on ENGINEER's Authority and Responsibilities

A. Neither ENGINEER's authority or responsibility under this Article 9 or under any other provision of the Contract Documents nor any decision made by ENGINEER in good faith either to exercise or not exercise such authority or responsibility or the undertaking, exercise, or performance of any authority or responsibility by ENGINEER shall create, impose, or give rise to any duty in contract, tort, or otherwise owed by ENGINEER to CONTRACTOR, any Subcontractor, any Supplier, any other individual or entity, or to any surety for or employee or agent of any of them.

B. ENGINEER will not supervise, direct, control, or have authority over or be responsible for CONTRACTOR's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of CONTRACTOR to comply with Laws and Regulations applicable to the performance of the Work. ENGINEER will not be responsible for CONTRACTOR's failure to perform the Work in accordance with the Contract Documents.

C. ENGINEER will not be responsible for the acts or omissions of CONTRACTOR or of any Subcontractor, any Supplier, or of any other individual or entity performing any of the Work.

D. ENGINEER's review of the final Application for Payment and accompanying documentation and all maintenance and operating instructions, schedules, guarantees, Bonds, certificates of inspection, tests and approvals, and other documentation required to be delivered by paragraph 14.07.A will only be to determine generally that their content complies with the requirements of, and in the case of certificates or inspections, tests, and approvals that the results certified indicate compliance with the Contract Documents.

E. The limitations upon authority and responsibility set forth in this paragraph 9.10 shall also apply to ENGINEER's Consultants, Resident Project Representative, and assistants.

ARTICLE 10 - CHANGES IN THE WORK; CLAIMS

10.01 *Authorized Changes in the Work*

A. Without invalidating the Agreement and without notice to any surety, OWNER may, at any time or from time to time, order additions, deletions, or revisions in the Work by a Written Amendment or a Change Order. Upon receipt of any such document, CONTRACTOR shall promptly proceed with the Work involved which will be performed under the applicable conditions of the Contract Documents (except as otherwise specifically provided).

B. If OWNER and CONTRACTOR are unable to agree on entitlement to, or on the amount or extent, if any, of an adjustment in the Contract Price or Contract Times, or both, that should be allowed as a result of a Change Order, a Claim may be made therefore as provided in paragraph 10.05.

10.02 *Unauthorized Changes in the Work*

A. CONTRACTOR shall not be entitled to an increase in the Contract Price or an extension of the Contract Times with respect to any work performed that is not required by the Contract Documents as amended, modified, or supplemented as provided in paragraph 3.04, except in the case of an emergency as provided in paragraph 6.16 or in the case of uncovering Work as provided in paragraph 13.04.B.

10.03 *Execution of Change Orders*

A. OWNER and CONTRACTOR shall execute appropriate Change Orders recommended by ENGINEER (or Written Amendments) covering:

1. Changes in the Work which are: (i) ordered by OWNER pursuant to paragraph 10.01.A, (ii) required because of acceptance of defective Work under paragraph 13.08.A or OWNER's correction of defective Work under paragraph 13.09, or (iii) agreed to by the parties;
2. Changes in the Contract Price or Contract Times which are agreed to by the parties, including any undisputed sum or amount of time for Work actually performed in accordance with a Change Order ; and
3. Changes in the Contract Price and Contract Times which embody the substance of any written decision rendered by ENGINEER pursuant to paragraph 10.05; provided that, in lieu of executing any such Change Order, an appeal may be taken from any such decision in accordance with the provisions of the Contract Documents and applicable Laws and Regulations, but during any such appeal, CONTRACTOR shall carry on the Work and adhere to the progress schedule as provided in paragraph 6.18.A.

10.04 *Notification to Surety*

A. If notice of any change affecting the general scope of the Work or the provisions of the Contract Documents (including, but not limited to, Contract Price or Contract Times) is required by the provisions of any Bond to be given to a surety, the giving of any such notice will be CONTRACTOR's responsibility. The amount of each applicable Bond will be adjusted to reflect the effect of any such change.

10.05 Disputes – Not Insurance Related

A. Notice: Written notice stating the general nature of each Claim, dispute, or other matter shall be delivered by the claimant to ENGINEER and the other party to the Contract promptly (but in no event later than 10 days) after the start of the event giving rise thereto. Notice of the amount or extent of the dispute, or other matter with supporting data shall be delivered to the ENGINEER, Risk Management Department and the other party to the Contract within 60 days after the start of such event. A dispute for an adjustment in Contract Price shall be prepared in accordance with the provisions in paragraph 12.01.B. A dispute for an adjustment in Contract Time shall be prepared in accordance with the provisions of paragraph 12.02.B. Each dispute shall be accompanied by claimant's written statement that the adjustment disputed is the entire adjustment to which the claimant believes it is entitled as a result of said event. The opposing party shall submit any response to ENGINEER and the claimant within 30 days after receipt of the claimant's last submittal (unless ENGINEER allows additional time).

B. ENGINEER'S Decision: ENGINEER will render a formal decision in writing within 30 days after receipt of the last submittal of the claimant or the last submittal of the opposing party, if any. ENGINEER's written decision on such dispute, or other matter will be final and binding upon CONTRACTOR unless:

1. An appeal from ENGINEER'S decision is taken within the time limits and in accordance with the dispute resolution procedures set forth in Article 16; or

2. If no such dispute resolution procedures have been set forth in Article 16, a written notice of intention to appeal from ENGINEER's written decision is delivered by CONTRACTOR to the other and to ENGINEER within 30 days after the date of such decision, and a formal proceeding is instituted by the appealing party in a forum of competent jurisdiction within 60 days after the date of such decision or within 60 days after Substantial Completion, whichever is later (unless otherwise agreed in writing by OWNER and CONTRACTOR), to exercise such rights or remedies as the appealing party may have the respect to such Claim, dispute, or other matter in accordance with applicable Laws and Regulations.

C. If ENGINEER does not render a formal decision in writing within the time stated in paragraph 10.05.B, a decision denying the dispute in its entirety shall be deemed to have been issued 31 days after receipt of the last submittal of the claimant or the submittal of the opposing party, if any.

D. No dispute for an adjustment in Contract Price or Contract Times (or Milestones) will be valid if not submitted in accordance with this paragraph 10.05.

ARTICLE 11 - COST OF THE WORK; CASH ALLOWANCES; UNIT PRICE WORK

11.01 Cost of the Work

A. Costs Included: The term Cost of the Work means the sum of all costs necessarily incurred and paid by CONTRACTOR in the proper performance of the Work. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the basis of the Cost of the Work, the costs to be reimbursed to CONTRACTOR will be only those additional or incremental costs required because of the change in the Work or because of the event giving rise to the Claim. Except as otherwise may be agreed to in writing by OWNER, such costs shall be in amounts no higher than those prevailing in the locality of the Project, shall include only the following items, and shall not include any of the costs itemized in paragraph 11.01.B.

1. Payroll costs for employees in the direct employ of CONTRACTOR in the performance of the Work under schedules of job classifications agreed upon by OWNER and CONTRACTOR. Such employees shall include without limitation superintendents, foremen, and other personnel employed full time at the Site. Payroll costs of employees not employed full time on the Work shall be apportioned on the basis of their time spent on the Work. Payroll costs shall include, but not be limited to, salaries and wages plus the cost of fringe benefits which shall include social security contributions, unemployment, excise, and payroll taxes, workers' compensation, health and retirement benefits, bonuses, sick leave, vacation and holiday pay applicable thereto. The expenses of performing Work outside of regular working hours, on Saturday, Sunday, or legal holidays, shall be included in the above to the extent authorized by OWNER.

2. Cost of all materials and equipment furnished and incorporated in the Work, including costs of transportation and storage thereof, and Suppliers' field services required in connection therewith. All cash discounts shall accrue to CONTRACTOR unless OWNER deposits funds with CONTRACTOR with which to make payments, in which case the cash discounts shall accrue to OWNER. All trade discounts, rebates and refunds and returns from sale of surplus materials and equipment shall accrue to OWNER, and CONTRACTOR shall make provisions so that they may be obtained.
3. Payments made by CONTRACTOR to Subcontractors for Work performed by Subcontractors. If required by OWNER, CONTRACTOR shall obtain competitive bids from subcontractors acceptable to OWNER and CONTRACTOR and shall deliver such bids to OWNER, who will then determine, with the advice of ENGINEER, which bids, if any, will be acceptable. If any subcontract provides that the Subcontractor is to be paid on the basis of Cost of the Work plus a fee, the Subcontractor's Cost of the Work and fee shall be determined in the same manner as CONTRACTOR's Cost of the Work and fee as provided in this paragraph 11.01.
4. Costs of special consultants (including but not limited to engineers, architects, testing laboratories, surveyors, attorneys, and accountants) employed for services specifically related to the Work.
5. Supplemental costs including the following:
 - a. The proportion of necessary transportation, travel, and subsistence expenses of CONTRACTOR's employees incurred in discharge of duties connected with the Work.
 - b. Cost, including transportation and maintenance, of all materials, supplies, equipment, machinery, appliances, office, and temporary facilities at the Site, and hand tools not owned by the workers, which are consumed in the performance of the Work, and cost, less market value, of such items used but not consumed which remain the property of CONTRACTOR.
 - c. Rentals of all construction equipment and machinery, and the parts thereof whether rented from CONTRACTOR or others in accordance with rental agreements approved by OWNER with the advice of ENGINEER, and the costs of transportation, loading, unloading, assembly, dismantling, and removal thereof. All such costs shall be in accordance with the terms of said rental agreements. The rental of any such equipment, machinery, or parts shall cease when the use thereof is no longer necessary for the Work.
6. Rental rates shall be determined as follows:
 - a. The base rates shall be those established in publications and revisions thereto entitled "Rental Rate Blue Book for Construction Equipment" or the "Rental Rate Blue Book for Older Construction Equipment" as published by K-III, 1735 Technology Drive, Suite 401, San Jose, CA 95110-1313, Phone (408) 467-6700.
 - b. Attachments (e.g. tractor with ripper and dozer or tractor with loader and backhoe) will be included in the hourly rental rate only when deemed essential to the work as determined the Engineer. When multiple attachments are approved for use and are being used interchangeably, the attachment having the higher rental rate shall be the only one included for payment.
 - c. No direct payment will be made for necessary accessories (including replenishing blades, augers, teeth, hoses, bits, etc.) if not listed in the Rental Rate Blue Book.
 - d. No compensation will be allowed for shop tools having a daily rental rate of less than \$10 as set forth in Section 18 of the Rental Rate Blue Book.
 - i. If ordered to use equipment not listed in the aforementioned publications, the Engineer will establish a rental rate for such equipment. CONTRACTOR shall furnish cost data that might assist in the establishment of such rental rate.
 - ii. Payment will be made for the actual time that such equipment is in operation on the work.

iii. Authorized standby time for idle equipment shall be paid at 50% of the specified rate, less the estimated operating cost per hour. No markup will be added for overhead and profit.

iv. Rental rate paid as above provided shall include the cost of fuel, oil, lubrication, small tools, necessary attachments, repairs and maintenance of any kind, depreciation, storage, insurance and all incidentals. CONTRACTOR shall provide the Engineer with a complete Force Account Equipment Listing for each piece of equipment utilized.

e. Sales, consumer, use, and other similar taxes related to the Work, and for which CONTRACTOR is liable, imposed by Laws and Regulations.

f. Deposits lost for causes other than negligence of CONTRACTOR, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, and royalty payments and fees for permits and licenses.

g. Losses and damages (and related expenses) caused by damage to the Work, not compensated by insurance or otherwise, sustained by CONTRACTOR in connection with the performance of the Work, provided such losses and damages have resulted from causes other than negligence of CONTRACTOR, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable. Such losses shall include settlements made with the written consent and approval of OWNER. No such losses, damages and expenses shall be included in the Cost of the Work for the purpose of determining CONTRACTOR's fee.

h. The cost of utilities, fuel, and sanitary facilities at the Site.

i. Minor expenses such as telegrams, long distance telephone calls, telephone service at the Site, expressage, and similar petty cash items in connection with the Work.

j. When the Cost of the Work is used to determine the value of a Change Order or of a Claim, the cost of premiums for additional Bonds and insurance required because of the changes in the Work or caused by the event giving rise to the Claim

k. When all the Work is performed on the basis of cost-plus, the costs of premiums for all Bonds and insurance CONTRACTOR is required by the Contract Documents to purchase and maintain.

B. Costs Excluded: The term Cost of the Work shall not include any of the following items:

1. Payroll costs and other compensation of CONTRACTOR's officers, executives, principals (of partnerships and sole proprietorships), general managers, engineers, architects, estimators, attorneys, auditors, accountants, purchasing and contracting agents, expeditors, timekeepers, clerks, and other personnel employed by CONTRACTOR, whether at the Site or in CONTRACTOR's principal or branch office for general administration of the Work and not specifically included in the agreed upon schedule of job classifications referred to in paragraph 11.01.A.1 or specifically covered by paragraph 11.01.A.4, all of which are to be considered administrative costs covered by the CONTRACTOR's fee.

2. Expenses of CONTRACTOR's principal and branch offices other than CONTRACTOR's office at the Site.

3. Any part of CONTRACTOR's capital expense, including interest on CONTRACTOR's capital employed for the Work and charges against CONTRACTOR for delinquent payments.

4. Costs due to the negligence of CONTRACTOR, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, including but not limited to, the correction of defective Work, disposal of materials or equipment wrongly supplied, and making good any damage to property.

5. Other overhead or general expense costs of any kind and the costs of any item not specifically and expressly included in paragraphs 11.01.A and 11.01.B.

C. **CONTRACTOR's Fee:** When all the Work is performed on the basis of cost-plus, CONTRACTOR's fee shall be determined as set forth in the Agreement. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the basis of Cost of the Work, CONTRACTOR's fee shall be determined as set forth in paragraph 12.01.C.

D. **Documentation:** Whenever the cost of the Work for any purpose is to be determined pursuant to paragraphs 11.01.A. and 11.01.B, CONTRACTOR will establish and maintain records thereof in accordance with generally accepted accounting practices and submit in a form acceptable to ENGINEER as itemized cost breakdown together with supporting data.

11.02 Cash Allowances

A. It is understood that CONTRACTOR has included in the Contract Price all allowances so named in the Contract Documents and shall cause the Work so covered to be performed for such sums as may be acceptable to OWNER and ENGINEER. CONTRACTOR agrees that:

1. The allowances include the cost to CONTRACTOR (less any applicable trade discounts) of materials and equipment required by the allowances to be delivered at the Site, and all applicable taxes; and
2. CONTRACTOR's costs for unloading and handling on the Site, labor, installation costs, overhead, profit, and other expenses contemplated for the allowances have been included in the Contract Price and not in the allowances, and no demand for additional payment on account of any of the foregoing will be valid.

B. Prior to final payment, an appropriate Change Order will be issued as recommended by ENGINEER to reflect actual amounts due CONTRACTOR on account of Work covered by allowances, and the Contract Price shall be correspondingly adjusted.

11.03 Unit Price Work

A. Where the Contract Documents provide that all or part of the Work is to be Unit Price Work, initially the Contract Price will be deemed to include for all Unit Price Work an amount equal to the sum of the unit price for each separately identified item of Unit Price Work times the estimated quantity of each item as indicated in the Agreement. The estimated quantities of items of the Unit Price Work are not guaranteed and are solely for the purpose of comparison of Bids and determining an initial Contract Price. Determinations of the actual quantities and classifications of Unit Price Work performed by CONTRACTOR will be made by ENGINEER subjects to the provisions of paragraph 9.08

B. Each unit price will be deemed to include an amount considered by CONTRACTOR to be adequate to cover CONTRACTOR's overhead and profit for each separately identified item.

ARTICLE 12 - CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIMES

12.01 Change of Contract Price

A. The Contract Price may only be changed by a Change Order or by a Written Amendment. Any Claim for an adjustment in the Contract Price shall be based on written notice submitted by the party making the Claim to the ENGINEER and the other party to the Contract in accordance with the provisions of paragraph 10.05.

B. The value of any Work covered by a Change Order or of any Claim for an adjustment in the Contract Price will be determined as follows:

1. Where the Work involved is covered by unit prices contained in the Contract Documents, by application of such unit prices to the quantities of the items involved (subject to the provisions of paragraph 11.03); or

2. Where the Work involved is not covered by unit prices contained in the Contract Documents, by a mutually agreed lump sum (which may include an allowance for overhead and profit not necessarily in accordance with paragraph 12.01.C.2); or

3. Where the Work involved is not covered by unit prices contained in the Contract Documents an agreement to a lump sum is not reached under paragraph 12.01.B.2, on the basis of the cost of the Work (determined as provided in paragraph 11.01) plus a CONTRACTOR's fee for overhead and profit (determined as provided in paragraph 12.01.C).

C. CONTRACTOR's Fee: The CONTRACTOR's fee for overhead and profit shall be determined as follows:

1. A mutually acceptable fixed fee; or

2. If a fixed fee is not agreed upon, then a fee based on the following percentages of the various portions of the Cost of the Work:

a. For costs incurred under paragraphs 11.01.A.1 and 11.01.A.2, the CONTRACTOR's fee shall be 15 percent;

b. For costs incurred under paragraph 11.01.A.3, the CONTRACTOR's fee shall be five percent;

c. Where one or more tiers of subcontracts are on the basis of Cost of the Work plus a fee and no fixed fee is agreed upon, the intent of paragraph 12.01.C.2.a. is that the Subcontractor who actually performs the Work, at whatever tier, will be paid a fee of 15 percent of the costs incurred by such Subcontractor under paragraphs 11.01.A.1 and 11.01.A.2 and that any higher tier Subcontractor and CONTRACTOR will each be paid a fee of five percent of the amount paid to the next lower tier Subcontractor;

d. No fee shall be payable on the basis of costs itemized under paragraphs 11.01.A.4, 11.01.A.5, and 11.01.B;

e. The amount of credit to be allowed by CONTRACTOR to OWNER for any change which results in a net decrease in cost will be the amount of the actual net decrease in cost plus a deduction in CONTRACTOR's fee by an amount equal to five percent of such net decrease; and

f. When both addition and credits are involved in any one change, the adjustment in CONTRACTOR's fee shall be computed on the basis of the net change in accordance with paragraphs 12.01.C.2.a through 12.01.C.2.e inclusive.

12.02 Change of Contract Times

A. The Contract Times (or Milestones) may only be changed by a Change Order or by a Written Amendment. Any Claim for an adjustment in the Contract Times (or Milestones) shall be based on written notice submitted by the party making the claim to the ENGINEER and the other party to the Contract in accordance with the provisions of paragraph 10.05.

B. Any adjustment of the contract Times (or Milestones) covered by a Change Order or of any Claim for an adjustment in the Contract Times (or Milestones) will be determined in accordance with the provisions of this Article 12.

12.03 Delays beyond CONTRACTOR's Control

A. Where CONTRACTOR is prevented from completing any part of the Work within the Contract Times (or Milestones) due to delay beyond the control of CONTRACTOR, the Contract Times (or Milestones) will be extended in an amount equal to the time lost due to such delay if a Claim is made therefore as provided in paragraph 12.02.A. Delays beyond the control of CONTRACTOR shall include, but not be limited to, acts or neglect by OWNER, acts or neglect of utility owners or other contractors performing other work as contemplated by Article 7, fires, floods, epidemics, abnormal weather conditions, or acts of God.

12.04 Delays within CONTRACTOR's Control

A. The Contract Times (or Milestones) will not be extended due to delays within the control of CONTRACTOR. Delays attributable to and within the control of a Subcontractor or Supplier shall be deemed to be delays within the control of CONTRACTOR.

12.05 Delays beyond OWNER's and CONTRACTOR's Control

A. Where CONTRACTOR is prevented from completing any part of the Work within the Contract Times (or Milestones) due to delay beyond the control of both OWNER and CONTRACTOR, an extension of the Contract Times (or Milestones) in an amount equal to the time lost due to such delay shall be CONTRACTOR's sole and exclusive remedy for such delay.

12.06 Delay Damages

A. In no event shall OWNER or ENGINEER be liable to CONTRACTOR, any Subcontractor, any Supplier, or any other person or organization, or to any surety for or employee or agent of any of them, for damages arising out of or resulting from:

1. Delays caused by or within the control of CONTRACTOR; or
2. Delays beyond the control of both OWNER and CONTRACTOR including but not limited to fires, flood, epidemics, abnormal weather conditions, acts of God, or acts or neglect by utility owners or other contractors performing other work as contemplated by Article 7.

B. Nothing in this paragraph 12.06 bars a change in Contract Price pursuant to this Article 12 to compensate CONTRACTOR due to delay, interference, or disruption directly attributable to actions or inactions of OWNER or anyone from whom OWNER is responsible.

ARTICLE 13 - TESTS AND INSPECTIONS; CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK

13.01 Notice of Defects

A. Prompt notice of all defective Work of which OWNER or ENGINEER has actual knowledge will be given to CONTRACTOR. All defective Work may be rejected, corrected, or accepted as provided in this Article 13.

13.02 Access to Work

A. OWNER, ENGINEER, ENGINEER'S Consultants, other representatives and personnel of OWNER, independent testing laboratories, and governmental agencies with jurisdictional interest will have access to the Site and the Work at reasonable times for their observation, inspecting, and testing. CONTRACTOR shall provide them proper and safe conditions for such access and advise them of CONTRACTOR's Site safety procedures and programs so that they may comply therewith as applicable.

13.03 Tests and Inspections

A. CONTRACTOR shall give ENGINEER timely notice of readiness of the Work for all required inspections, tests, or approvals and shall cooperate with inspection and testing personnel to facilitate required inspections or tests.

B. OWNER shall employ and pay for the services of an independent testing laboratory to perform all inspections, tests, or approvals required by the Contract Documents except:

1. For inspections, tests, or approvals covered by paragraphs 13.03.C and 13.03.D below;
2. That costs incurred in connection with tests or inspections conducted pursuant to paragraph 13.04.B shall be paid as provided in said paragraph 13.04.B; and

3. As otherwise specifically provided in the Contract Documents.

4. That costs incurred by OWNER due to retesting, reinspection, or standby time due to unacceptable materials, or workmanship provided by the CONTRACTOR, or due to poor scheduling by the CONTRACTOR of tests or inspections, will be deducted from the payments to the CONTRACTOR. CONTRACTOR shall stop work as necessary to allow for inspections and tests by OWNER and ENGINEER.

C. If Laws or Regulations of any public body having jurisdiction require any Work (or part thereof) specifically to be inspected, tested, or approved by an employee or other representative of such public body, CONTRACTOR shall assume full responsibility for arranging and obtaining such inspections, tests, or approvals, pay all costs in connection therewith, and furnish ENGINEER the required certificates of inspection or approval.

D. CONTRACTOR shall be responsible for arranging and obtaining and shall pay all costs in connection with any inspections, tests, or approvals required for OWNER'S and ENGINEER's acceptance of materials or equipment to be incorporated in the Work; or acceptance of materials, mix designs, or equipment submitted for approval prior to CONTRACTOR's purchase thereof for incorporation in the Work. Such inspections, tests, or approvals shall be performed by organizations acceptable to OWNER and ENGINEER.

E. If any Work (or the work of others) that is to be inspected, tested, or approved is covered by CONTRACTOR without written concurrence of ENGINEER, it must, if requested by ENGINEER, be uncovered for observation.

F. Uncovering Work as provided in paragraph 13.03.E shall be at CONTRACTOR's expense unless CONTRACTOR has given ENGINEER timely notice of CONTRACTOR's intention to cover the same and ENGINEER has not acted with reasonable promptness in response to such notice.

G. The OWNER intends to provide inspection for the project. The inspector will be available during a forty (40) hour period during the week from Monday through Friday. In the event the CONTRACTOR receives permission from the OWNER and elects to work more than forty hours during the week or more than 10 hours in one day, or on a Saturday, Sunday, or legal holiday, the CONTRACTOR shall be responsible for all inspection, engineering and testing costs incurred during that period. For all inspection and testing work performed on Saturday, Sunday, or legal holidays the minimum chargeable time shall be four (4) hours. The OWNER reserves the right to deduct these inspection, engineering, and testing costs directly from the CONTRACTOR'S payments.

13.04 Uncovering Work

A. If any Work is covered contrary to the written request of ENGINEER, it must, if requested by ENGINEER, be uncovered for ENGINEER's observation and replaced at CONTRACTOR'S expense.

B. If ENGINEER considers it necessary or advisable that covered Work be observed by ENGINEER or inspected or tested by others, CONTRACTOR, at ENGINEER's request, shall uncover, expose, or otherwise make available for observation, inspection, or testing as ENGINEER may require, that portion of the Work in question, furnishing all necessary labor, material, and equipment. If it is found that such Work is defective, CONTRACTOR shall pay all Claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such uncovering, exposure, observation, inspection, and testing, and of satisfactory replacement or reconstruction (including but not limited to all costs of repair or replacement of work of others); and OWNER shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount thereof, OWNER may make a Claim therefore as provided in paragraph 10.05. If, however, such Work is not found to be defective, CONTRACTOR shall be allowed an increase in the Contract Price or an extension of the Contract Times (or Milestones), or both, directly attributable to such uncovering, exposure, observation, inspection, testing, replacement, and reconstruction. If the parties are unable to agree as to the amount or extent thereof, CONTRACTOR may make a Claim therefore as provided in paragraph 10.05.

13.05 OWNER May Stop the Work

A. If the Work is defective, or CONTRACTOR fails to supply sufficient skilled workers or suitable materials or equipment, or fails to perform the Work in such a way that the completed Work will conform to the Contract Documents, OWNER may order CONTRACTOR to stop the Work, or any portion thereof, until the cause of such order has been eliminated; however, this right of OWNER to stop the Work shall not give rise to any duty on the part of OWNER to exercise this right for the benefit of CONTRACTOR, any Subcontractor, any Supplier, any other individual or entity, or any surety for, or employee or agent of any of them.

13.06 Correction or Removal of Defective Work

A. CONTRACTOR shall correct all defective Work, whether or not fabricated, installed, or completed, or, if the Work has been rejected by ENGINEER, remove it from the Project and replace it with Work that is not defective. CONTRACTOR shall pay all Claims, costs, losses, damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or removal (including but not limited to all costs of repair or replacement of work of others).

13.07 Correction Period

A. If within one year after the date of Substantial Completion or such longer period of time as may be prescribed by Laws or Regulations or by the terms of any applicable special guarantee required by the Contract documents or by any specific provision of the Contract Documents, any Work is found to be defective, or if the repair of any damages to the land or areas made available for CONTRACTOR's use by OWNER or permitted by Laws and Regulations as contemplated in paragraph 6.11.A is found to be defective, CONTRACTOR shall promptly, without cost to OWNER and in accordance with OWNER's written instructions: (i) repair such defective land or areas, or (ii) correct such defective Work or, if the defective Work has been rejected by OWNER, remove it from the Project and replace it with Work that is not defective, and (iii) satisfactorily correct or repair or remove and replace any damage to other Work, to the work of others or other land or areas resulting there from. If CONTRACTOR does not promptly comply with the terms of such instructions, or in an emergency where delay would cause serious risk of loss or damage, OWNER may have the defective Work corrected or repaired or may have the rejected Work removed and replaced, and all Claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or repair or such removal and replacement (including but not limited to all costs of repair or replacement work of others) will be paid by CONTRACTOR.

B. In special circumstances where a particular item of equipment is placed in continuous service before Substantial Completion of all the Work, the correction period for that item may start to run from an earlier date if so provided in the Specifications or by Written Amendment.

C. Where defective Work (and damage to other Work resulting there from) has been corrected or removed and replaced under this paragraph 13.07, the correction period hereunder with respect to such Work will be extended for an additional period of one year after such correction or removal and replacement has been satisfactorily completed.

D. CONTRACTOR's obligations under this paragraph 13.07 are in addition to any other obligation or warranty. The provisions of this paragraph 13.07 shall not be construed as a substitute for or a waiver of the provisions of any applicable statute of limitation or repose.

13.08 Acceptance of Defective Work

A. If, instead of requiring correction or removal and replacement of defective Work, OWNER (and, prior to ENGINEER's recommendation of final payment, ENGINEER) prefers to accept it, OWNER may do so, CONTRACTOR shall pay all Claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) attributable to OWNER's evaluation of and determination to accept such defective Work (such costs to be approved by ENGINEER as to reasonableness) and the diminished value of the Work to the extent not otherwise paid by CONTRACTOR

pursuant to this sentence. If any such acceptance occurs prior to ENGINEER's recommendation of final payment, a Change Order will be issued incorporating the necessary revisions in the Contract Price, reflecting the diminished value of Work so accepted. If the parties are unable to agree as to the amount thereof, OWNER may make a Claim therefore as provided in paragraph 10.05. If the acceptance occurs after such recommendation, an appropriate amount will be paid by CONTRACTOR to OWNER.

13.09 OWNER May Correct Defective Work

A. If CONTRACTOR fails within a reasonable time after written notice from ENGINEER to correct defective Work or to remove and replace rejected Work as required by ENGINEER in accordance with paragraph 13.06.A, or if CONTRACTOR fails to perform the Work in accordance with the Contract Documents, or if CONTRACTOR fails to comply with any other provision of the Contract Documents, OWNER may, after seven days written notice to CONTRACTOR, correct and remedy any such deficiency.

B. In exercising the rights and remedies under this paragraph, OWNER shall proceed expeditiously. In connection with such corrective and remedial action, OWNER may exclude CONTRACTOR from all or part of the Site, take possession of all or part of the Work and suspend CONTRACTOR's services related thereto, take possession of CONTRACTOR's tools, appliances, construction equipment and machinery at the Site, and incorporate in the Work all materials and equipment stored at the Site or for which OWNER has paid CONTRACTOR but which are stored elsewhere. CONTRACTOR shall allow OWNER, OWNER's representatives, agents and employees, OWNER's other contractors, and ENGINEER and ENGINEER's Consultants access to the Site to enable OWNER to exercise the rights and remedies under this paragraph.

C. All Claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred or sustained by OWNER in exercising the rights and remedies under this paragraph 13.09 will be charged against CONTRACTOR, and a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the Work; and OWNER shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount of the adjustment, OWNER may make a Claim therefore as provided in paragraph 10.05. Such claims, costs, losses and damages will include but not be limited to all costs of repair, or replacement of work of others destroyed or damaged by correction, removal, or replacement of CONTRACTOR's defective Work.

D. CONTRACTOR shall not be allowed an extension of the Contract Times (or Milestones) because of any delay in the performance of the Work attributable to the exercise by OWNER of OWNER's rights and remedies under this paragraph 13.09.

ARTICLE 14 - PAYMENTS TO CONTRACTOR AND COMPLETION

14.01 Schedule of Values

A. The schedule of values established as provided in paragraph 2.01.A will serve as the basis for progress payments and will be incorporated into a form of Application for Payment acceptable to ENGINEER. Progress payments on account of Unit Price Work will be based on the number of units completed.

14.02 Progress Payment

A. Applications for Payments

1. At least 20 days before the date established for each progress payment (but not more often than once a month), CONTRACTOR shall submit to OWNER an Application for Payment filled out and signed by CONTRACTOR covering the Work completed as of the date of the Application and accompanied by such supporting documentation as is required by the Contract Documents. If payment is requested on the basis of materials and equipment not incorporated in the Work but delivered and suitably stored at the Site or at another location agreed to in writing, the Application for Payment shall also be accompanied by a bill of sale, invoice, or other documentation warranting that OWNER has received the materials and equipment free and clear of all Liens and evidence that the materials and equipment are covered by appropriate property insurance or other

arrangements to protect OWNER's interest therein, all of which must be satisfactory to OWNER. Any request for partial or final payment shall specifically list the work completed. **To facilitate the proper and timely payment of applications, the OWNER requires that all applications must reference a valid PURCHASE ORDER NUMBER, as submitted to CONTRACTOR under the Notice to Proceed, be in original format; OWNER will not authorize payments from carbon or Xerox copies, and mailed directly to the following address:**

**City of Nashua
Accounts Payable
PO Box 2019
Nashua, NH 03061-2019
Attn: Tim Watson**

2. Beginning with the second Application for Payment, each Application shall include an affidavit of CONTRACTOR stating that all previous progress payments received on account of the Work have been applied on account to discharge CONTRACTOR's legitimate obligations associated with prior Applications for Payment.

3. The amount of retainage with respect to progress payments will be stipulated in the Agreement.

B. Review of Applications.

1. ENGINEER will, within 10 days after receipt of each Application for Payment, either indicate in writing a recommendation of payment and present the Application to OWNER or return the Application to CONTRACTOR indicating in writing ENGINEER's reasons for refusing to recommend payment. In the latter case, CONTRACTOR may make the necessary corrections and resubmit the Application.

2. ENGINEER's recommendation of any payment requested in an Application for Payment will constitute a representation by ENGINEER to OWNER, based on ENGINEER's observations on the Site of the executed Work as an experienced and qualified design professional and on ENGINEER's review of the Application for Payment and the accompanying date and schedules, that to the best of ENGINEER's knowledge, information and belief:

a. The Work has progressed to the point indicated;

b. The quality of the Work is generally in accordance with the Contract Documents (subject to an evaluation of the Work as a functioning whole prior to or upon Substantial Completion, to the results of any subsequent tests called for in the Contract documents, to a final determination of quantities and classifications for Unit Price Work under paragraph 9.08 and to any other qualifications stated in the recommendation); and

c. The conditions precedent to CONTRACTOR's being entitled to such payment appears to have been fulfilled in so far as it is ENGINEER's responsibility to observe the Work.

3. By recommending any such payment ENGINEER will not thereby be deemed to have represented that: (i) inspections made to check the quality or the quantity of the Work as it has been performed have been exhaustive, extended to every aspect of the Work in progress, or involved detailed inspections of the Work beyond the responsibilities specifically assigned to ENGINEER in the Contract Documents; or (ii) that there may not be other matters or issues between the parties that might entitle CONTRACTOR to be paid additionally by OWNER or entitle OWNER to withhold payment to CONTRACTOR.

4. Neither ENGINEER's review of CONTRACTOR's Work for the purposes of recommending payments nor ENGINEER's recommendation of any payment, including final payment, will impose responsibility on ENGINEER to supervise, direct, or control the Work or for the means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for CONTRACTOR's failure to comply with Laws and Regulations applicable to CONTRACTOR's performance of the Work. Additionally, said review or recommendation will not impose responsibility on ENGINEER to make any examination to ascertain how or for what purposes CONTRACTOR has used the moneys paid on account of the Contract Price, or to determine that title to any of the Work, materials, or equipment has passed to OWNER free and clear of any Liens.

5. ENGINEER may refuse to recommend the whole or any part of any payment if, in ENGINEER's opinion, it would be incorrect to make the representations to OWNER referred to in paragraph 14.02.B.2. ENGINEER may also refuse to recommend any such payment or, because of subsequently discovered evidence or the results of subsequent inspections or tests, revise or revoke any such payment recommendation previously made, to such extent as may be necessary in ENGINEER's opinion to protect OWNER from loss because:

- a. The Work is defective, or completed Work has been damaged, requiring correction or replacement;
- b. The Contract Price has been reduced by Written Amendment or Change Orders;
- c. OWNER has been required to correct defective Work or complete Work in accordance with paragraph 13.09; or
- d. ENGINEER has actual knowledge of the occurrence of any of the events enumerated in paragraph 15.02.A.

C. Payment Becomes Due

1. Not more than 30 days after presentation of the application for payment to OWNER with ENGINEER's recommendation, the amount recommended will become due, and when due will be paid by OWNER to CONTRACTOR.

D. Reduction in Payment.

1. OWNER may refuse to make payment of the full amount recommended by ENGINEER because:

- a. Claims have been made against OWNER on account of CONTRACTOR's performance or furnishing of the Work;
- b. Liens have been filed in connection with the Work, except where CONTRACTOR has delivered a specific Bond satisfactory to OWNER to secure the satisfaction and discharge of such Liens;
- c. There are other items entitling OWNER to a set-off against the amount recommended; or
- d. OWNER has actual knowledge of the occurrence of any of the events enumerated in paragraphs 14.02.B.5.a through 14.02.B.5.c or paragraph 15.02.A.

2. If OWNER refuses to make payment of the full amount recommended by ENGINEER, OWNER must give CONTRACTOR immediate written notice (with a copy to ENGINEER) stating the reasons for such action and promptly pay CONTRACTOR any amount remaining after deduction of the amount so withheld. OWNER shall promptly pay CONTRACTOR the amount so withheld, or any adjustment thereto agreed to by OWNER and CONTRACTOR, when CONTRACTOR corrects to OWNER's satisfaction the reasons for such action.

3. If it is subsequently determined that OWNER's refusal of payment was not justified, the amount wrongfully withheld shall be treated as an amount due as determined by paragraph 14.02.C.1.

14.03 CONTRACTOR'S Warranty of Title

A. CONTRACTOR warrants and guarantees that title to all Work, materials, and equipment covered by any Application for Payment, whether incorporated in the Project or not, will pass to OWNER no later than the time of payment free and clear of all Liens.

14.04 Substantial Completion

A. When CONTRACTOR considers the entire Work ready for its intended use CONTRACTOR shall notify OWNER and ENGINEER in writing that the entire Work is substantially complete (except for items specifically listed by

CONTRACTOR as incomplete) and request that ENGINEER issue a certificate of Substantial Completion. Promptly thereafter, OWNER, CONTRACTOR, and ENGINEER shall make an inspection of the Work to determine the status of completion. If ENGINEER does not consider the Work substantially complete, ENGINEER will notify CONTRACTOR in writing giving the reasons therefore. If ENGINEER considers the Work substantially complete, ENGINEER will prepare and deliver to OWNER a tentative certificate of Substantial Completion which shall fix the date of Substantial Completion. There shall be attached to the certificate a tentative list of items to be completed or corrected before final payment. OWNER shall have seven days after receipt of the tentative certificate during which to make written objection to ENGINEER as to any provisions of the certificate or attached list. If, after considering such objections, ENGINEER concludes that the Work is not substantially complete, ENGINEER will within 14 days after submission of the tentative certificate to OWNER notify CONTRACTOR in writing, stating the reasons therefore. If after consideration of OWNER's objections, ENGINEER considers the Work substantially complete, ENGINEER will within said 14 days execute and deliver to OWNER and CONTRACTOR a definitive certificate of Substantial Completion (with a revised tentative list of items to be completed or corrected) reflecting such changes from the tentative certificate as ENGINEER believes justified after consideration of any objections from OWNER. At the time of delivery of the tentative certificate of Substantial Completion ENGINEER will deliver to OWNER and CONTRACTOR a written recommendation to division of responsibilities pending final payment between OWNER and CONTRACTOR with respect to security, operation, safety, and protection of the Work, maintenance, heat, utilities, insurance, and warranties and guarantees. Unless OWNER and CONTRACTOR agree otherwise in writing and so inform ENGINEER in writing prior to ENGINEER's issuing the definitive certificate of Substantial Completion, ENGINEER's aforesaid recommendation will be binding on OWNER and CONTRACTOR until final payment.

B. OWNER shall have the right to exclude CONTRACTOR from the Site after the date of Substantial Completion, but OWNER shall allow CONTRACTOR reasonable access to complete or correct items on the tentative list.

14.05 Partial Utilization

A. Use by OWNER at OWNER's option of any substantially completed part of the Work which has specifically been identified in the Contract Documents, or which OWNER, ENGINEER and CONTRACTOR agree constitutes a separately functioning and usable part of the Work that can be used by OWNER for its intended purpose without significant interference with CONTRACTOR's performance of the remainder of the Work, may be accomplished prior to Substantial Completion of all the Work subject to the following conditions.

1. OWNER at any time may request CONTRACTOR in writing to permit OWNER to use any such part of the Work which OWNER believes to be ready for its intended use and substantially complete. If CONTRACTOR agrees that such part of the Work is substantially complete, CONTRACTOR will certify to OWNER and ENGINEER that such part of the Work is substantially complete and request ENGINEER to issue a certificate of Substantial Completion for that part of the Work. Within a reasonable time after either such request, OWNER, CONTRACTOR, and ENGINEER shall make an inspection of that part of the Work to determine its status of completion. If ENGINEER does not consider that part of the Work to be substantially complete, the provisions of paragraph 14.04 will apply with respect to certification of Substantial Completion of that part of the Work and the division of responsibility in respect thereof and access thereto.
2. No occupancy or separate operation of part of the Work may occur prior to compliance with the requirements of paragraph 5.10 regarding property insurance.

14.06 Final Inspection

A. Upon written notice from CONTRACTOR that the entire Work or an agreed portion thereof is complete, ENGINEER will promptly make a final inspection with OWNER and CONTRACTOR and will notify CONTRACTOR in writing of all particulars in which this inspection reveals that the Work is incomplete or defective. CONTRACTOR shall immediately take such measures as are necessary to complete such Work or remedy such deficiencies.

14.07 Final Payment

A. Application for Payment

1. After CONTRACTOR has, in the opinion of ENGINEER, satisfactorily completed all corrections identified during the final inspection and has delivered, in accordance with the Contract Documents, all maintenance and operating instructions, schedules, guarantees, Bonds, certificates or other evidence of insurance certificates of inspection, marked-up record documents (as provided in paragraph 6.12), and other documents, CONTRACTOR may make application for final payment following the procedure for progress payments.

2. The final Application for Payment shall be accompanied (except as previously delivered) by: (i) all documentation called for in the Contract Documents, including but not limited to the evidence of insurance required by subparagraph 5.04.B.7; (ii) consent of the surety, if any, to final payment; and (iii) complete and legally effective releases or waivers (satisfactory to OWNER) of all Lien rights arising out of or Liens filed in connection with the Work.

3. In lieu of the releases or waivers of Liens specified in paragraph 14.07.A.2 and as approved by OWNER, CONTRACTOR may furnish receipts or releases in full and an affidavit of CONTRACTOR that: (i) the releases and receipts include all labor, services, material, and equipment for which a Lien could be filed; and (ii) all payrolls, material and equipment bills, and other indebtedness connected with the Work for which OWNER or OWNER's property might in any way be responsible have been paid or otherwise satisfied. If any Subcontractor or Supplier fails to furnish such a release or receipt in full, CONTRACTOR may furnish a Bond or other collateral satisfactory to OWNER to indemnify OWNER against any lien.

B. Review of Application and Acceptance

1. If, on the basis of ENGINEER's observation of the Work during construction and final inspection, and ENGINEER's review of the final Application of Payment and accompanying documentation as required by the Contract Documents, ENGINEER is satisfied that the Work has been completed and CONTRACTOR's other obligations under the Contract Documents have been fulfilled, ENGINEER will, within ten days after receipt of the final Application for Payment, indicate in writing ENGINEER's recommendation of payment and present the Application for Payment to OWNER for payment. At the same time ENGINEER will also give written notice to OWNER and CONTRACTOR that the Work is acceptable subject to the provisions of paragraph 14.09. Otherwise, ENGINEER will return the Application for Payment to CONTRACTOR, indicating in writing the reasons for refusing to recommend final payment, in which case CONTRACTOR shall make the necessary corrections and resubmit the Application for Payment.

C. Payment Becomes Due

1. Thirty days after the presentation to OWNER of the Application for Payment and accompanying documentation, the amount recommended by ENGINEER will become due and, when due, will be paid by OWNER to CONTRACTOR.

14.08 Final Completion Delayed

A. If, through no fault of CONTRACTOR, final completion of the Work is significantly delayed, and if ENGINEER so confirms, OWNER shall, upon receipt of CONTRACTOR's final Application for Payment and recommendation of ENGINEER, and without terminating the Agreement, make payment of the balance due for that portion of the Work fully completed and accepted. If the remaining balance to be held by OWNER for Work not fully completed or corrected is less than the retainage stipulated in the Agreement, and if Bonds have been furnished as required in paragraph 5.01, the written consent of the surety to the payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by CONTRACTOR to ENGINEER with the Application for such payment. Such payment

shall be made under the terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

14.09 Waiver of Claims

A. The making and acceptance of final payment will constitute:

1. A waiver of all Claims by CONTRACTOR against OWNER other than those previously made in writing which are still unsettled.

ARTICLE 15 - SUSPENSION OF WORK AND TERMINATION

15.01 OWNER May Suspend Work

A. At any time and without cause, OWNER may suspend the Work or any portion thereof for a period of not more than 90 consecutive days by notice in writing to CONTRACTOR and ENGINEER which will fix the date on which Work will be resumed. CONTRACTOR shall resume the Work on the date so fixed. CONTRACTOR shall be allowed an adjustment in the Contract Price or an extension of the Contract Times, or both, directly attributable to any such suspension if CONTRACTOR makes a Claim therefore as provided in paragraph 10.05.

B. If the performance of all or any part of the work is suspended, delayed or interrupted for an unreasonable period of time by an act of the OWNER in administration of the Contract, or by the OWNER's failure to act within the time specified in the Contract (or if no time is specified, within a reasonable time), the OWNER will make an adjustment for any increase in the cost of performance of this Contract (excluding profit) necessarily caused by such unreasonable suspension, delay or interruption and modify the Contract in writing. However, no adjustment shall be made under this clause for any suspension, delay or interruption to the extent (1) that performance would have been so suspended, delayed, or interrupted by any other cause, including the fault or negligence of the CONTRACTOR, or (2) for which an equitable adjustment is provided for or excluded under any other provision of the Contract.

C. No claim under paragraphs 15.01.A or 15.01.B shall be allowed unless the amount claimed is asserted in writing as soon as practicable after the termination of such suspension, delay or interruption, but no later than the date of application for final payment under the contract.

15.02 OWNER May Terminate for Cause

A. The occurrence of any one or more of the following events will justify termination for cause:

1. CONTRACTOR's persistent failure to perform the Work in accordance with the Contract Documents (including, but not limited to, failure to supply sufficient skilled workers or suitable materials or equipment or failure to adhere to the progress schedule established under paragraph 2.07 as adjusted from time to time pursuant to paragraph 6.04);
2. CONTRACTOR's disregard of Laws or Regulations of any public body having jurisdiction;
3. CONTRACTOR's disregard of the authority of ENGINEER; or
4. CONTRACTOR's violation in any substantial way of any provisions of the Contract Documents.

B. If one or more of the events identified in paragraph 15.02.A occur, OWNER may, after giving CONTRACTOR (and the surety, if any) seven days written notice, terminate the services of CONTRACTOR, exclude CONTRACTOR from the Site, and take possession of the Work and of all CONTRACTOR's tools, appliances, construction equipment, and machinery at the Site, and use the same to the full extent that could be used by CONTRACTOR (without liability to CONTRACTOR for trespass or conversion), incorporate in the Work all materials and equipment stored at the Site or

for which OWNER had paid CONTRACTOR but which are stored elsewhere, and finish the Work as OWNER may deem expedient. In such case, CONTRACTOR shall not be entitled to receive any further payment until the Work is finished. If the unpaid balance of the Contract Price exceeds all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by OWNER arising out of or relating to completing the work, such excess will be paid to CONTRACTOR. If such claims, costs, losses, and damages exceed such unpaid balance, CONTRACTOR shall pay the difference to OWNER. Such claims, costs, losses, and damages incurred by OWNER will be reviewed by ENGINEER, incorporated in a Change Order. When exercising any rights or remedies under this paragraph OWNER shall not be required to obtain the lowest price for the Work performed.

C. Where CONTRACTOR's service have been so terminated by OWNER, the termination will not affect any rights or remedies of OWNER against CONTRACTOR then existing or which may thereafter accrue. Any retention or payment of moneys due CONTRACTOR by OWNER will not release CONTRACTOR from liability.

15.03 OWNER May Terminate For Convenience

A. Upon seven days written notice to CONTRACTOR and ENGINEER, OWNER may, without cause and without prejudice to any other right or remedy of OWNER, elect to terminate the Contract. In such cases, CONTRACTOR shall be paid (without duplication of any items):

1. For completed and acceptable Work executed in accordance with the Contract Documents prior to the effective date of termination, including fair and reasonable sums for overhead and profit on such Work;
2. For expenses sustained prior to the effective date of termination in performing services and furnishing labor, materials, or equipment as required by Contract Documents in connection with uncompleted Work, plus fair and reasonable sums of overhead and profit on such expenses;
3. For all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred in settlement of terminated contracts with Subcontractors, Suppliers, and others; and
4. For reasonable expenses directly attributable to termination.

B. CONTRACTOR shall not be paid on account of loss of anticipated profits or revenue or other economic loss arising out of or resulting from such termination.

C. This Contract may be terminated in whole or in part in writing by the OWNER for its convenience, provided that the CONTRACTOR is given written notice (delivered by certified mail, return receipt requested) of intent to terminate, and an opportunity for consultation with the terminating party prior to termination.

D. If termination for default is effected by the OWNER, and equitable adjustment in the price provided for in this Contract shall be made, but (1) no amount shall be allowed for anticipated profit on unperformed services or other work, and (2) any payment due to the CONTRACTOR at the time of termination may be adjusted to cover any additional costs to the OWNER because of the CONTRACTOR's default. If termination for default is effected by the CONTRACTOR, or if termination for convenience is effected by the OWNER, the equitable adjustment shall include a reasonable profit for services or other work performed. The equitable adjustment for any termination shall provide for payment to the CONTRACTOR for services rendered and expenses incurred prior to the termination, in addition to termination settlement costs reasonably incurred by the CONTRACTOR relating to commitments which had become firm prior to the termination.

E. Upon receipt of a termination action under paragraphs 15.03.C or 15.03.D above, the CONTRACTOR shall (1) promptly discontinue all affected work (unless the notice directs otherwise), and (2) deliver or otherwise make available to the OWNER all data, Drawings, Specifications, reports, estimates, summaries and such other information and materials as may have been accumulated by the CONTRACTOR in performing this Contract, whether completed or in process.

F. Upon termination under paragraphs 15.03.C or 15.03.D above, the OWNER may take over the work and may award another party a contract to complete the work under this Contract.

G. If, after termination for failure of the CONTRACTOR to fulfill contractual obligations, it is determined that the CONTRACTOR had not failed to fulfill contractual obligations, the termination shall be deemed to have been for the convenience of the OWNER. In such event, adjustment of the Contract Price shall be made as provided in paragraph 15.03.D of this clause.

15.04 CONTRACTOR May Stop Work or Terminate

A. If, through no act or fault of CONTRACTOR, the Work is suspended for more than 90 consecutive days by OWNER or under an order of court or other public authority, or ENGINEER fails to act on any Application for Payment within 30 days after it is submitted, or OWNER fails for 30 days to pay CONTRACTOR any sum finally determined to be due, then CONTRACTOR may, upon seven days written notice to OWNER and ENGINEER, and provided OWNER or ENGINEER do not remedy such suspension or failure within that time, terminate the Contract and recover from OWNER payment on the same terms as provided in paragraph 15.03. In lieu of terminating the Contract and without prejudice to any other right or remedy, if ENGINEER has failed to act on an Application for Payment within 30 days after it is submitted, or OWNER has failed for 30 days to pay CONTRACTOR any sum finally determined to be due, CONTRACTOR may, seven days after written notice to OWNER and ENGINEER, stop the Work until payment is made of all such amounts due CONTRACTOR, including interest thereon. The provisions of this paragraph 15.04 are not intended to preclude CONTRACTOR from making a Claim under paragraph 10.05 for an adjustment in Contract Price or Contract Times or otherwise for expenses or damage directly attributable to CONTRACTOR's stopping the Work as permitted by this paragraph.

B. This Contract may be terminated in whole or in part in writing by either party in the event of substantial failure by the other party to fulfill its obligations under the Contract through no fault of the terminating party, provided that no termination may be effected unless the other party is given (1) not less than ten (10) calendar days written notice (delivered by certified mail, return receipt requested) of intent to terminate, and (2) an opportunity for consultation with the terminating party prior to termination.

ARTICLE 16 - DISPUTE RESOLUTION

16.01 Methods and Procedures

A. Dispute resolution methods and procedures, if any, shall be as set forth in the Supplementary Conditions. If no method and procedure has been set forth, and subject to the provisions of paragraphs 9.09 and 10.05, OWNER and CONTRACTOR may exercise such rights or remedies as either may otherwise have under the Contract Documents or by Laws or Regulations in respect of any dispute.

ARTICLE 17 - MISCELLANEOUS

17.01 Giving Notice

A. Whenever any provision of the Contract Documents requires the giving of written notice, it will be deemed to have been validly given if delivered in person to the individual or to a member of the firm or to an officer of the corporation for whom it is intended, or if delivered at or sent by registered or certified mail, postage prepaid, to the last business address known to the giver of the notice.

17.02 Computation of Times

A. When any period of time is referred to in the Contract Documents by days, it will be computed to exclude the first and include the last day of such period. If the last day of any such period falls on a Saturday or Sunday or on a day made a legal holiday by the law of the applicable jurisdiction, such day will be omitted from the computation.

17.03 Cumulative Remedies

A. The duties and obligations imposed by these General Conditions and the rights and remedies available hereunder to the parties hereto are in addition to, and are not to be construed in any way as a limitation or, any rights and remedies available to any or all of them which are otherwise imposed or available by Laws and Regulations, by special warranty or guarantee, or by other provisions of the contract Documents, and the provisions of this paragraph will be as effective as if repeated specifically in the Contract Documents in connection with each particular duty, obligation, right, and remedy to which they apply.

17.04 Survival of Obligations

A. All representations, indemnifications, warranties, and guarantees made in, required by, or given in accordance with the Contract Documents, will survive final payment, completion, and an acceptance of the Work or termination or completion of the Agreement.

17.05 Controlling Law

A. The Contract is to be governed by the law of the state in which the Project is located, and any litigation arising out of this Contract shall be brought in a court located in the State of New Hampshire.

17.06 Access To Records

A. At all times during regular business hours, CONTRACTOR shall provide full and free access to the OWNER, ENGINEER, and State of New Hampshire to any books, documents, papers, and records related to the work for the purpose of examination, audit, and duplication. The CONTRACTOR shall maintain all required accounts, records, and books for three years after final completion of the work.

17.07 Road Closures and Traffic Delays

A. Partial or full closure of streets in order to facilitate construction will be permitted, or required by the Engineer in accordance with the following:

1. If the CONTRACTOR proposes a closure, the CONTRACTOR notifies the OWNER in writing at least 5 days prior to the proposed closure of his intent to close the road.
2. At least 5 days prior to the proposed closure, the CONTRACTOR shall submit a detour traffic plan for each location being detoured.
3. The CONTRACTOR shall install standard traffic control devices in accordance with the Detour Signage plan provided in the bid documents and the Manual on Uniform Traffic Control Devices (MUTCD.)
4. The detour signage shall be covered when the road closure is not in effect.

B. CONTRACTOR shall notify the following agencies of any traffic delays or road closures three days in advance of the work:

Nashua Police Department:	(603) 594-3500
Nashua Fire Department:	(603) 594-3652
School Bus Garage:	(603) 594-4300
Nashua Solid Waste Department	(603) 589-3410
Nashua Building Department	(603) 589-3080

17.08 Prohibited Interests

CONTRACTOR shall not allow any officer or employee of the OWNER to have any indirect or direct interest in this contract or the proceeds of this contract CONTRACTOR warrants that no officer or employee of the OWNER has any

direct or indirect interest, whether contractual, noncontractual, financial or otherwise, in this contract or in the business of CONTRACTOR. If any such interest comes to the attention of CONTRACTOR at any time, a full and complete disclosure of the interest shall be immediately made in writing to the OWNER. CONTRACTOR also warrants that it presently has no interest and that it will not acquire any interest, direct or indirect, which would conflict in any manner or degree with the performance of services required to be performed under this contract. CONTRACTOR further warrants that no person having such an interest shall be employed in the performance of this contract. If OWNER determines that a conflict exists and was not disclosed to the OWNER, it may terminate the contract at will or for cause in accordance with Article 15.02.

In the event Contractor (or any of its officers, partners, principals, or employees acting with its authority) is convicted of a crime involving a public official arising out or in connection with the procurement of work to be done or payments to be made under this contract, City may terminate the contract at will or for cause in accordance with paragraph 9. Upon termination, Contractor shall refund to the City any profits realized under this contract, and Contractor shall be liable to the City for any costs incurred by the City in completing the work described in this contract. At the discretion of the City, these sanctions shall also be applicable to any such conviction obtained after the expiration or completion of the contract.

Contractor warrants that no gratuities (including, but not limited to, entertainment or gifts) were offered or given by Contractor to any officer or employee of the City with a view toward securing a contract or securing favorable treatment with respect to the awarding or amending or making of any determinations with respect to the performance of this contract. If City determines that such gratuities were or offered or given, it may terminate the contract at will or for cause in accordance with Article 15.02.

The rights and remedies of this section shall in no way be considered for be construed as a waiver of any other rights or remedies available to the City under this contract or at law.

DIVISION 7
SUPPLEMENTARY CONDITIONS

TABLE OF CONTENTS
FOR SUPPLEMENTARY CONDITIONS

	<u>PAGE</u>
ARTICLE 2 – PRELIMINARY MATTERS.....	2
SC-2.06B Subcontractor's Pre-Construction Meetings	
ARTICLE 6 -- CONTRACTOR'S RESPONSIBILITY.....	2
SC-6.02C Labor; Working Hours; School Zone	
ARTICLE 17 -- MISCELLANEOUS	2
SC-17.07 Detours, Reducing Traffic to One Lane.....	3
SC-17.09 Cooperation with refuse pickup	3

SUPPLEMENTARY CONDITIONS TO THE STANDARD GENERAL CONDITIONS

These Supplementary Conditions amend or supplement the Standard General Conditions of the Construction Contract and other provisions of the Contract Documents as indicated below. All provisions which are not so amended or supplemented remain in full force and effect.

ARTICLE 2 - PRELIMINARY MATTERS

SC-2.06B Subcontractor's Pre-Construction Meetings

Each Individual Subcontractor will be required to attend a Pre-Construction Meeting to discuss technical, safety, schedule and other issues. Each meeting shall be attended by the Subcontractor's responsible person in charge for the work and by the contractor's superintendent.

ARTICLE 6 -- CONTRACTOR'S RESPONSIBILITY

This section below REPLACES section 6.02C of the General Conditions.

SC-6.02C Labor; Working Hours; School Zone

Working hours shall generally be from 7:00 AM to 5:00 PM Monday through Friday, except as noted herein. No weekend, holiday or night work allowed without expressed written approval of the City Engineer.

This work is being constructed in the school zone of Mt. Pleasant Street Elementary School. Heavy congestion of vehicles and pedestrians are expected **at all crosswalk locations** at morning arrivals and afternoon dismissals of students. Morning arrivals will be during the period of 7:45 am to 8:30 am. Dismissals occur on the following schedule: Preschool dismisses at 10:40am for the morning session and 2:40 pm for the afternoon session. Kindergarten is dismissed at 2:35 p.m. Dismissal is at 2:50 pm for grades 1 through 5.

The Contractor shall not start work on the French Street/Manchester Street and Mt. Pleasant Street/Manchester Street crosswalks until after 8:30 am Monday through Fridays. Contractor shall open all lanes of traffic at these two work areas from the period 2:20 pm to 3:05 pm Monday through Fridays to allow for dismissal of students. Early release occurs on one Wednesday a month and students are dismissed at 12:50 pm. On Early Release Wednesdays, the Contractor shall open all lanes of traffic at these two work areas from the period 12:35 pm to 1:05 pm. A School Calendar is available from the Engineer, if requested by the Contractor.

ARTICLE 17 -- MISCELLANEOUS

SC-17.07 Road Closures and Traffic Delays

Add the following new paragraphs immediately after paragraph 17.07A.4:

5. Manchester Street and Concord Street Detours. Traffic shall be reduced to one lane and/or detoured around each section of work as work progresses. The Contractor shall keep one lane of traffic open on Concord Street and Manchester Street at all times, unless expressed written approval is given by the City Engineer. A traffic plan shall be submitted by the contractor showing the one lane reduction/traffic detour (if warranted) around all work sites, subject to approval the City Engineering office. This plan may be updated by the City Traffic Engineer, and will show the sign type needed at that time. **A traffic plan with lane reduction and/or detouring will be approved by the City Engineer's Office 24 hours before construction can begin.**

6. Other Street Detours (French Street, Mt Pleasant Street, Laton Street and Orange Street). The contractor shall reduce to one lane and/or detour traffic around the work area in each of these streets with the possible exception of Orange Street. Due to the volume of traffic and width of roadway on Orange Street, the Contractor should try to maintain 2-way traffic, if not, at least one-way traffic with flaggers at each end. A traffic plan shall be submitted by the contractor showing the traffic detour around all work sites subject to approval the City Engineering office. **A traffic plan with lane reduction and/or detouring will be approved by the City Engineer's Office 24 hours before construction can begin.**

7. Street Opening Permit. The Contractor shall obtain an approved Street Opening Permit from the Permits Coordinator in the City Engineer's Office prior to beginning work.

SC-17.09 Cooperation with refuse pickup:

The contractor shall determine the schedule for trash pickup by contacting The City of Nashua Solid Waste Department. The contractor shall cooperate and make arrangements to insure that trash pick up is not delayed or obstructed in any way. This may involve the contractor bring trash barrels to the front or backside of the work area for pickup by the Solid Waste Department and then returning the barrels back to each house.

DIVISION 8

SPECIAL PROVISIONS

Applicability

The Project or Program to which the construction work covered by this contract pertains is being assisted by the United States of America and the following Federal Labor Standards Provisions are included in this Contract pursuant to the provisions applicable to such Federal assistance.

A. 1. (i) Minimum Wages. All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR Part 3), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics. Contributions made or costs reasonably anticipated for bona fide fringe benefits under Section I(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of 29 CFR 5.5(a)(1)(iv); also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs, which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period.

Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under 29 CFR 5.5(a)(1)(ii) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible, place where it can be easily seen by the workers.

(ii) (a) Any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. HUD shall approve an additional classification and wage rate and fringe benefits therefor only when the following criteria have been met:

(1) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(2) The classification is utilized in the area by the construction industry; and

(3) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(b) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and HUD or its designee agree on the classification and wage rate (including the amount designated for fringe benefits where

appropriate), a report of the action taken shall be sent by HUD or its designee to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, D.C. 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise HUD or its designee or will notify HUD or its designee within the 30-day period that additional time is necessary. (Approved by the Office of Management and Budget under OMB control number 1215-0140.)

(c) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and HUD or its designee do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), HUD or its designee shall refer the questions, including the views of all interested parties and the recommendation of HUD or its designee, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise HUD or its designee or will notify HUD or its designee within the 30-day period that additional time is necessary. (Approved by the Office of Management and Budget under OMB Control Number 1215-0140.)

(d) The wage rate (including fringe benefits where appropriate) determined pursuant to subparagraphs (1)(ii)(b) or (c) of this paragraph, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

(iii) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

(iv) If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program. (Approved by the Office of Management and Budget under OMB Control Number 1215-0140.)

2. Withholding. HUD or its designee shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld from the contractor under this contract or any other Federal contract with the same prime contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee or helper, employed or working on the site of the work, all or part

of the wages required by the contract, HUD or its designee may, after written notice to the contractor, sponsor, applicant, or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased. HUD or its designee may, after written notice to the contractor, disburse such amounts withheld for and on account of the contractor or subcontractor to the respective employees to whom they are due. The Comptroller General shall make such disbursements in the case of direct Davis-Bacon Act contracts.

3. (i) Payrolls and basic records. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in Section I(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5 (a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in Section I(b)(2)(B) of the Davis-Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs. (Approved by the Office of Management and Budget under OMB Control Numbers 1215-0140 and 1215-0017.)

(ii) (a) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to HUD or its designee if the agency is a party to the contract, but if the agency is not such a party, the contractor will submit the payrolls to the applicant sponsor, or owner, as the case may be, for transmission to HUD or its designee. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i). This information may be submitted in any form desired. Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal Stock Number 029-005-00014-1), U.S. Government Printing Office, Washington, DC 20402. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. (Approved by the Office of Management and Budget under OMB Control Number 1215-0149.)

(b) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

(1) That the payroll for the payroll period contains the information required to be maintained under 29 CFR 5.5 (a)(3)(i) and that such information is correct and complete;

(2) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll

period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in 29 CFR Part 3;

(3) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(c) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by subparagraph A.3.(ii)(b).

(d) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 231 of Title 31 of the United States Code.

(iii) The contractor or subcontractor shall make the records required under subparagraph A.3.(i) available for inspection, copying, or transcription by authorized representatives of HUD or its designee or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, HUD or its designee may, after written notice to the contractor, sponsor, applicant or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

4. Apprentices and Trainees.

(i) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the

journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(ii) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(iii) Equal employment opportunity. The utilization of apprentices, trainees and journeymen under 29 CFR Part 5 shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR Part 3 which are incorporated by reference in this contract

6. Subcontracts. The contractor or subcontractor will insert in any subcontracts the clauses contained in subparagraphs 1 through 11 of this paragraph A and such other clauses as HUD or its designee may by appropriate instructions require, and a copy of the applicable prevailing wage decision, and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in this paragraph.

7. Contract termination; debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act Requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are herein incorporated by reference in this contract

9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR Parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and HUD or its designee, the U.S. Department of Labor, or the employees or their representatives.

10. (i) Certification of Eligibility. By entering into this contract the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of Section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1) or to be awarded HUD contracts or participate in HUD programs pursuant to 24 CFR Part 24.

(ii) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of Section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1) or to be awarded HUD contracts or participate in HUD programs pursuant to 24 CFR Part 24.

(iii) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001. Additionally, U.S. Criminal Code, Section 1010, Title 18, U.S.C., "Federal Housing Administration transactions", provides in part: "Whoever, for the purpose of . . . influencing in any way the action of such Administration.... makes, utters or publishes any statement knowing the same to be false..... shall be fined not more than \$5,000 or imprisoned not more than two years, or both."

11. Complaints, Proceedings, or Testimony by Employees. No laborer or mechanic to whom the wage, salary, or other labor standards provisions of this Contract are applicable shall be discharged or in any other manner discriminated against by the Contractor or any subcontractor because such employee has filed any complaint or instituted or caused to be instituted any proceeding or has testified or is about to testify in any proceeding under or relating to the labor standards applicable under this Contract to his employer.

B. Contract Work Hours and Safety Standards Act. The provisions of this paragraph B are applicable only where the amount of the prime contract exceeds \$100,000. As used in this paragraph, the terms "laborers" and "mechanics" include watchmen and guards.

(1) Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of 40 hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of 40 hours in such workweek.

(2) Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in subparagraph

graph (1) of this paragraph, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in subparagraph (1) of this paragraph, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of 40 hours without payment of the overtime wages required by the clause set forth in sub paragraph (1) of this paragraph.

(3) Withholding for unpaid wages and liquidated damages. HUD or its designee shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contract, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act which is held by the same prime contractor such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in subparagraph (2) of this paragraph.

(4) Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses set forth in subparagraph (1) through (4) of this paragraph and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in subparagraphs (1) through (4) of this paragraph.

C. Health and Safety. The provisions of this paragraph C are applicable only where the amount of the prime contract exceeds \$100,000.

(1) No laborer or mechanic shall be required to work in surroundings or under working conditions which are unsanitary, hazardous, or dangerous to his health and safety as determined under construction safety and health standards promulgated by the Secretary of Labor by regulation.

(2) The Contractor shall comply with all regulations issued by the Secretary of Labor pursuant to Title 29 Part 1926 and failure to comply may result in imposition of sanctions pursuant to the Contract Work Hours and Safety Standards Act, 40 USC 3701 et seq.

(3) The Contractor shall include the provisions of this paragraph in every subcontract so that such provisions will be binding on each subcontractor. The Contractor shall take such action with respect to any subcontract as the Secretary of Housing and Urban Development or the Secretary of Labor shall direct as a means of enforcing such provisions.

General Decision Number: NH140032 01/03/2014 NH32

Superseded General Decision Number: NH20130032

State: New Hampshire

Construction Type: Highway

County: Hillsborough County in New Hampshire.

HIGHWAY CONSTRUCTION PROJECTS (excluding tunnels, building structures in rest area projects & railroad construction; bascule, suspension & spandrel arch bridges designed for commercial navigation, bridges involving marine construction; and other major bridges).

Modification Number	Publication Date
0	01/03/2014

* SUNH2011-028 08/15/2011

	Rates	Fringes
CARPENTER (Excluding Form Work).....	\$ 24.27	1.06
CARPENTER (Form Work Only).....	\$ 19.93	1.06
ELECTRICIAN.....	\$ 23.22	2.78
INSTALLER: Guardrail.....	\$ 20.50	6.30
IRONWORKER, REINFORCING.....	\$ 20.18	0.00
IRONWORKER, STRUCTURAL.....	\$ 34.45	17.20
LABORER: BLASTER, ROCK.....	\$ 29.50	11.21
LABORER: Common or General.....	\$ 16.99	2.60
LABORER: Flagger.....	\$ 11.79	1.37
LABORER: Highway/Parking Lot Striping.....	\$ 17.95	0.00
LABORER: Landscape.....	\$ 14.40	0.00
LABORER: Pipelayer.....	\$ 17.63	2.72
OPERATOR: Auger.....	\$ 26.07	0.00
OPERATOR: Backhoe.....	\$ 27.05	7.95
OPERATOR: Bobcat/Skid Steer/Skid Loader.....	\$ 19.25	0.00
OPERATOR: Bucket.....	\$ 25.19	0.00
OPERATOR: Bulldozer.....	\$ 25.39	5.09

OPERATOR: Crane.....	\$ 23.37	2.21
OPERATOR: Drill Rig Caissons....	\$ 33.46	19.78
OPERATOR: Excavator.....	\$ 24.98	6.56
OPERATOR: Grader/Blade.....	\$ 25.75	6.00
OPERATOR: Loader.....	\$ 25.40	7.51
OPERATOR: Mechanic.....	\$ 25.12	3.44
OPERATOR: Oiler.....	\$ 29.54	16.15
OPERATOR: Paver.....	\$ 28.88	17.05
OPERATOR: Roller.....	\$ 25.23	9.69
OPERATOR: Post Driver/Pounder....	\$ 23.16	6.32
TRUCK DRIVER, Includes all axles including Dump Trucks.....	\$ 17.42	3.37
TRUCK DRIVER: Low Bed Truck.....	\$ 20.77	4.27

WELDERS - Receive rate prescribed for craft performing
operation to which welding is incidental.

=====

Unlisted classifications needed for work not included within
the scope of the classifications listed may be added after
award only as provided in the labor standards contract clauses
(29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification
and wage rates that have been found to be prevailing for the
cited type(s) of construction in the area covered by the wage
determination. The classifications are listed in alphabetical
order of "identifiers" that indicate whether the particular
rate is union or non-union.

Union Identifiers

An identifier enclosed in dotted lines beginning with
characters other than "SU" denotes that the union
classification and rate have found to be prevailing for that
classification. Example: PLUM0198-005 07/01/2011. The first
four letters , PLUM, indicate the international union and the
four-digit number, 0198, that follows indicates the local union
number or district council number where applicable , i.e.,
Plumbers Local 0198. The next number, 005 in the example, is

an internal number used in processing the wage determination. The date, 07/01/2011, following these characters is the effective date of the most current negotiated rate/collective bargaining agreement which would be July 1, 2011 in the above example.

Union prevailing wage rates will be updated to reflect any changes in the collective bargaining agreements governing the rates.

0000/9999: weighted union wage rates will be published annually each January.

Non-Union Identifiers

Classifications listed under an "SU" identifier were derived from survey data by computing average rates and are not union rates; however, the data used in computing these rates may include both union and non-union data. Example: SULA2004-007 5/13/2010. SU indicates the rates are not union majority rates, LA indicates the State of Louisiana; 2004 is the year of the survey; and 007 is an internal number used in producing the wage determination. A 1993 or later date, 5/13/2010, indicates the classifications and rates under that identifier were issued as a General Wage Determination on that date.

Survey wage rates will remain in effect and will not change until a new survey is conducted.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor

200 Constitution Avenue, N.W.
Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====

END OF GENERAL DECISION



(For Contractor's Optional Use; See Instructions, Form WH-347 Inst.)

Persons are not required to respond to the collection of information unless it displays a currently valid OMB control number.

[illegible]

We estimate that it will take an average of 56 minutes to complete this collection of information, including time for reviewing instructions searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. If you have any comments regarding these estimates or any other aspect of this collection of information, including suggestions for reducing this burden, send them to the Administrator, Wage and Hour Division, ESA, U. S. Department of Labor, Room S3502, 200 Constitution Avenue, N. W., Washington, D. C. 20210.

Date _____

I, _____ (Name of Signatory Party) _____ (Title)
do hereby state:

(1) That I pay or supervise the payment of the persons employed by

_____ on the _____
(Contractor or Subcontractor)
_____ that during the payroll period commencing on the _____
(Building or Work)

_____ day of _____, and ending the _____ day of _____,
all persons employed on said project have been paid the full weekly wages earned, that no rebates have
been or will be made either directly or indirectly to or on behalf of said

_____ from the full _____
(Contractor or Subcontractor)

weekly wages earned by any person and that no deductions have been made either directly or indirectly
from the full wages earned by any person, other than permissible deductions as defined in Regulations, Part
3 (29 CFR Subtitle A), issued by the Secretary of Labor under the Copeland Act, as amended (48 Stat. 948,
63 Stat. 108, 72 Stat. 967; 76 Stat. 357; 40 U.S.C. 276c), and described below:

(2) That any payrolls otherwise under this contract required to be submitted for the above period are
correct and complete; that the wage rates for laborers or mechanics contained therein are not less than the
applicable wage rates contained in any wage determination incorporated into the contract; that the
classifications set forth therein for each laborer or mechanic conform with the work he performed.

(3) That any apprentices employed in the above period are duly registered in a bona fide
apprenticeship program registered with a State apprenticeship agency recognized by the Bureau of
Apprenticeship and Training, United States Department of Labor, or if no such recognized agency exists in a
State, are registered with the Bureau of Apprenticeship and Training, United States Department of Labor.

(4) That:
(a) WHERE FRINGE BENEFITS ARE PAID TO APPROVED PLANS, FUNDS, OR PROGRAMS

☐ — in addition to the basic hourly wage rates paid to each laborer or mechanic listed in
the above referenced payroll, payments of fringe benefits as listed in the contract
have been or will be made to appropriate programs for the benefit of such
employees, except as noted in Section 4(c) below.

(b) WHERE FRINGE BENEFITS ARE PAID IN CASH

☐ — Each laborer or mechanic listed in the above referenced payroll has been paid,
as indicated on the payroll, an amount not less than the sum of the applicable
basic hourly wage rate plus the amount of the required fringe benefits as listed
in the contract, except as noted in Section 4(c) below.

(c) EXCEPTIONS

EXCEPTION (CRAFT)	EXPLANATION

REMARKS:

--	--

NAME AND TITLE	SIGNATURE
THE WILLFUL FALSIFICATION OF ANY OF THE ABOVE STATEMENTS MAY SUBJECT THE CONTRACTOR OR SUBCONTRACTOR TO CIVIL OR CRIMINAL PROSECUTION. SEE SECTION 1001 OF TITLE 18 AND SECTION 231 OF TITLE 31 OF THE UNITED STATES CODE.	

LIST OF EXHIBITS

- A. Notice to Proceed
- B. Application for Payment
- C. Change Order
- D. Certificate of Substantial Completion
- E. Affidavit of Payment

**DIVISION 9
EXHIBITS**

NOTICE TO PROCEED

DATED: _____

TO: _____
(Bidder)

ADDRESS: _____

OWNER'S PROJECT NO. : _____

PROJECT: _____
(Insert name of Contract as it appears in the Bidding Document)

OWNER'S CONTRACT NO. _____

CONTRACT FOR: _____

You are notified that the Contract Times under the above contract will commence to run on _____, 20____. By that date, you are to start performing your obligations under the Contract Documents. In accordance with Article 4 of the Agreement, the dates of Substantial Completion and Final Completion are _____ and _____, respectively.

Also before you may start any Work at the site you must:

(Add other requirements)

(OWNER)

By _____
(AUTHORIZED SIGNATURE)

(TITLE)

APPLICATION FOR PAYMENT NO. _____

TO: _____ (OWNER)

CONTRACT: _____

OWNER'S CONTRACT NO. _____ ENGINEER'S PROJECT NO. _____

FOR WORK ACCOMPLISHED THROUGH DATE OF _____

ITEM	CONTRACTOR's Schedule of Values			Work Completed	
	Unit Price	Quantity	Amount	Quantity	Amount
	\$		\$		\$
Total (Orig. Contract) C.O. No. 1 C.O. No. 2			\$		\$

Accompanying Documentation:

GROSS AMOUNT DUE.....\$

LESS %RETAINAGE.....\$

AMOUNT DUE TO DATE.....\$

LESS PREVIOUS PAYMENTS.....\$

AMOUNT DUE THIS APPLICATION.....\$

CONTRACTOR's Certification

The undersigned CONTRACTOR certifies that: (1) all previous progress payments received from OWNER on account of Work done under the Contract referred to above have been applied to discharge in full all obligations of CONTRACTOR incurred in connection with Work covered by prior Applications for Payment numbered 1 through _____ inclusive; (2) title to all Work, materials and equipment incorporated in said Work or otherwise listed in or covered by this Application for Payment will pass to OWNER at time of payment free and clear of all liens, claims, security interest and encumbrances (except such as are covered by Bond acceptable to OWNER indemnifying OWNER against any such lien, claim, security interest or encumbrance); and (3) all Work covered by this Application for Payment is in accordance with the Contract Documents and not *defective* as that term is defined in the Contract Documents.

Dated _____, 20____

CONTRACTOR

By _____
(Authorized Signature)

Payment of the above AMOUNT DUE THIS APPLICATION is recommended.

Dated _____, 20____

ENGINEER

By _____
(Authorized Signature)

INSTRUCTIONS

A. GENERAL INFORMATION

This standard form is intended as a guide only. Many projects require a much more extensive form with space for numerous items, descriptions of Change Orders, identification of variable quantity adjustments, summary of materials and equipment stored at the site and other information. It is expected that a separate form will be developed by Engineer or Contractor at the time Contractor's Schedule of Values is finalized. Note also that the format for retainage must be changed if the Agreement permits (or the Law provides), and Contractor elects, the deposit of securities in lieu of retainage. Refer to Article 14 of the General Conditions for provisions concerning payments to Contractor.

B. COMPLETING THE FORM

The Schedule of Values, submitted and approved as provided in paragraphs 2.6.3 and 2.9 of the General Conditions, should be copied in the space indicated on the Application For Payment form. Note that the cost of materials and equipment is often listed separately from the cost of their installation. All Change Orders affecting the Contract Price should be identified and include such supplemental Schedules of Values as required for progress payments.

The form is suitable for use in the Final Application for Payment as well as for Progress Payments; however, the required accompanying documentation is usually more extensive for final payment. All accompanying documentation should be identified in the space provided on the form.

C. ENGINEER'S REVIEW

Engineer *must* review all Applications for Payment with care to avoid recommending any payments not yet earned by Contractor. All accompanying documentation of legal nature, such as lien waivers, should be reviewed by Owner's attorney, and Engineer should so advise Owner.

CHANGE ORDER

No. _____

PROJECT: _____

OWNER'S CONTRACT NO.: _____

DATE OF ISSUANCE: _____

EFFECTIVE DATE: Upon City Approval

OWNER: _____ City of Nashua, NH _____

OWNER's Purchase Order NO.: _____

CONTRACTOR: _____

ENGINEER: _____

You are directed to make the following changes in the Contract Documents: Description, Purpose of Change Order, and Justification. Attachments: (List Documents supporting change)

New Price and Time Summary:

<u>CHANGE IN CONTRACT PRICE:</u>	<u>CHANGE IN CONTRACT TIMES:</u>
Original Contract Price \$0.00	Original Contract Times Ready for final payment: days or dates
Net changes from previous Change Orders \$0.00	Net change from previous Change Orders days
Contract Price prior to this Change Order \$0.00	Contract Times prior to this Change Order Ready for final payment: days or dates
Net Increase (decrease) of this Change Order \$0.00	Net Increase (decrease) of this Change Order days
Contract Price with all approved Change Orders \$0.00	Contract Times with all approved Change Orders Ready for final payment: days or dates

RECOMMENDED:

APPROVED:

ACCEPTED:

By: _____ Engineer
(Authorized Signature)

By: _____
Owner (Authorized Signature)

By: _____
Contractor (Authorized Signature)

Date: _____

Date: _____

Date: _____

Change Order #

CERTIFICATE OF SUBSTANTIAL COMPLETION

PROJECT: _____

OWNER'S CONTRACT NO: _____

DATE OF ISSUANCE: _____

CONTRACTOR: _____

ENGINEER: _____

This Certificate of Substantial Completion applies to all Work under the Contract Documents or to the following specified parts thereof:

TO _____ City of Nashua
(OWNER)

And To _____
(CONTRACTOR)

The Work to which this Certificate applies has been inspected by authorized representative of OWNER, CONTRACTOR, and ENGINEER, and that Work is hereby declared to be substantially complete in accordance with the Contract Documents on

(DATE OF SUBSTANTIAL COMPLETION)

A Tentative list of items to be completed or corrected is attached hereto. This list may not be all-inclusive, and the failure to include an item in it does not alter the responsibility of CONTRACTOR to complete all the Work in accordance with the Contract Documents. The items in the tentative list shall be completed or corrected by CONTRACTOR within _____ days of the above date of Substantial Completion.

From the date of Substantial Completion the responsibilities between OWNER and CONTRACTOR for security, operation, safety, maintenance, heat, utilities, insurance and warranties and guarantees shall be as follows:

RESPONSIBILITIES

OWNER: _____ City of Nashua _____

CONTRACTOR: _____

The following documents are attached to and made a part of this Certificate:

[For items to be attached see definition of Substantial Completion as supplemented and other specifically noted conditions precedent to achieving Substantial Completion as required by Contract Documents.]

This certificate does not constitute an acceptance of Work not in accordance with the Contract Documents nor is it a release of CONTRACTOR's obligation to complete the Work in accordance with the Contract Documents.

Executed by ENGINEER on _____, 20 _____

(ENGINEER)

By: _____
(Authorized Signature)

CONTRACTOR accepts this Certificate of Substantial Completion on _____, 20 _____

(CONTRACTOR)

By: _____
(Authorized Signature)

OWNER accepts this Certificate of Substantial Completion on _____, 20 _____

(OWNER)

By: _____
(Project Manager)

CONTRACTOR'S AFFIDAVIT

STATE OF: _____

COUNTY OF: _____

Before me, the undersigned, a _____
(Notary Public, Justice of Peace, Alderman)
in and for said County and State personally appeared, _____
(Individual, Partner or duly
authorized representative of corporate contractor) who being duly sworn according to law
deposes and says that the cost of all the Work, and outstanding claims and indebtedness of
whatever
nature arising out of the performance of the contract
between _____
(Owner)
and _____ of _____
(Contractor) (Address)
dated _____ for the construction of the _____
(Project Name)
and necessary appurtenant installations have been paid in full.

(Individual, Partner, or duly authorized representative of corporate contractor)

(Title)

Sworn to and subscribed before me

this _____ day of _____, 20 _____

Notary Public

**DIVISION 10
CONSTRUCTION
SPECIFICATIONS**

**Division 10 – Construction Specifications
CDBG Manchester St/Concord St Crosswalks**

All Items that are not included in the special provision shall comply with the latest approved NHDOT Standard Specifications for Road and Bridge Construction, the latest approved City of Nashua Standard Specifications for Road Construction Sewer and Drains, the latest approved NHDOT Standard Plans for Construction and the latest approved edition of Manual of Uniform Traffic Control Devices. The most stringent specification shall apply.

Unless otherwise noted all work will be paid for by the quantity actually installed.

Additional Technical Specifications

ITEM 618.6S - UNIFORMED OFFICERS

A. SCOPE

This work shall consist of furnishing qualified uniformed officers, with or without vehicles, as required to direct traffic through or around the Work as ordered by the Engineer.

B. MATERIALS AND CONSTRUCTION

The Contractor shall supply qualified uniformed officers as stated in Section 618 of the NHDOT Standard Specifications for Road and Bridge Construction, (Latest Edition). Uniformed officers shall only be used when there are no available flaggers and the Engineer has previously approved it. Daily coverage needs to be approved by the Engineer.

C. MEASUREMENT AND PAYMENT

Uniformed officers will be measured by the actual number of hours authorized, as determined by the Engineer. This item has a budgeted allowance as shown on the Bid Schedule. Payments to Contractor will be made based on approved hours and resulting dollar amounts on Police Department invoices and only after contractor's proof of payment to Police Department.

ITEM 618.7S - FLAGGERS

A. SCOPE

This work shall consist of furnishing qualified flaggers, as required to direct traffic through or around the Work as ordered by the Engineer.

B. MATERIALS AND CONSTRUCTION

**Division 10 – Construction Specifications
CDBG Manchester St/Concord St Crosswalks**

The Contractor shall supply qualified flaggers as stated in Section 618 of the NHDOT Standard Specifications for Road and Bridge Construction. Daily coverage needs to be approved by the Engineer.

C. MEASUREMENT AND PAYMENT

Flaggers will be measured by the actual number of hours authorized, as determined by the Engineer. This item has a budgeted allowance as shown on the Bid Form. In no case shall the gross hourly rate exceed \$22/hour for straight time work and \$33/hour for overtime work. Payments to Contractor will be made based on approved hours and resulting dollar amounts. In the case of outsourced flagger services, payments to Contractor will be made only after Contractor's proof of payment to flagger company

ITEM 619.1S - MAINTENANCE OF TRAFFIC

A. SCOPE

This work shall consist of providing and maintaining safe and passable traffic accommodations for public traffic and furnishing, erecting and maintaining necessary traffic signs, barricades, lights, signals, delineators, concrete barriers, signs, and other traffic control warning devices through the work zone. The contractor is responsible for preparing a work area that is free of parked vehicles or other obstructing objects. This includes, but is not limited to, erecting "no-parking" signs provided by the City of Nashua and returning same signs as directed by the Engineer.

B. MATERIALS AND CONSTRUCTION

The Contractor shall furnish all labor, materials, equipment and transportation necessary for the required maintenance of traffic needs based on the Contractors daily operations in accordance with Section 619 of the NHDOT Standard Specifications for Road and Bridge Construction, (Approved Latest Edition) and Section 6H of the MUTCD (Latest Edition). At a minimum, the Contractor's crew shall, at all times, carry Two (2) of the following signs to be erected as the need may arise:

- ROAD WORK AHEAD (MUTCD W20-1)
- ONE LANE ROAD AHEAD (MUTCD W20-4)
- DIRECTIONAL ARROW SIGN (MUTCD W1-6)
- FLAGGER SIGN (MUTCD W20-7)
- ROAD CLOSED AHEAD (MUTCD W20-3)

**Division 10 – Construction Specifications
CDBG Manchester St/Concord St Crosswalks**

C. MEASUREMENT AND PAYMENT

Maintenance of traffic will be paid for periodically and at final payment based on percent of total contract value completed.

**ITEM 'A' – IMPRINTED AGGREGATE REINFORCED PREFORMED THERMOPLASTIC
PAVEMENT MARKING SYSTEM**

1. **Use:** A durable imprinted aggregate reinforced preformed thermoplastic pavement marking system (herein "System") that provides a textured, highly attractive and durable topical treatment to the surface of asphalt pavement. Typically the system replicates, in relief, the grout lines common to brick or other types of unit pavers, but may also be used to create other patterns. It is intended for use on asphalt pavements to create traffic calming solutions and decorative crosswalks, medians, intersections and through areas in parking lots. It provides a seamless, aesthetic look without the trip hazards and ongoing maintenance often associated with pavers and stamped concrete. TrafficPatternsXD™ Stamped Asphalt Surfacing System or approved equal.
 - 1.1 The aggregate reinforced preformed thermoplastic is typically supplied in panels measuring 2 ft. x 2 ft. [$\pm\frac{1}{8}$ in.] (.61m x .61m [± 3 mm])
 - 1.2 The System must be able to be applied to asphalt surfaces without preheating the application surface to a specific temperature.
 - 1.3 The System must be able to be applied in temperatures down to 45°F (7°C) without any special storage, preheating or treatment of the material before application.
 - 1.4 The System is applied to asphalt pavement using proprietary reciprocating infrared heating equipment. A two-part epoxy sealer specified by the manufacturer must be applied to the substrate prior to preformed thermoplastic application to ensure proper adhesion, and to provide reinforcement for larger volumes of material. Immediately following sealer application, panels of aggregate reinforced preformed thermoplastic are positioned properly on the asphalt substrate. The preformed thermoplastic is then heated to the required melting temperature. Additional aggregate may be applied to the preformed thermoplastic surface as needed following the melting process, to achieve added friction properties and a uniform surface appearance. As the material is cooling, it is imprinted with a vibratory plate compactor and a template made from 3/8 in. (9.5 mm) flexible wire rope in the required design to create crisp, clean lines which define the pattern. For crosswalks, it is typically demarcated by applying white preformed thermoplastic transverse lines on both sides of the installation.
 - 1.5 The System is available in a variety of standard colors and patterns. Color can be used to create patterns within the crosswalk area to reflect the typical white "continental" crosswalk bars for additional visibility and awareness. Within certain limitations, custom patterns and colors are available upon request.
 - 1.6 The System shall utilize a resilient, aggregate reinforced preformed thermoplastic product which contains a minimum of thirty percent (30%) intermixed anti-skid/anti-slip elements and where the top surface contains anti-skid/anti-slip elements. These anti-skid/anti-slip elements must have a minimum hardness of 6 (Mohs scale).
 - 1.7 The System must be resistant to the detrimental effects of motor fuels, antifreeze, lubricants, hydraulic fluids, etc.

**Division 10 – Construction Specifications
CDBG Manchester St/Concord St Crosswalks**

2. **MANUFACTURING CONTROL AND ISO CERTIFICATION:** The System manufacturer must be ISO 9001:2008 certified for design, development and manufacturing of preformed thermoplastic, and provide proof of current certification.
3. **PREFORMED THERMOPLASTIC MATERIAL:** Must be composed of an ester modified rosin impervious to degradation by motor fuels, lubricants, etc. in conjunction with aggregates, pigments, binders, and anti-skid/anti-slip elements. Pigments and anti-skid/anti-slip elements must be uniformly distributed throughout the material. The material conforms to AASHTO designation M249, with the exception of the relevant differences due to the material being supplied in a preformed state, being non-reflective, and potentially being of a color different from white or yellow. PreMark® or approved equal.
 - 3.1 **Pigments:**
 - 3.1.1 **White:** The material shall be manufactured with sufficient titanium dioxide pigment to meet FHWA Docket No. FHWA-99-6190 Table 5 and Table 6 as revised and corrected.
 - 3.1.2 **Other Colors:** The pigment system must not contain heavy metals nor any carcinogen, as defined in 29 CFR 1910.1200 in amounts exceeding permissible limits as specified in relevant Federal Regulations.
 - 3.2 **Skid Resistance:** The surface of the material shall contain factory applied anti-skid/anti-slip elements with a minimum hardness of 6 (Mohs scale). Upon application the material shall provide a minimum skid resistance value of 60 BPN when tested according to ASTM E 303.
 - 3.3 **Slip Resistance:** The surface of the material shall contain factory applied anti-skid/anti-slip elements with a minimum hardness of 6 (Mohs scale). Upon application the material shall provide a minimum static friction of coefficient of 0.6 when tested according to ASTM C 1028 (wet and dry), and a minimum static coefficient of friction of 0.6 when tested according to ASTM D 2047.
 - 3.4 **Thickness:** The material must be supplied at a minimum thickness of 150 mil (3.8mm).
 - 3.5 **Environmental Resistance:** The material must be resistant to deterioration due to exposure to sunlight, water, salt or adverse weather conditions and impervious to oil and gasoline.
 - 3.6 **Storage Life:** The material may be stored for 12 months, if stored indoors and protected from the elements.
 - 3.7 **Transverse Lines to Supplement System Application:** Supplied as white, retroreflective preformed thermoplastic line stripe material in 90 mil (2.3 mm) or 125 mil (3.2 mm) thicknesses, material is available in 6 in. (.15m), 8 in. (.20m) or 12 in. (.30m) widths. This preformed thermoplastic material may be supplied and applied by the certified applicator in conjunction with the System, and is available from the System manufacturer. (Consult the manufacturer's published application instructions for the preformed thermoplastic line stripe material selected, for proper application methods.)
4. **SPECIALIZED APPLICATION EQUIPMENT:**
 - 4.1 **Stamping Templates:** A wire rope template is required in the execution of the System. The template is used for imprinting the defined pattern once the preformed thermoplastic has been applied. The wire rope diameter for the imprinting template used for the specified pattern is 3/8 in. (9.5mm). The stamping templates are distributed by the System manufacturer.
 - 4.2 **Heating Equipment:** The System manufacturer shall distribute reciprocating infrared heating equipment designed specifically to elevate the temperature of the preformed thermoplastic

Division 10 – Construction Specifications

CDBG Manchester St/Concord St Crosswalks

material and asphalt pavement without adversely affecting it. The primary heating unit must employ a bank of propane-fired infrared heaters, mounted on a track device that allows the heater bank to reciprocate back and forth over a designated area, thereby allowing the operator to monitor the temperature of the preformed thermoplastic at all times during the pavement heating process.

4.2.1 A smaller, mobile infrared heater distributed by the System manufacturer is designed specifically to heat areas such as borders and narrow areas that are inaccessible to the primary heaters. This secondary heater also allows the operator to monitor the temperature of the preformed thermoplastic at all times during the heating process.

4.2.2 An approved hand-held propane heat torch distributed by the System manufacturer shall be used to heat isolated areas of the preformed thermoplastic.

- 4.3 **Sealer:** A two-part epoxy sealer specified and distributed by the System manufacturer must be applied to the substrate prior to material application to ensure proper adhesion, and to provide reinforcement for larger volumes of material.
- 4.4 **Specialized Sealer Dispensing Gun:** Used to dispense the required two-part epoxy sealer onto the substrate. The sealer dispensing guns are distributed by the System manufacturer.
- 4.5 **Hand Held Finishing Tool:** Enables the applicator to complete the imprinting of the thermoplastic in areas around permanent structures, such as curbs and manholes covers, which may be inaccessible to the stamping template. The hand held finishing tools are distributed by the System manufacturer.
- 4.6 **Aggregate:** Supplemental anti-skid/anti-slip elements to be applied to the surface of the molten thermoplastic as needed, if the factory applied anti-skid/anti-slip elements embed too deeply into the surface of the molten thermoplastic material during the heating process. (Embedded aggregate is exposed upon wear for extended skid resistance.) The aggregate is distributed by the System manufacturer.
- 4.7 **Air Powered Spray Hopper:** Used to spray supplemental anti-skid/anti-slip elements (aggregate) on the surface of the molten preformed thermoplastic in a uniform manner. The air powered spray hoppers are distributed by the System manufacturer.
- 4.8 **Vibratory Plate Compactor (700-900 lb.):** Shall be used for pressing the 3/8" (9.5mm) wire rope stamping templates into the thermoplastic to create the specified pattern in both the thermoplastic and asphalt substrate. The System manufacturer does not supply vibratory plate compactors.

5. APPLICATION (Asphalt Substrate Only):

- 5.1 **Manufacturer Certified Applicator Requirement:** The System shall be supplied and applied only by an applicator certified by the System manufacturer. The applicator shall provide proof of current certification before commencing work. The Certified Applicator shall follow the System manufacturer's current published application procedures.
- 5.2 **Substrate Condition:** The System must only be applied to a stable, high quality asphalt pavement substrate over a stable base that is free of defects, as per the manufacturer published Substrate Guide. The asphalt pavement surface shall be dry and free from all foreign matter, including but not limited to dirt, dust, de-icing materials, and chemical residue.
- 5.3 **Procedure:** The System is applied to asphalt pavement using proprietary reciprocating infrared heating equipment. The material must be able to be applied at ambient and road temperatures down to 45°F (7°C) without any preheating of the pavement to a specific

Division 10 – Construction Specifications CDBG Manchester St/Concord St Crosswalks

temperature. A two-part epoxy sealer specified by the manufacturer must be applied to the substrate prior to preformed thermoplastic application. Immediately following sealer application, the panels of aggregate reinforced preformed thermoplastic are positioned properly on the asphalt substrate with the aggregate side facing up. The preformed thermoplastic is then heated to the required melting temperature. Additional aggregate may be applied to the preformed thermoplastic surface as needed following the melting process. As the material is cooling, it is imprinted with a stamping template made from 3/8 in. (9.5 mm) flexible wire rope in the required design using a vibratory plate compactor. The preformed thermoplastic material is then allowed to cool thoroughly before being opened to vehicle or pedestrian traffic. (Consult the manufacturer's published application procedures for complete information.)

- 5.4 The System shall not be applied to Portland Cement Concrete.
6. **PACKAGING:** The preformed thermoplastic material shall be packaged in cardboard cartons with a plastic sheet between each layer of preformed thermoplastic. The cartons in which packed shall be non-returnable and shall not exceed 25 in. (.64m) in length and 25 in. (.64m) in width. The cartons shall be labeled for ease of identification. The weight of the individual carton must not exceed seventy (70) pounds (32 kg). A protective film around the carton must be applied in order to protect the material from rain or premature aging.
7. **TECHNICAL SERVICES:** The successful bidder shall provide technical services as required.
8. **PERFORMANCE:** Where applicable, the preformed thermoplastic pavement overlay material shall meet state specifications and be approved for use by the appropriate state agency.

ITEM 'B' – PREFORMED THERMOPLASTIC PAVEMENT MARKINGS

1. **USE:** A durable, retroreflective pavement marking material suitable for use as roadway, intersection, commercial or private pavement delineation and markings.
 - 1.1 The markings must be a resilient white or yellow thermoplastic product with uniformly distributed glass beads throughout the entire cross sectional area. The markings must be resistant to the detrimental effects of motor fuels, lubricants, hydraulic fluids, antifreeze, etc. Lines, legends and symbols are capable of being affixed to bituminous and/or portland cement concrete pavements by the use of the normal heat of a propane torch. Other colors shall be available as required.
 - 1.2 The markings must be capable of conforming to pavement contours, breaks and faults through the action of traffic at normal pavement temperatures. The markings shall have resealing characteristics, such that it is capable of fusing with itself and previously applied thermoplastic when heated with the torch.
 - 1.3 The markings shall not have minimum ambient and road temperature requirements for application, storage, or handling.
2. **MANUFACTURING CONTROL AND ISO CERTIFICATION:** The manufacturer must be ISO 9001:2008 certified and provide proof of current certification. The scope of the certification shall include manufacture of preformed thermoplastic marking materials.

Division 10 – Construction Specifications

CDBG Manchester St/Concord St Crosswalks

3. **MATERIAL:** Must be composed of an ester modified rosin resistant to degradation by motor fuels, lubricants etc. in conjunction with aggregates, pigments, binders and glass beads which have been factory produced as a finished product, and meets the requirements of the current edition of the Manual on Uniform Traffic Control Devices for Streets and Highways. The thermoplastic material conforms to AASHTO designation M249, with the exception of the relevant differences due to the material being supplied in a preformed state.

3.1 Graded Glass Beads:

- 3.1.1 The material must contain a minimum of thirty percent (30%) intermixed graded glass beads by weight. The intermixed beads shall be conforming to AASHTO designation M247, with minimum 80% true spheres and minimum refractive index of 1.50.
- 3.1.2 The material must have factory applied coated surface beads in addition to the intermixed beads at a rate of 1 lb. ($\pm 10\%$) per 10 sq. ft. These factory applied coated surface beads shall have a minimum of 90% true spheres, minimum refractive index of 1.50, and meet the following gradation.

Size Gradation		Retained, %	Passing, %
US Mesh	μm		
12	1700	0 - 2%	98 - 100%
14	1400	0 - 3.5%	96.5 - 100%
16	1180	2 - 25%	75 - 98%
18	1000	28 - 63%	37 - 72%
20	850	63 - 72%	28 - 37%
30	600	67 - 77%	23 - 33%
50	300	89 - 95%	5 - 11%
80	200	97-100%	0 - 3%

3.2 Pigments:

- 3.2.1 White: The material shall be manufactured with sufficient titanium dioxide pigment to meet FHWA Docket No. FHWA-99-6190 Table 5 and Table 6 as revised and corrected.
- 3.2.2 Red, Blue, and Yellow: The material shall be manufactured with sufficient pigment to meet FHWA Docket No. FHWA-99-6190 Table 5 and Table 6 as revised and corrected. The yellow pigments must be organic and must be heavy-metal free.
- 3.2.3 Other Colors: The pigments must be heavy-metal free.
- 3.3 Heating indicators: The top surface of the material (same side as the factory applied surface beads) shall have regularly spaced indents. These indents shall act as a visual cue during application that the material has reached a molten state so satisfactory adhesion and proper bead embedment has been achieved and a post-application visual cue that the installation procedures have been followed.
- 3.4 Skid Resistance: The surface, with properly applied and embedded surface beads, must provide a minimum resistance value of 45 BPN when tested according to ASTM E 303.
- 3.5 Thickness: The material must be supplied at a minimum thickness of 125 mils (3.15 mm).
- 3.6 Versatility: As an option, turn arrows and combination arrows may come without surface applied glass beads, thus facilitating the use of those arrows as either left or right indicators, thereby reducing inventory requirements.
- 3.7 Environmental Resistance: The material must be resistant to deterioration due to exposure to sunlight, water, salt or adverse weather conditions and impervious to oil and gasoline.

Division 10 – Construction Specifications
CDBG Manchester St/Concord St Crosswalks

- 3.8 **Retroreflectivity:** The material, when applied in accordance with manufacturer's guidelines, must demonstrate a uniform level of sufficient nighttime retroreflection when tested in accordance to ASTM E 1710. The applied material must have an initial minimum intensity reading of 500 mcd·m⁻²·lx⁻¹ for white and 300 mcd·m⁻²·lx⁻¹ for yellow as measured with an LTL-2000 or LTL-X Retroreflectometer.

Note: Initial retroreflection is affected by the amount of heat applied during installation. When ambient temperatures are such that greater amounts of heat are required for proper installation, initial retroreflection levels may be affected.

4. APPLICATION:

- 4.1 **Asphalt:** The materials shall be applied using the propane torch method recommended by the manufacturer. The material must be able to be applied without minimum requirements for ambient and road temperatures and without any preheating of the pavement to a specific temperature. The material must be able to be applied without the use of a thermometer. The pavement shall be clean, dry and free of debris. Supplier must enclose application instructions in English and Spanish with each box/package.
- 4.2 **Portland Cement Concrete:** The same application procedure shall be used as described under Section 4.1. However, a compatible primer sealer shall be applied before application to assure proper adhesion.

5. **PACKAGING:** The preformed thermoplastic markings shall be placed in protective plastic film with cardboard stiffeners where necessary to prevent damage in transit. Linear material must be cut to a maximum of 3' long pieces. Legends and symbols must also be supplied in flat pieces. The cartons in which packed shall be non-returnable and shall not exceed 40" in length and 25" in width, and be labeled for ease of identification. The weight of the individual carton must not exceed seventy (70) pounds. A protective film around the box must be applied in order to protect the material from rain or premature aging.

6. **TECHNICAL SERVICES:** The successful bidder shall provide technical services as required.

ITEM 'C' – BRICK MATERIAL AND INSTALLATION

A. SCOPE

This work shall consist of installing Pine Hall Brick 2 1/4" X4"X8" English Edge Series Full Range following the detail sheet of the plan set provided or as ordered by the Engineer. This style conforms to the color and style used for the recently constructed Main Street sidewalks to create a cohesive look in this area.

B. MATERIALS AND CONSTRUCTION

The Contractor shall supply all labor, materials, equipment and transportation necessary for the required work.

Division 10 – Construction Specifications CDBG Manchester St/Concord St Crosswalks

Installation

Compact 6 inches of gravel at 95 % or more compaction as shown on the detail then install 1" sand bed minimum also compacted (see detail for additional info)

Wet saw is required for cutting of bricks and filling in pieces where needed. No other method will be acceptable. All adjacent surfaces such as curb tops, manhole/handhole covers and rims, tree grates, etc. shall be absolutely flush with brick paving surfaces after compaction. Once the bricks are placed in their specified patterns, they shall be compacted with a plate compactor. The compactor shall have a minimum force of 5000 lbs. and a frequency of 75 to 90 cycles per second. Brick pavers shall be tamped with manual equipment in tight areas to assure tight bonding with setting material.

Work shall proceed within an area only when that area can be completed within the work period. Secure all loose materials and provide temporary accessible edges of partially completed areas of brick that will be accessible to the public.

Newly laid bricks shall be protected at all times by panels of plywood. These may be advanced as work progresses; however, the plywood protection shall be left in areas that will be subjected to continued movement of materials and equipment. All necessary precautions shall be taken in order to avoid depressions and protect brick alignment.

After the bricks are in place, when the brick is thoroughly dry, apply dry sand/cement and sweep into the joint voids around the bricks. Re-apply a minimum of three times until all the voids are filled and sweep away all extraneous material.

Brick shall be sealed using KURE 1315 and applied according to the manufacturers recommendations.

Prior to acceptance, the brick paved area shall be flooded with water to assure that there are no depressions. Remove and reset bricks as required until surface is true to line and grade. Refill sand-cement joints as necessary until all joints are filled to finish grade.

Sidewalks shall be installed in strict conformance with the layout and grades shown on the Drawings, current Americans with Disabilities Act (ADA) and City of Nashua regulations.


The Contractor shall establish grade elevations at all sidewalk locations. The Contractor shall use a digital "Smart Level" to check all sub-base grades for compliance prior to installation of bricks. The Contractor shall not proceed with brick installation on a sidewalk that is out of compliance without first contacting the Engineer.

C. MEASUREMENT AND PAYMENT

**Division 10 – Construction Specifications
CDBG Manchester St/Concord St Crosswalks**

Brick walk will be measured by the square yard, complete in place. Payment for work under these items shall be at the contract unit price per square yard and shall include full compensation for excavation, furnishing and installing new bricks, sand setting bed, gravel layer, sand-cement joint filler, labor, tools, equipment, disposal of construction debris (existing sidewalk, concrete, asphalt, etc.), and any other incidentals necessary for the satisfactory completion of this work as specified.

NOTES ON EXCLUSIONS: Disposal of excavated soil and HMA base is not included for payment under this item and shall be paid for separately.



English Edge® Full Range

English Edge Series

English Edge® is the ultimate in interlocking pavers for sand-based applications. Sizes: 2 1/4" x 4" x 8" pedestrian/light vehicular and 2 3/4" x 4" x 8" heavy vehicular. Made from hardened Triassic shale, this paver features beveled edges on both bed surfaces making it easy to install and to flip over should the need arise. Spacer nibs provide consistent joints with virtually no edge chippage even on driveways. Elegant and prestigious, any English Edge® color you choose will last a lifetime. All our pavers exceed the most stringent ASTM standards with high strength (10,000 psi+) and low water absorption (5-6%).



**Division 10 – Construction Specifications
CDBG Manchester St/Concord St Crosswalks**

ITEM 'D' – BOLLARD – STEEL FILLED WITH CONCRETE

A. SCOPE

This work shall consist of installing and providing bollards following the detail sheet of the plan set provided or as ordered by the Engineer.

B. MATERIALS AND CONSTRUCTION

The Contractor shall supply all labor, materials, equipment and transportation necessary for the required work. Bollards shall be painted black with a minimum of two coats.

C. MEASUREMENT AND PAYMENT

Bollard – Steel Filled with Concrete will be measured by each installed bollard. Payment for work under these items shall be at the contract unit price per unit and shall include full compensation for excavation, furnishing and installing bollards, concrete, paint, labor, tools, equipment, disposal of construction debris (existing sidewalk, concrete, asphalt, etc.), and any other incidentals necessary for the satisfactory completion of this work as specified.

ITEM 'E' – RECTANGULAR RAPID FLASH BEACON SYSTEM

Description: Furnish and install a pedestrian actuated rectangular rapid flashing beacon (RRFB) at the locations indicated on the plans or where directed by the Engineer.

General Requirements: Each RRFB will be a complete assembly, consisting of a 4 1/2" Diameter Aluminum Pole with Powder Coated Black Finish provided by the same manufacturer of the RRFB unit, solar unit indications, Lithium Iron Phosphate Batteries, Sealed Lead Acid Batteries are not permitted. A separate controller cabinet will not be permitted. The RRFB unit must be self-contained.

Each RRFB will contain five rectangular indications, two on each side facing traffic, and one indication on the end facing pedestrians in the cross walk.

Functional Requirement:

Each RRFB when activated shall flash the two indications in an alternating "wig-wag" sequence (left light on, then right light on).

Each of the two indications shall have 70 to 80 periods of flashing per minute and shall have alternating but approximately equal periods of rapid pulsing light emissions and dark operation. During each of its 70 to 80 flashing periods per minute, one of the indications shall emit two rapid pulses of light and the other indication shall emit three rapid pulses of light.

Division 10 – Construction Specifications CDBG Manchester St/Concord St Crosswalks

The rapid flash rate of each indication, as applied over the full on-off sequence of a flashing period of the indication, shall not be between 5 and 30 flashes per second, to avoid frequencies that might cause seizures.

The light intensity shall meet the minimum specifications of Society of Automotive Engineers (SAE) standard Class 1 J595 (Directional Flashing Optical Warning Devices for Authorized Emergency, Maintenance, and Service Vehicles) dated January 2005.

Each RRFB indication will be activated by an ADA compliant pedestrian Pushbutton and operation will cease after a predetermined time limit (based on MUTCD procedures).

All RRFBs associated with a given crosswalk (including those with an advance crossing sign, if used) shall, when activated, simultaneously commence operation of their alternating rapid flashing indications and shall cease operation simultaneously.

Mechanical and Electrical Requirements:

Two sided/5 Whelen LEDs Amber TIR500


120VAC or Solar Power per requirement

Temperature: All components will be capable of continuous operation over a temperature range of -4 DEG. F to 165DEG. F

Indications:	Daylight distance visibility	>1000 feet
	Night distance visibility	>1 mile
	Flash Pattern	Wig-Wag
	Optics	Polycarbonate Lenses
	LED	Amber
	Body	Powder Coated Black
	Battery	Lithium Iron Phosphate (5 Year Battery Warranty)

Housing: RRFB unit must house: Controller, batteries and wireless equipment; an external enclosure will not be permitted; Batteries stored in solar panel housing will not be permitted.

Division 10 – Construction Specifications CDBG Manchester St/Concord St Crosswalks



*Numbers represent height, in inches, above ground level.

Construction Method:

Each RRFB indication will be mounted horizontally to an aluminum pedestal and in accordance with dimensions and details shown on the plan.

The two RRFB indications shall be aligned horizontally, with the longer dimension horizontal and with a minimum space between the two indications of approximately seven inches (7 in), measured from inside edge of one indication to inside edge of the other indication.

The outside edges of the RRFB indications, including any housing, shall not project beyond the outside edges of the sign.

Method of Measurements: This work will be measured as the number of RRFB systems furnished, installed and accepted in place.

Basis of Payment: This work will be paid for at the contract unit price of each "Rectangular Rapid Flashing Beacon System" of the type specified which will include the cost of footings, mounting pole, fittings, hardware, ground rod, armored ground cable, paint and all materials, equipment, tools and labor included thereto.